

LEASE NO. GS-11P-LVA00543**Warehouse Lease
GSA FORM L201WH (02/2020)**

This Lease is made and entered into between

Lorton GSA, LLC

(Lessor), whose principal place of business is 1 N. Wacker Drive, Suite 4025, Chicago, Illinois 60606-2807, and whose interest in the Property described herein is that of Fee Owner, and

The United States of America

(Government), acting by and through the designated representative of the General Services Administration (GSA), upon the terms and conditions set forth herein.

Witnesseth: The parties hereto, for the consideration hereinafter mentioned, covenant and agree as follows:

Lessor hereby leases to the Government the Premises described herein, being all or a portion of the Property located at

10555 Furnace Road, Lorton, Virginia 22079-2616

and more fully described in Section 1 and Exhibit A, together with rights to the use of parking and other areas as set forth herein, to be used for such purposes as determined by GSA.

LEASE TERM


To Have and To Hold the said Premises with its appurtenances for the term beginning **August 6, 2020**, and continuing for a period of

15 Years Firm,

subject to termination and renewal rights as may be hereinafter set forth.

In Witness Whereof, the parties to this Lease evidence their agreement to all terms and conditions set forth herein by their signatures below, to be effective as of the date of delivery of the fully executed Lease to the Lessor.

FOR THE LESSOR:


DocuSigned by:

D834E505999A470...
Name: Steve Riley
Title: Authorized Signatory
Entity: Lorton GSA, LLC
Date: 4/16/2021

FOR THE GOVERNMENT:

DocuSigned by:

C91D6C5999A5411...
Name: Joel T. Berelson
Title: Lease Contracting Officer
General Services Administration, Public Buildings Service
Date: 5/22/2021

WITNESSED FOR THE LESSOR BY:

DocuSigned by:

C5E00B5A233A488...
Name: Jeffrey Hurvitz
Title: Authorized Signatory
Date: 4/16/2021

The information collection requirements contained in this Solicitation/Contract, that are not required by the regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

SECTION 1 THE PREMISES, RENT, AND OTHER TERMS	5
1.01 THE PREMISES (WAREHOUSE) (OCT 2016)	5
1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)	5
1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.06 RENT AND OTHER CONSIDERATION (WAREHOUSE) (OCT 2019)	6
1.07 BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016)	7
1.08 TERMINATION RIGHTS (OCT 2016) INTENTIONALLY DELETED	8
1.09 RENEWAL RIGHTS (OCT 2016) INTENTIONALLY DELETED	8
1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2019)	8
1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)	8
1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016)	8
1.13 TENANT IMPROVEMENT FEE SCHEDULE (JUN 2012)	9
1.14 BUILDING SPECIFIC AMORTIZED CAPITAL (SEP 2012)	9
1.15 BUILDING SPECIFIC AMORTIZED CAPITAL RENTAL ADJUSTMENT (SEP 2013)	9
1.16 PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2018)	9
1.17 REAL ESTATE TAX BASE (SEP 2013) INTENTIONALLY DELETED	9
1.18 OPERATING COST BASE (OCT 2016)	9
1.19 RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)	9
1.20 HOURLY OVERTIME HVAC RATES (OCT 2016)	9
1.21 ADJUSTMENT FOR REDUCED SERVICES (OCT 2018) INTENTIONALLY DELETED	9
1.22 BUILDING IMPROVEMENTS (MAR 2016)	10
1.23 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAR 2012) INTENTIONALLY DELETED	10
1.24 LESSOR'S DUNS NUMBER (OCT 2017)	10
SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS	11
2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016)	11
2.02 AUTHORIZED REPRESENTATIVES (OCT 2016)	12
2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)	12
2.04 WAIVER OF RESTORATION (OCT 2018)	12
2.05 PAYMENT OF BROKER (JUL 2011)	12
2.06 CHANGE OF OWNERSHIP (OCT 2018)	12
2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012)	13
2.08 ADJUSTMENT FOR VACANT PREMISES (OCT 2017)	14
2.09 OPERATING COSTS ADJUSTMENT (JUN 2012)	14
2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)	15
2.11 RELOCATION ASSISTANCE ACT (APR 2011) INTENTIONALLY DELETED	15
SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS	16
3.01 LABOR STANDARDS (OCT 2016) INTENTIONALLY DELETED	16
3.02 WORK PERFORMANCE (JUN 2012)	16
3.03 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (OCT 2019)	16
3.04 CONSTRUCTION WASTE MANAGEMENT (OCT 2019)	16
3.05 WOOD PRODUCTS (OCT 2019)	16
3.06 ADHESIVES AND SEALANTS (OCT 2019)	16
3.07 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016)	17
3.08 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)	17
3.09 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)	17
3.10 VESTIBULES (APR 2011)	17
3.11 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)	17
3.12 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)	18
3.13 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)	18
3.14 ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016)	18
3.15 ELEVATORS (WAREHOUSE) (MAY 2014)	19
3.16 FLAGPOLE (SEP 2013)	19
3.17 DEMOLITION (JUN 2012)	19
3.18 ACCESSIBILITY (FEB 2007)	19
3.19 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)	20
3.20 DOORS: IDENTIFICATION (APR 2011)	20
3.21 WINDOWS (APR 2011)	20
3.22 PARTITIONS: GENERAL (OCT 2019)	20
3.23 PARTITIONS: PERMANENT (OCT 2019)	20
3.24 INSULATION: THERMAL, ACOUSTIC, AND HVAC (OCT 2019)	20
3.25 WALL FINISHES—SHELL (SEP 2015)	21
3.26 PAINTING—SHELL (OCT 2019)	21
3.27 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (OCT 2019)	21
3.28 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)	22

3.29	MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)	22
3.30	BUILDING SYSTEMS (APR 2011)	22
3.31	ELECTRICAL—SHELL (WAREHOUSE) (OCT 2019)	22
3.32	ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)	22
3.33	PLUMBING (JUN 2012)	22
3.34	DRINKING FOUNTAINS (WAREHOUSE) (OCT 2018)	22
3.35	RESTROOMS (WAREHOUSE) (OCT 2016)	23
3.36	PLUMBING FIXTURES: WATER CONSERVATION (OCT 2019)	23
3.37	JANITOR CLOSETS (SEP 2015)	23
3.38	HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2016)	24
3.39	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)	24
3.40	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)	24
3.41	LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2019)	25
3.42	ACOUSTICAL REQUIREMENTS (JUN 2012)	25
3.43	ENERGY EFFICIENCY AND CONSERVATION FOR NEW CONSTRUCTION (SEP 2010)	25
3.44	SECURITY FOR NEW CONSTRUCTION (OCT 2019)	26
3.45	SEISMIC SAFETY FOR NEW CONSTRUCTION (SEP 2012) INTENTIONALLY DELETED	26
3.46	FIRE PROTECTION FOR NEW CONSTRUCTION (WAREHOUSE) (MAY 2015)	26
3.47	INDOOR AIR QUALITY DURING CONSTRUCTION (OCT 2019)	26
3.48	SYSTEMS COMMISSIONING (APR 2011)	26
3.49	LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)	27
3.50	EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)	28
3.51	MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)	28
3.52	DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)	28
3.53	NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS – LEASE (SEP 2014) INTENTIONALLY DELETED	28

SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES.....29

4.01	SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2017)	29
4.02	CONSTRUCTION DOCUMENTS (SEP 2012)	29
4.03	TENANT IMPROVEMENTS PRICE PROPOSAL (OCT 2016)	30
4.04	BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2015)	30
4.05	GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2019)	30
4.06	CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)	31
4.07	PROGRESS REPORTS (JUN 2012)	31
4.08	ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)	31
4.09	CONSTRUCTION INSPECTIONS (SEP 2015)	31
4.10	ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (SEP 2015)	31
4.11	LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)	32
4.12	AS-BUILT DRAWINGS (OCT 2019)	32
4.13	LIQUIDATED DAMAGES (JUN 2012) INTENTIONALLY DELETED	32
4.14	SEISMIC RETROFIT (SEP 2013) INTENTIONALLY DELETED	32
4.15	LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)	32

SECTION 5 TENANT IMPROVEMENT COMPONENTS.....33

5.01	TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)	33
5.02	FINISH SELECTIONS (SEP 2015)	33
5.03	WINDOW COVERINGS (WAREHOUSE) (JUN 2012)	33
5.04	DOORS: SUITE ENTRY (OCT 2019)	33
5.05	DOORS: INTERIOR (OCT 2019)	33
5.06	DOORS: HARDWARE (SEP 2013)	33
5.07	DOORS: IDENTIFICATION (JUN 2012)	33
5.08	PARTITIONS: SUBDIVIDING (OCT 2019)	33
5.09	CEILINGS—TI (WAREHOUSE) (OCT 2019)	34
5.10	WALL FINISHES (OCT 2019)	34
5.11	PAINTING—TI (OCT 2019)	34
5.12	FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2019)	34
5.13	HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)	35
5.14	ELECTRICAL: DISTRIBUTION—TI (WAREHOUSE) (MAY 2014)	35
5.15	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)	35
5.16	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)	35
5.17	DATA DISTRIBUTION (JUN 2012)	36
5.18	ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)	36
5.19	LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)	36
5.20	LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)	37
5.21	AUTOMATIC FIRE SPRINKLER SYSTEM – TI (OCT 2016)	37

SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM.....38

6.01	PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)	38
6.02	UTILITIES (APR 2011)	38

6.03	UTILITY CONSUMPTION REPORTING (OCT 2016)	38
6.04	HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2018)	38
6.05	OVERTIME HVAC USAGE (OCT 2018)	39
6.06	JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)	39
6.07	SELECTION OF CLEANING PRODUCTS (OCT 2019)	40
6.08	SELECTION OF PAPER PRODUCTS (OCT 2019)	40
6.09	SNOW REMOVAL (WAREHOUSE) (MAY 2014)	40
6.10	MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)	40
6.11	MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016)	40
6.12	ASBESTOS ABATEMENT (APR 2011)	41
6.13	ONSITE LESSOR MANAGEMENT (APR 2011)	41
6.14	IDENTITY VERIFICATION OF PERSONNEL (OCT 2016)	41
6.15	SCHEDULE OF PERIODIC SERVICES (JUN 2012)	42
6.16	LANDSCAPING (OCT 2019)	42
6.17	LANDSCAPE MAINTENANCE (APR 2011)	42
6.18	RECYCLING—WAREHOUSE (MAY 2014)	42
6.19	RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)	42
6.20	SAFEGUARDING AND DISSEMINATION OF SENSITIVE BUT UNCLASSIFIED (SBU) BUILDING INFORMATION (FEB 2020)	42
6.21	INDOOR AIR QUALITY (OCT 2019)	43
6.22	RADON IN AIR (OCT 2016)	44
6.23	RADON IN WATER (JUN 2012)	44
6.24	HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)	44
6.25	MOLD (OCT 2018)	44
6.26	OCCUPANT EMERGENCY PLANS (SEP 2013)	45
6.27	FLAG DISPLAY (OCT 2016)	45
6.28	PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)	45
6.29	TRASH DUMPSTER SERVICE – LESSOR PROVIDED (WAREHOUSE) (OCT 2016)	45
6.30	ACCESS TO BUILDING INFORMATION (MAY 2014)	45

SECTION 7 ADDITIONAL TERMS AND CONDITIONS.....46

7.01	SECURITY REQUIREMENTS (OCT 2016)	46
7.02	MODIFIED LEASE PARAGRAPHS (OCT 2016)	46
7.03	ADDENDUM TO GSA FORM 3517B, GENERAL CLAUSES, NO FEDERALLY ELECTED OFFICIALS TO BENEFIT (OCT 2018)	
	INTENTIONALLY DELETED	46
7.04	SUPPLEMENTAL EQUIPMENT	46
7.05	ENHANCED ENGINEERING SERVICES	46
7.06	PROPERTY AND LEASED PREMISES CONDITION	46
7.07	RECONCILIATION PAYMENT	46
7.08	CONSTRUCTION SCHEDULE	47

SECTION 1 THE PREMISES, RENT, AND OTHER TERMS

1.01 THE PREMISES (WAREHOUSE) (OCT 2016)

The Premises are described as follows:

- A. Warehouse and Related Space: **89,317** rentable square feet yielding **82,827** ANSI/BOMA Office Area (ABOA) square feet (SF) of warehouse and office Space consisting of the entire Building, as depicted on the floor plan(s) attached hereto as Exhibit **A**.
- B. Common Area Factor: The Common Area Factor (CAF), defined under Section 2 of the Lease, is established as **7.84** percent. This factor, rounded to the nearest whole percentage, shall be used for purposes of rental adjustments in accordance with the Payment Clause of the General Clauses.

1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)

The Government shall have exclusive or non-exclusive (as identified) right to the use of Appurtenant Areas, and shall have the right to post Rules and Regulations Governing Conduct on Federal Property, Title 41, CFR, Part 102-74, Subpart C within such areas. The Government will coordinate with Lessor to ensure signage is consistent with Lessor's standards. Appurtenant to the Premises and included in the Lease are rights to use the following:

- A. Automobile Parking: **200** parking spaces for passenger vehicles as depicted on the plan attached hereto as Exhibit **C**, all of which shall be reserved for the exclusive use of the Government. All spaces must be secured and lit in accordance with the Security Requirements set forth in this Lease. There shall be no cost for parking.
- B. INTENTIONALLY DELETED
- C. Delivery Route:
- (1) At least one unobstructed route having no steps or abrupt changes in level shall connect with all accessible elements, spaces, buildings, and courses of passage. The minimum clear width of a route shall be 36 inches. If a route is less than 60 inches in width then it shall have level passing zones, spaced at no more than 200 feet apart, measuring a minimum of 60 inches by 60 inches.
 - (2) Objects projecting from walls with their leading edges between 27 and 80 inches above the finished floor shall protrude no more than 4 inches into an accessible route. Freestanding objects mounted on posts or pylons may overhang 12 inches maximum from 27 to 80 inches above the ground or the finished floor. Objects mounted with their leading edges at or below 27 inches above the finished floor may protrude any distance. However, no protruding objects shall reduce the clear width of an accessible route or maneuvering space. If vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches, a barrier to warn blind or visually impaired persons shall be provided.
 - (3) Mechanical rooms and spaces which are not normally frequented by the public or occupants and are not part of an accessible or emergency route are excepted and need not be accessible.
 - (4) Gratings in a route surface shall have spaces no wider than ½ inch in one direction and shall be placed so that the long dimension of openings is perpendicular to the dominant direction of travel.
- D. Delivery Ramps:
- (1) Any part of an accessible route with a slope greater than 1 foot rise in 20 feet shall be considered a ramp. Where ramps are necessary, they shall have a non-slip surface with a slope no greater than 1 foot rise in 12 feet. Ramps must have a minimum clear width of 3 feet with level landings at the top and bottom of each ramp run. Each landing shall be at least 5 feet in length and as wide as any ramp run leading into it. The maximum rise for any run shall be 30 inches. Intermediate landings for turning ramps shall measure a minimum of 5 feet by 5 feet.
 - (2) Lessor shall provide handrails complying with "HANDRAILS" (36 CFR 1191) on both sides of all ramps with a vertical rise greater than 6 inches. Ramps with drop-offs shall have curbs (minimum 2 inches high), walls, railings or projecting surfaces. Lessor shall provide curb ramps wherever an accessible route crosses a curb. Curb ramps shall not interfere with walks or vehicular traffic. The maximum slope of a curb ramp shall be a 1 inch rise per 12 inch run. The maximum length of a curb ramp shall be 6 feet with a minimum width of 36 inches, exclusive of flared sides. If no other alternative is feasible, accessible platform lifts may be used in lieu of a ramp or elevator. Lifts shall have accessible controls and clearances, shall comply with applicable safety regulations, and should facilitate unassisted entry and exit.
- E. Antennas, Satellite Dishes, and Related Transmission Devices:
- (1) Space located on the roof of the Building sufficient in size for the installation and placement of telecommunications equipment,
 - (2) the right to access the roof of the Building, and
 - (3) use of all Building areas (e.g., chases, plenums, etc.) necessary for the use, operation, and maintenance of such telecommunications equipment at all times during the term of this Lease.

Notwithstanding anything to the contrary in the Lease, the Government's right to affix security, communications equipment, and antennae or similar equipment to the roof, parapet or building envelope shall be at no additional rent to the Government, but shall be subject to Lessor's

consent (not to be unreasonably withheld, conditioned, or delayed). The Government shall not be permitted to modify the roof, or affix anything to the roof, where such action might void any roof warranties.

F. Loading Docks. See "LOADING DOCKS SHELL WAREHOUSE" paragraph in Section 3 of this Lease.

1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)

At a minimum, a truck turning radius sized for **standard sized tractor trailers** shall be provided and maintained at all times for all loading docks designed for such sized trucks. One-way design for service traffic is **preferred** in order to avoid the need for large turning areas.

1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)

A minimum of **63,117 ABOA SF** must have a clear ceiling height of **26 feet 0 inches**, measured from floor to the lowest obstruction, with the balance of the space maintaining a clear ceiling height of a minimum of **9 feet 3 inches**. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided.

1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)

The following minimum requirements apply to this Lease:

Lessor shall provide a minimum of one (1) vehicular repair garage with three (3) bays and overhead doors.

Bay Width: **12' 0"** (the distance from one side of the bay to the other side of the bay in linear feet and inches)

Bay Depth: **23' 0"** (the distance from the front of the bay to the back of the bay in linear feet and inches)

Column Spacing: Columns shall be **centerline to centerline**.

1.06 RENT AND OTHER CONSIDERATION (WAREHOUSE) (OCT 2019)

A. The Government shall pay the Lessor annual rent, payable in monthly installments in arrears, at the following rates:

	YEARS 1-5	YEARS 6-10	YEARS 11-15
	ANNUAL RENT	ANNUAL RENT	ANNUAL RENT
SHELL RENT ¹	(b) (4)		
OPERATING COSTS ²			
TENANT IMPROVEMENTS RENT ³			
BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) ⁴			
PARKING ⁵			
ROUTINE CLEANING & DISINFECTING SERVICES ⁶			
ENHANCED ENGINEERING SERVICES ⁷			
TOTAL ANNUAL RENT	\$2,932,338.54	\$3,021,796.55	\$3,110,972.54

(b) (4)

B. INTENTIONALLY DELETED

C. In accordance with the Lease negotiations, the Lessor has offered free rent to the Government for the first **six (6)** months of the Lease (net of Routine Cleaning & Disinfecting Services and Enhanced Engineering Services). Therefore, the first **six (6)** months of the Lease (net of Routine Cleaning & Disinfecting Services and Enhanced Engineering Services) shall be provided at no cost to the Government for a total value of (b) (4)

D. INTENTIONALLY DELETED

E. INTENTIONALLY DELETED

F. Rent is subject to adjustment based upon the final Tenant Improvement (TI) cost to be amortized in the rental rate, as agreed upon by the parties subsequent to the Lease Award Date.

G. If the Government occupies the Premises for less than a full calendar month, then rent shall be prorated based on the actual number of days of occupancy for that month.

H. Rent shall be paid to Lessor by electronic funds transfer in accordance with the provisions of the General Clauses. Rent shall be payable using the EFT information contained in the System for Award Management (SAM). In the event the EFT information changes, the Lessor shall be responsible for providing the updated information to SAM. Failure by the Lessor to maintain an active registration in SAM may result in delay of rental payments until such time as the SAM registration is activated.

I. Lessor shall provide to the Government, in exchange for the payment of rental and other specified consideration, the following:

1. The leasehold interest in the Property described herein in the paragraph entitled "The Premises."
2. All costs, expenses, and fees to perform the work required for acceptance of the Premises in accordance with this Lease, including all costs for labor, materials, and equipment, professional fees, contractor fees, attorney fees, permit fees, inspection fees, and similar such fees, and all related expenses;
3. Performance or satisfaction of all other obligations set forth in this Lease; and all services, utilities, and maintenance required for the proper operation of the Property, the Building, and the Premises in accordance with the terms of the Lease, including, but not limited to, all inspections, modifications, repairs, replacements, and improvements required to be made thereto to meet the requirements of this Lease.

J. For succeeding Leases with an incumbent Lessor where the Lease requires the Lessor to perform alterations using either the TIA or BSAC, the amortized tenant improvement rent and/or BSAC rent will not commence until the alterations are complete and accepted by the Government. Upon acceptance of these improvements, the Government will commence payment of the tenant improvement and/or BSAC rent as stipulated under the Lease, in addition to payment of the accrued tenant improvement and/or BSAC rent for the period of time where such rent was withheld (such accrued rent will not include any additional interest). Additionally, in the event the Government does not use all the TIA or BSAC, then the accrued amount will be adjusted in accordance with the provisions of the Lease (e.g., de-amortization).

K. The Lessor shall provide routine cleaning and disinfecting services, as outlined under sub-paragraph O of the paragraph entitled "Janitorial Services", (b) (4). The routine cleaning and disinfecting services rent will not commence and is not effective until the Lease Award Date. The Government shall not be charged for these services, and Lessor shall not be required to provide these services, for the period between the Lease Term Commencement Date and the Lease Award Date. The Government reserves the right to issue notice to unilaterally cancel the routine cleaning and disinfecting at any time during the Lease term and, in such a case, the rental rate will be reduced by this amount. This reduction shall occur after the Government gives 30 calendar days notice to the Lessor and shall continue in effect until the Lease expires or is terminated.

L. The Lessor shall provide the Government with Enhanced Engineering Services, as outlined in section 7.05. The base cost of these services is (b) (4) payable in monthly installments of (b) (4). This amount is subject to an annual increase of (b) (4) per year, commencing with the second lease year, as outlined below.

Lease Year	Effective Dates	Annual	Monthly
1	August 6, 2020 – August 5, 2021	\$97,416.96	(b) (4)
2	August 6, 2021 – August 5, 2022	\$100,339.47	(b) (4)
3	August 6, 2022 – August 5, 2023	\$103,349.65	(b) (4)
4	August 6, 2023 – August 5, 2024	\$106,450.14	(b) (4)
5	August 6, 2024 – August 5, 2025	\$109,643.65	(b) (4)
6	August 6, 2025 – August 5, 2026	\$112,932.96	(b) (4)
7	August 6, 2026 – August 5, 2027	\$116,320.94	(b) (4)
8	August 6, 2027 – August 5, 2028	\$119,810.57	(b) (4)
9	August 6, 2028 – August 5, 2029	\$123,404.89	(b) (4)
10	August 6, 2029 – August 5, 2030	\$127,107.04	(b) (4)
11	August 6, 2030 – August 5, 2031	\$130,920.25	(b) (4)
12	August 6, 2031 – August 5, 2032	\$134,847.86	(b) (4)
13	August 6, 2032 – August 5, 2033	\$138,893.29	(b) (4)
14	August 6, 2033 – August 5, 2034	\$143,060.09	(b) (4)
15	August 6, 2034 – August 5, 2035	\$147,351.89	(b) (4)

1.07 BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016)

A. CBRE, Inc. (Broker) is the authorized real estate Broker representing GSA in connection with this Lease transaction. The total amount of the Commission is (b) (4) and is earned upon Lease execution, payable according to the Commission Agreement signed between the Lessor and Broker. Only (b) (4) of the Commission will be payable to CBRE Inc. with the remaining (b) (4), which is the Commission Credit, to be credited to the shell rental portion of the annual rental payments due and owing to fully recapture this Commission Credit. The reduction in shell rent

shall commence with the first month of the rental payments and continue until the credit has been fully recaptured in equal monthly installments over the shortest time practicable.

B. Notwithstanding the "Rent and Other Consideration" paragraph of this Lease, the shell rental payments due and owing under this Lease shall be reduced to recapture fully this Commission Credit. The reduction in shell rent shall commence with the first month of the rental payments and continue as indicated in this schedule for adjusted Monthly Rent:

Month 7 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 7th Month's Rent.*

Month 8 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 8th Month's Rent.*

Month 9 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 9th Month's Rent.*

Month 10 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 10th Month's Rent.*

Month 11 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 11th Month's Rent.*

Month 12 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 12th Month's Rent.*

Month 13 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 13th Month's Rent.*

Month 14 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 14th Month's Rent.*

* Subject to change based on adjustments outlined under the paragraph "Rent and Other Consideration."

1.08 ~~TERMINATION RIGHTS (OCT 2016)~~ INTENTIONALLY DELETED

1.09 ~~RENEWAL RIGHTS (OCT 2016)~~ INTENTIONALLY DELETED

1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2019)

The following documents are attached to and made part of the Lease:

DOCUMENT NAME	NO. OF PAGES	EXHIBIT
FLOOR PLANS	5	A
SITE PLANS	5	B
PARKING PLAN & NARRATIVE	2	C
AGENCY SPECIAL REQUIREMENTS	13	D
SECURITY REQUIREMENTS, LEVEL III	11	E
GSA FORM 1217, LESSOR'S ANNUAL COST STATEMENT	2	F
GSA FORM 3517B GENERAL CLAUSES	17	G
List of Shell and Tenant Improvements	2	H

1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)

The Tenant Improvement Allowance (TIA) for purposes of this Lease is (b) (4). The TIA is the amount that the Lessor shall make available for the Government to be used for TIs. This amount is amortized in the rent over the Firm Term of this Lease at an annual interest rate of 0 percent.

1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016)

A. The Government, at its sole discretion, shall make all decisions as to the use of the TIA. The Government may use all or part of the TIA. The Government may return to the Lessor any unused portion of the TIA in exchange for a decrease in rent according to the agreed-upon amortization rate over the Firm Term.

B. The Government may elect to make lump sum payments for any or all work covered by the TIA. That part of the TIA amortized in the rent shall be reduced accordingly. At any time after occupancy and during the Firm Term of the Lease, the Government, at its sole discretion, may elect to pay lump sum for any part or all of the remaining unpaid amortized balance of the TIA. If the Government elects to make a lump sum payment for the TIA after occupancy, the payment of the TIA by the Government will result in a decrease in the rent according to the amortization rate over the Firm Term of the Lease.

C. If it is anticipated that the Government will spend more than the identified TIA, the Government may elect to:

1. Reduce the TI requirements;
2. Pay lump sum for the overage upon substantial completion in accordance with the "Acceptance of Space and Certificate of Occupancy" paragraph;
3. Negotiate an increase in the rent.

1.13 TENANT IMPROVEMENT FEE SCHEDULE (JUN 2012)

For pricing TI costs, the following rates shall apply for the initial build-out of the Space.

	INITIAL BUILD-OUT
ARCHITECT/ENGINEER FEES (% OF TI CONSTRUCTION COSTS)	(b) (4)
LESSOR'S PROJECT MANAGEMENT FEE (% OF TI CONSTRUCTION COSTS)	

1.14 BUILDING SPECIFIC AMORTIZED CAPITAL (SEP 2012)

For purposes of this Lease, the Building Specific Amortized Capital (BSAC) is (b) (4). The Lessor will make the total BSAC amount available to the Government, which will use the funds for security related improvements. This amount is amortized in the rent over the Firm Term of this lease at an annual interest rate of 0 percent.

1.15 BUILDING SPECIFIC AMORTIZED CAPITAL RENTAL ADJUSTMENT (SEP 2013)

A. The Government, at its sole discretion, shall make all decisions about the use of the Building Specific Amortized Capital (BSAC). The Government may use all or part of the BSAC. The Government may return to the Lessor any unused portion of the BSAC in exchange for a decrease in rent (where applicable) according to the agreed-upon amortization rate over the Firm Term.

B. The Government may elect to make lump-sum payments for any work covered by the BSAC. The part of the BSAC amortized in the rent shall be reduced accordingly. At any time after occupancy and during the Firm Term of the Lease, the Government, at its sole discretion, may elect to pay a lump sum for any part or all of the remaining unpaid amortized balance of the BSAC. If the Government elects to make a lump-sum payment for the BSAC after occupancy, the payment of the BSAC by the Government will result in a decrease in the rent according to the amortization rate over the Firm Term of the Lease.

C. If it is anticipated that the Government will spend more than the BSAC identified above, the Government may elect to:

1. Reduce the security countermeasure requirements;
2. Pay a lump sum for the amount overage upon substantial completion in accordance with the "Acceptance of Space and Certificate of Occupancy" paragraph; or
3. Negotiate an increase in the rent.

1.16 PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2018)

A. As of the Lease Award Date, the Government's Percentage of Occupancy, as defined in the "Real Estate Tax Adjustment" paragraph of this Lease is 100 percent. The Percentage of Occupancy is derived by dividing the total Government Space of 89,317 RSF by the total Building space of 89,317 RSF. The tax parcel number is 1133 01 0005E.

B. All relevant tax adjustment documentation (e.g. copies of paid tax receipts, invoices) must be submitted online via the GSA Real Estate Tax Portal at [RET.GSA.GOV](https://ret.gsa.gov).

1.17 ~~REAL ESTATE TAX BASE (SEP 2013)~~ INTENTIONALLY DELETED**1.18 OPERATING COST BASE (OCT 2016)**

The parties agree, for the purpose of applying the paragraph titled "Operating Costs Adjustment," that the Lessor's base rate for operating costs shall be (b) (4).

1.19 RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)

In accordance with the paragraph entitled "Adjustment for Vacant Premises," if the Government fails to occupy or vacates the entire or any portion of the Premises prior to expiration of the term of the Lease, the operating costs paid by the Government as part of the rent shall be reduced by \$2.19 per ABOA SF of Space vacated by the Government.

1.20 HOURLY OVERTIME HVAC RATES (OCT 2016)

The following rate shall apply in the application of the paragraph titled "Overtime HVAC Usage":

- \$40.00 per hour for the entire Space.

1.21 ~~ADJUSTMENT FOR REDUCED SERVICES (OCT 2018)~~ INTENTIONALLY DELETED

1.22 BUILDING IMPROVEMENTS (MAR 2016)

A. Within one year of lease award, the Lessor shall either earn an ENERGY STAR Label or complete (or provide verification of recent completion) the following energy-related Building improvements:

1. Replacement of all interior lighting with LED fixtures;
2. Replacement of all parking lot lighting with LED fixtures;
3. Replacement of two original R-22 rooftop HVAC units with new, more efficient R-410A units with high efficiency gas heat burners; and
4. Roof replacement with improved membrane, improving R value. For clarification, Lessor will apply a 15-year, zero VOC roof membrane overlay system. This system will not require removal of the current roofing materials nor will it require demolition and replacement of the roof decking.

B. In coordination with the Government, the Lessor shall increase the parking capacity of the Building, as outlined in Exhibit C.

C. In coordination with the Government's tenant improvements, the Lessor shall complete the shell improvements listed in Exhibit H.

1.23 ~~HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAR 2012)~~ INTENTIONALLY DELETED

1.24 LESSOR'S DUNS NUMBER (OCT 2017)

Lessor's Dun & Bradstreet DUNS Number: **079232345**.

SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS

2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016)

Unless otherwise specifically noted, all terms and conditions set forth in this Lease shall be interpreted by reference to the following definitions, standards, and formulas:

- A. Appurtenant Areas. Appurtenant Areas are defined as those areas and facilities on the Property that are not located within the Premises, but for which rights are expressly granted under this Lease, or for which rights to use are reasonably necessary or reasonably anticipated with respect to the Government's enjoyment of the Premises and express appurtenant rights (such as parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease).
- B. Broker. If GSA awarded this Lease using a contract real estate broker, Broker shall refer to GSA's broker.
- C. Building. Building(s) situated on the Property in which the Premises are located.
- D. Commission Credit. If GSA awarded this Lease using a Broker, and the Broker agreed to forego a percentage of its commission to which it is entitled in connection with the award of this Lease, the amount of this credit is referred to as the "Commission Credit."
- E. Common Area Factor. The "Common Area Factor" (CAF) is a conversion factor determined by the Building owner and applied by the owner to the ABOA SF to determine the RSF for the leased Space. The CAF is expressed as a percentage of the difference between the amount of rentable SF and ABOA SF, divided by the ABOA SF. For example 11,500 RSF and 10,000 ABOA SF will have a CAF of 15% [(11,500 RSF - 10,000 ABOA SF)/10,000 ABOA SF]. For the purposes of this Lease, the CAF shall be determined in accordance with the applicable ANSI/ BOMA standard for the type of space to which the CAF shall apply.
- F. Contract. "Contract" shall mean this Lease.
- G. Contractor. "Contractor" shall mean Lessor.
- H. Days. All references to "day" or "days" in this Lease shall mean calendar days, unless specified otherwise.
- I. FAR. All references to the FAR shall be understood to mean the Federal Acquisition Regulation, codified at 48 CFR Chapter 1.
- J. Firm Term/Non-Firm Term. The Firm Term is that part of the Lease term that is not subject to termination rights. The Non-Firm Term is that part of the Lease term following the end of the Firm Term.
- K. GSAR. All references to the GSAR shall be understood to mean the GSA supplement to the FAR, codified at 48 CFR Chapter 5.
- L. Lease Term Commencement Date. The date on which the lease term commences.
- M. Lease Award Date. The date the LCO executes the Lease and mails or otherwise furnishes written notification of the executed Lease to the successful Offeror (date on which the parties' obligations under the Lease begin).
- N. Premises. Defined as the total Warehouse Area, Office Area, and other type of Space, together with all associated common areas, described in Section 1 of this Lease, and delineated by plan in the attached exhibit. Parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease are not included in the Premises.
- O. Property. Defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas, wareyards, loading docks, aprons, loading ramps) to which the Government is granted rights.
- P. Racking System Plan—A plan that at a minimum must include clear ceiling height requirement(s), aisle width(s), shelving depth(s) and type of material(s) to be stored . In addition such Plan shall identify locations and dimensions of storage of materials in packed piles, on pallets, in racks, or on shelves.
- Q. Rentable Space or Rentable Square Feet (RSF). Rentable Space is the area for which a tenant is charged rent. It is determined by the Building owner and may vary by city or by building within the same city. The Rentable Space may include a share of Building support/common areas such as elevator lobbies, Building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The Rentable Space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts. Rentable Square Feet is calculated using the following formula for each type of Space (e.g., office, warehouse, etc.) included in the Premises: ABOA SF of Space x (1 + CAF) = RSF.
- R. Space. The Space shall refer to that part of the Premises to which the Government has exclusive use, such as Office Area, or other type of Space. Parking areas, wareyards, loading docks, aprons, loading ramps to which the Government has rights under this Lease are not included in the Space.
- S. Warehouse and office space. For the purposes of this Lease, Space shall be measured in accordance with the standard (Z65.1-1996) provided by American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) for Office Area, which means "the area

where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed." References to ABOA mean ANSI/BOMA Office Area.

T. Working Days. Working Days shall mean weekdays, excluding Saturdays and Sundays and Federal holidays.

2.02 AUTHORIZED REPRESENTATIVES (OCT 2016)

Signatories to this Lease shall have full authority to bind their respective principals with regard to all matters relating to this Lease. No other persons shall be understood to have any authority to bind their respective principals, except to the extent that such authority may be explicitly delegated by notice to the other party, or to the extent that such authority is transferred by succession of interest. The Government shall have the right to substitute its Lease Contracting Officer (LCO) by notice, without an express delegation by the prior LCO.

2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)

A. The Government may request the Lessor to provide alterations during the term of the Lease. Alterations will be ordered by issuance of a Lease Amendment, GSA Form 300, Order for Supplies or Services, or a tenant agency-approved form when specifically authorized to do so by the LCO. The General Services Administration Acquisition Manual ("GSAM") clause, 552.270-31, Prompt Payment, including its invoice requirements, shall apply to orders for alterations. All orders are subject to the terms and conditions of this Lease and may be placed by the LCO or a warranted contracting officer's representative (COR) in GSA or the tenant agency when specifically authorized to do so by the LCO, subject to the threshold limitation below. With respect to alterations which affect the Building structure or systems, the Government shall obtain the prior written consent of Lessor thereto (which consent shall not be unreasonably withheld, conditioned or delayed).

B. Orders for alterations issued by an authorized COR are limited to no more than \$250,000 (LCOs are not subject to this threshold). This threshold will change according to future adjustments of the simplified acquisition threshold (see FAR 2.101). The LCO will provide the Lessor with a list of tenant agency officials authorized to place orders and will specify any limitations on the authority delegated to tenant agency officials. The tenant agency officials are not authorized to deal with the Lessor on any other matters.

C. Payments for alterations ordered by the tenant agency under the authorization described in sub-paragraph B will be made directly by the tenant agency placing the order.

2.04 WAIVER OF RESTORATION (OCT 2018)

Lessor shall have no right to require the Government to restore the Premises upon expiration or earlier termination (full or partial) of the Lease, and waives all claims against the Government for waste, damages, or restoration arising from or related to (a) the Government's normal and customary use of the Premises during the term of the Lease (including any extensions thereof), as well as (b) any initial or subsequent alteration to the Premises regardless of whether such alterations are performed by the Lessor or by the Government. At its sole option, the Government may abandon property in the Space following expiration or earlier termination (full or partial) of the Lease, in which case the property will become the property of the Lessor and the Government will be relieved of any liability in connection therewith.

2.05 PAYMENT OF BROKER (JUL 2011)

If GSA awarded the Lease through its Broker, the Lessor shall pay GSA's Broker its portion of the commission one half upon Lease award and the remaining half upon acceptance of the Space. "Its portion of the commission" means the agreed-upon commission to GSA's Broker minus the Commission Credit specified in the Lease or Lease Amendment.

2.06 CHANGE OF OWNERSHIP (OCT 2018)

A. If during the term of the Lease, title to the Property is transferred, the Lease is assigned, or the Lessor changes its legal name, the Lessor and its successor shall comply with the requirements of FAR Subpart 42.12. If title is transferred, the Lessor shall notify the Government within five days of the transfer of title.

B. The Government and the Lessor may execute a Change of Name Agreement if the Lessor is changing only its legal name, and the Government's and the Lessor's respective rights and obligations remain unaffected. A sample form is found at FAR 42.1205.

C. If title to the Property is transferred, or the Lease is assigned, the Government, the original Lessor (Transferor), and the new owner or assignee (Transferee) shall execute a Novation Agreement providing for the transfer of Transferor's rights and obligations under the Lease to the Transferee. When executed on behalf of the Government, a Novation Agreement will be made part of the Lease via Lease Amendment.

D. In addition to all documents required by FAR 42.1204, the LCO may request additional information (e.g., copy of the deed, bill of sale, certificate of merger, contract, court decree, articles of incorporation, operation agreement, partnership certificate of good standing, etc.) from the Transferor or Transferee to verify the parties' representations regarding the transfer, and to determine whether the transfer of the Lease is in the Government's interest.

E. If the LCO determines that recognizing the Transferee as the Lessor will not be in the Government's interest, the Transferor shall remain fully liable to the Government for the Transferee's performance of obligations under the Lease, notwithstanding the transfer. Under no condition shall the Government be obligated to release the Transferor of obligations prior to (a) the rent commencement date; and (b) any amounts due and owing to the Government under the Lease have been paid in full or completely set off against the rental payments due under the Lease.

F. As a condition for being recognized as the Lessor and entitlement to receiving rent, the Transferee must register in the System for Award Management (SAM) for purposes of "All Awards" (See FAR 52.232-33), and complete all required representations and certifications within SAM. In addition, the Transferee must also complete a Foreign Ownership and Financing Representation.

G. If title to the Property is transferred, or the Lease is assigned, rent shall continue to be paid to the original Lessor, subject to the Government's rights as provided for in this Lease. The Government's obligation to pay rent to the Transferee shall not commence until the Government has received all information reasonably required by the LCO under sub-paragraph D, the Government has determined that recognizing the Transferee as the Lessor is in the Government's interest (which determination will be prompt and not unreasonably withheld), and the Transferee has met all conditions specified in sub-paragraph F.

2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012)

A. Purpose: This paragraph provides for adjustment in the rent (tax adjustment) to account for increases or decreases in Real Estate Taxes for the Property after the establishment of the Real Estate Tax Base, as those terms are defined herein. Tax adjustments shall be calculated in accordance with this paragraph.

B. Definitions: The following definitions apply to the use of the terms within this paragraph:

Property is defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas to which the Government is granted rights).

Real Estate Taxes are those taxes that are levied upon the owners of real property by a Taxing Authority (as hereinafter defined) of a state or local Government on an ad valorem basis to raise general revenue for funding the provision of government services. The term excludes, without limitation, special assessments for specific purposes, assessments for business improvement districts, and/or community development assessments.

Taxing Authority is a state, commonwealth, territory, county, city, parish, or political subdivision thereof, authorized by law to levy, assess, and collect Real Estate Taxes.

Tax Year refers to the 12-month period adopted by a Taxing Authority as its fiscal year for assessing Real Estate Taxes on an annual basis.

Tax Abatement is an authorized reduction in the Lessor's liability for Real Estate Taxes below that determined by applying the generally applicable real estate tax rate to the Fully Assessed (as hereinafter defined) valuation of the Property.

Unadjusted Real Estate Taxes are the full amount of Real Estate Taxes that would be assessed for the Property for one full Tax Year without regard to the Lessor's entitlement to any Tax Abatements (except if such Tax Abatement came into effect after the date of award of the Lease), and not including any late charges, interest or penalties. If a Tax Abatement comes into effect after the date of award of the Lease, "unadjusted Real Estate Taxes" are the full amount of Real Estate Taxes assessed for the Property for one full Tax Year, less the amount of such Tax Abatement, and not including any late charges, interest, or penalties.

Real Estate Tax Base is the unadjusted Real Estate Taxes for the first full Tax Year following the commencement of the Lease term. If the Real Estate Taxes for that Tax Year are not based upon a Full Assessment of the Property, then the Real Estate Tax Base shall be the Unadjusted Real Estate Taxes for the Property for the first full Tax Year for which the Real Estate Taxes are based upon a Full Assessment. Such first full Tax Year may be hereinafter referred to as the Tax Base Year.

The Property is deemed to be Fully Assessed (and Real Estate Taxes are deemed to be based on a Full Assessment) only when a Taxing Authority has, for the purpose of determining the Lessor's liability for Real Estate Taxes, determined a value for the Property taking into account the value of all improvements contemplated for the Property pursuant to the Lease, and issued to the Lessor a tax bill or other notice of levy wherein the Real Estate Taxes for the full Tax Year are based upon such Full Assessment. At no time prior to the issuance of such a bill or notice shall the Property be deemed Fully Assessed.

Percentage of Occupancy refers to that portion of the Property exclusively occupied or used by the Government pursuant to the Lease. For Buildings, the Percentage of Occupancy is determined by calculating the ratio of the RSF occupied by the Government pursuant to the Lease to the total RSF in the Building or Buildings so occupied, and shall not take into account the Government's ancillary rights including, but not limited to, parking or roof space for antennas (unless facilities for such ancillary rights are separately assessed). This percentage shall be subject to adjustment to take into account increases or decreases for Space leased by the Government or for rentable space on the Property.

C. Adjustment for changes in Real Estate Taxes. After the Property is Fully Assessed, the Government shall pay its share of any increases and shall receive its share of any decreases in the Real Estate Taxes for the Property, such share of increases or decreases to be referred to herein as "tax adjustment." The amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base, less the portion of such difference not paid due to a Tax Abatement (except if a Tax Abatement comes into effect after the date of award of the Lease). If a Tax Abatement comes into effect after the date of award of the Lease, the amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base. The Government shall pay the tax adjustment in a single annual lump sum payment to the Lessor. In the event that this tax adjustment results in a credit owed to the Government, the Government may elect to receive payment in the form of a rental credit or lump sum payment.

If the Property contains more than one separately assessed parcel, then more than one tax adjustment shall be determined based upon the Percentage of Occupancy, Real Estate Tax Base, and Real Estate Taxes for each respective parcel.

After commencement of the Lease term, the Lessor shall provide to the LCO copies of all real estate tax bills for the Property, all documentation of Tax Abatements, credits, or refunds, if any, and all notices which may affect the assessed valuation of the Property, for the Tax Year prior to the commencement of the Lease Term, and all such documentation for every year following. Lessor acknowledges that the LCO shall rely on the completeness and accuracy of these submissions in order to establish the Real Estate Tax Base and to determine tax adjustments. The LCO may memorialize the establishment of the Real Estate Tax Base by issuing a unilateral administrative lease amendment indicating the base year, the amount of the Real Estate Tax Base, and the Government's Percentage of Occupancy.

The Real Estate Tax Base is subject to adjustment when increases or decreases to Real Estate Taxes in any Tax Year are attributable to (a) improvements or renovations to the Property not required by this Lease, or (b) changes in net operating income for the Property not derived from this Lease. If either condition results in a change to the Real Estate Taxes, the LCO may re-establish the Real Estate Tax Base as the Unadjusted Real Estate Taxes for the Tax Year the Property is reassessed under such condition, less the amount by which the Unadjusted Real Estate Taxes for the Tax Year prior to reassessment exceeds the prior Real Estate Tax Base.

If this Lease includes any options to renew the term of the Lease, or be otherwise extended, the Real Estate Tax Base for determining tax adjustments during the renewal term or extension shall be the last Real Estate Tax Base established during the base term of the Lease.

If any Real Estate Taxes for the Property are retroactively reduced by a Taxing Authority during the term of the Lease, the Government shall be entitled to a proportional share of any tax refunds to which the Lessor is entitled, calculated in accordance with this Paragraph. Lessor acknowledges that it has an affirmative duty to disclose to the Government any decreases in the Real Estate Taxes paid for the Property during the term of the Lease. Lessor shall annually provide to the LCO all relevant tax records for determining whether a tax adjustment is due, irrespective of whether it seeks an adjustment in any Tax Year.

If the Lease terminates before the end of a Tax Year, or if rent has been suspended, payment for the real estate tax increase due because of this section for the Tax Year will be prorated based on the number of days that the Lease and the rent were in effect. Any credit due the Government after the expiration or earlier termination of the Lease shall be made by a lump sum payment to the Government or as a rental credit to any succeeding Lease, as determined in the LCO's sole discretion. Lessor shall remit any lump sum payment to the Government within 15 calendar days of payment or credit by the Taxing Authority to Lessor or Lessor's designee. If the credit due to the Government is not paid by the due date, interest shall accrue on the late payment at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978, as amended (41 USC § 611), that is in effect on the day after the due date. The interest penalty shall accrue daily on the amount of the credit and shall be compounded in 30-day increments inclusive from the first day after the due date through the payment date. The Government shall have the right to pursue the outstanding balance of any tax credit using all such collection methods as are available to the United States to collect debts. Such collection rights shall survive the expiration of this Lease.

In order to obtain a tax adjustment, the Lessor shall furnish the LCO with copies of all paid tax receipts, or other similar evidence of payment acceptable to the LCO, and a proper invoice (as described in GSA Form 3517, General Clauses, 552.270-31, Prompt Payment) for the requested tax adjustment, including the calculation thereof. All such documents must be received by the LCO within 60 calendar days after the last date the real estate tax payment is due from the Lessor to the Taxing Authority without payment of penalty or interest. FAILURE TO SUBMIT THE PROPER INVOICE AND EVIDENCE OF PAYMENT WITHIN SUCH TIME FRAME SHALL CONSTITUTE A WAIVER OF THE LESSOR'S RIGHT TO RECEIVE A TAX ADJUSTMENT PURSUANT TO THIS PARAGRAPH FOR THE TAX YEAR AFFECTED.

Tax Appeals. If the Government occupies more than 50 percent of the Building by virtue of this and any other Government Lease(s), the Government may, upon reasonable notice, direct the Lessor to initiate a tax appeal, or the Government may elect to contest the assessed valuation on its own behalf or jointly on behalf of Government and the Lessor. If the Government elects to contest the assessed valuation on its own behalf or on behalf of the Government and the Lessor, the Lessor shall cooperate fully with this effort, including, without limitation, furnishing to the Government information necessary to contest the assessed valuation in accordance with the filing requirements of the Taxing Authority, executing documents, providing documentary and testimonial evidence, and verifying the accuracy and completeness of records. If the Lessor initiates an appeal at the direction of the Government, the Government shall have the right to approve the selection of counsel who shall represent the Lessor with regard to such appeal, which approval shall not be unreasonably withheld, conditioned or delayed, and the Lessor shall be entitled to a credit in the amount of its reasonable expenses in pursuing the appeal.

2.08 ADJUSTMENT FOR VACANT PREMISES (OCT 2017)

A. If the Government fails to occupy any portion of the leased Premises or vacates the Premises in whole or in part prior to expiration of the term of the Lease, the rental rate and the base for operating cost adjustments will be reduced using the figure specified in the "Rate for Adjustment for Vacant Leased Premises" paragraph of this Lease.

B. If no rate reduction has been established in this Lease, the rate will be reduced by that portion of the costs per ABOA SF of operating expenses not required to maintain the Space.

C. Said reduction shall occur after the Government gives 30 calendar days' prior notice to the Lessor and shall continue in effect until the Government occupies the vacant Premises or the Lease expires or is terminated.

2.09 OPERATING COSTS ADJUSTMENT (JUN 2012)

A. Beginning with the second year of the Lease and each year thereafter, the Government shall pay annual incremental adjusted rent for changes in costs for cleaning services, supplies, materials, maintenance, trash removal, landscaping, water, sewer charges, heating, electricity, and certain administrative expenses attributable to occupancy.

B. The amount of adjustment will be determined by multiplying the base rate by the annual percent of change in the Cost of Living Index. The percent change will be computed by comparing the index figure published for the month prior to the Lease Term Commencement Date with the index figure published for the month prior which begins each successive 12-month period. For example, a Lease which commences in June of 2005 would use the index published for May of 2005, and that figure would be compared with the index published for May of 2006, May of 2007, and so on, to determine the percent change. The Cost of Living Index will be measured by the Department of Labor revised Consumer Price Index for Urban Wage Earners and Clerical Workers (CPI-W), U.S. city average, all items, (1982 to 1984 = 100) published by the Bureau of Labor Statistics. Payment will be made with the monthly installment of fixed rent. Rental adjustments will be effective on the anniversary date of the Lease; however, payment of the adjusted rental rate will become due on the first workday of the second month following the publication of the Cost of Living Index for the month prior to the commencement of each 12-month period.

C. In the event of any decreases in the Cost of Living Index occurring during the term of the occupancy under the Lease, the rental amount will be reduced accordingly. The amount of such reductions will be determined in the same manner as increases in rent provided under this paragraph.

D. If the Government exercises an option to extend the Lease term at the same rate as that of the original term, the option price will be based on the adjustment during the original term. Annual adjustments will continue.

2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)

A. If the Lessor is a HUBZone small business concern (SBC) that did not waive the price evaluation preference, the Lessor shall provide a certification within 10 days after Lease award to the LCO (or representative designated by the LCO) that the Lessor was an eligible HUBZone SBC on the date of award. If it is determined within 20 days after award that a HUBZone SBC Offeror that has been awarded the Lease was not an eligible HUBZone SBC at the time of award, and the HUBZone SBC Lessor failed to provide the LCO with information regarding a change to its HUBZone eligibility prior to award, then the Lease shall be subject, at the LCO's discretion, to termination, and the Government will be relieved of all obligations to the Lessor in such an event and not be liable to the Lessor for any costs, claims or damages of any nature whatsoever.

B. Within **20** days after Lease award, the Lessor shall provide to the LCO (or representative designated by the LCO) evidence of:

1. A firm commitment of funds in an amount sufficient to perform the work.
2. The names of at least two proposed construction contractors, as well as evidence of the contractors' experience, competency, and performance capabilities with construction similar in scope to that which is required herein.
3. The license or certification to practice in the state where the Building is located from the individual(s) and/or firm(s) providing architectural and engineering design services.

C. The Government shall have the right to withhold approval of design intent drawings (DIDs) until the conditions specified in sub-paragraphs A and B have been satisfied.

D. Within ten (10) calendar days after the LCO issues the Notice To Proceed (NTP) for TI construction, the Lessor shall provide to the LCO evidence of:

1. Award of a construction contract for TIs with a firm completion date. This date must be in accordance with the construction schedule for TIs as described in the "Schedule for Completion of Space" paragraph of this Lease.
2. Issuance of required permits for construction of the TIs.

2.11 ~~RELOCATION ASSISTANCE ACT (APR 2011)~~ INTENTIONALLY DELETED

SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS

3.01 LABOR STANDARDS (OCT 2016) INTENTIONALLY DELETED

3.02 WORK PERFORMANCE (JUN 2012)

All work in performance of this Lease shall be done by skilled workers or mechanics and shall be acceptable to the LCO. The LCO may reject the Lessor's workers 1) if such are unlicensed, unskilled, or otherwise incompetent, or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other government or private contracts.

3.03 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (OCT 2019)

A. Items and materials existing in the Premises, or to be removed from the Premises during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in refurbished condition and shall meet the quality standards set forth by the Government in this Lease. In the absence of definitive quality standards, the Lessor is responsible to confirm that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.

B. Unless waived by the LCO, the Lessor shall submit a reuse plan for leases 10,000 RSF or greater. The Government will not pay for existing fixtures and other TIs accepted in place. However, the Government will reimburse the Lessor, as part of the TIA, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the LCO.

3.04 CONSTRUCTION WASTE MANAGEMENT (OCT 2019)

A. For leases 10,000 RSF or greater, recycling construction waste is mandatory for initial space alterations for TIs and subsequent alterations under the Lease.

B. SUBMITTAL REQUIREMENT: Prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the LCO, may permit alternative means of disposal.

C. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility: Ceiling grid and tile, light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bulbs, duct work and HVAC equipment, wiring and electrical equipment, aluminum and/or steel doors and frames, hardware, drywall, steel studs, carpet, carpet backing, and carpet padding, wood, insulation, cardboard packaging, pallets, windows and glazing materials, all miscellaneous metals (as in steel support frames for filing equipment), and all other finish and construction materials.

D. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCBs) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with Federal and state laws and requirements concerning hazardous waste.

E. In addition to providing "one time" removal and recycling of large scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.

F. Construction materials recycling records shall be maintained by the Lessor and shall be accessible to the LCO. Records shall include materials recycled or land-filled, quantity, date, and identification of hazardous wastes.

3.05 WOOD PRODUCTS (OCT 2019)

A. Particle board, strawboard, and plywood materials used shall be free of formaldehyde or sufficiently aged prior to use such that indoor air levels in the finished leased space shall not exceed 0.016 parts per million (ppm) of formaldehyde.

B. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

C. For leases 10,000 RSF or greater, new installations of wood products shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at [HTTP://WWW.WOOD-DATABASE.COM/WOOD-ARTICLES/RESTRICTED-AND-ENDANGERED-WOOD-SPECIES/](http://www.wood-database.com/wood-articles/restricted-and-endangered-wood-species/) or <https://www.fws.gov/international/plants/current-cites-listings-of-tree-species.html>. In addition, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Stewardship Council United States ([HTTPS://US.FSC.ORG/EN-US](https://us.fsc.org/en-us)), or the Sustainable Forestry Initiative ([HTTP://WWW.SFIPROGRAM.ORG/](http://www.sfiprogram.org/)).

3.06 ADHESIVES AND SEALANTS (OCT 2019)

A. All adhesives employed (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no heavy metals and that do not result in indoor air levels above 0.016 parts per million (ppm) of formaldehyde. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

B. For leases 10,000 RSF or greater the Lessor is encouraged to use applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement) and <https://sftool.gov/greenprocurement/green-products/8/miscellaneous/1238/adhesives/0>

3.07 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016)

A. The Building Shell shall be designed, constructed, and maintained in accordance with the standards set forth herein and completed prior to acceptance of Space. For pricing, fulfillment of all requirements not specifically designated as TIs, Building Specific Amortized Capital, Operating Costs, or other rent components as indicated shall be deemed included in the Shell Rent.

B. Base structure and Building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and service areas, shall be complete. Restrooms shall be complete and operational with an adequate number of fixtures for men and women to meet current local codes based on building occupancy and use. All newly installed Building shell components, including but not limited to, heating and ventilation, electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with TIs. Circulation corridors are provided as part of the base Building only on multi-tenanted buildings where the corridor is common to more than one tenant. In single tenant buildings, only the fire egress corridor(s) necessary to meet code is provided as part of the shell.

C. The Building Shell rental rate shall also include, but is not limited to, costs included listed under Section II of GSA Form 1217, Lessor's Annual Cost Statement, including insurance, taxes, lease commission and management, in addition to profit, reserve costs and loan financing for the Building.

3.08 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)

A. The Lessor shall be responsible for the professional quality, technical accuracy, and the coordination of all designs, drawings, specifications, and other services furnished by the Lessor under this contract. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services.

B. THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Government retains the right to review and approve many aspects of the Lessor's design, including without limitation, review of the Lessor's design and construction drawings, shop drawings, product data, finish samples, and completed base building and TI construction. Such review and approval is intended to identify potential design flaws, to minimize costly misdirection of effort, and to assist the Lessor in its effort to monitor whether such design and construction comply with applicable laws and satisfy all Lease requirements.

C. Neither the Government's review, approval or acceptance of, nor payment through rent of the services required under this contract, shall be construed to operate as a waiver of any rights under this contract or of any cause of action arising out of the performance of this contract, and the Lessor shall be and remain liable to the Government in accordance with applicable law for all damages to the Government caused by the Lessor's negligent performance of any of the services required under this Lease.

D. Design and construction and performance information is contained throughout several of the documents which comprise this Lease. The Lessor shall provide to space planners, architects, engineers, construction contractors, etc., all information required whether it is found in this Lease, special requirements and attachments, price lists, or design intent drawings. Reliance upon one of these documents to the exclusion of any other may result in an incomplete understanding of the scope of the work to be performed and/or services to be provided.

3.09 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)

The Building in which the leased Space is located shall be designed, built, and maintained in good condition, suitable for Lessee's use at all times, and in accordance with the requirements of this Lease.

3.10 VESTIBULES (APR 2011)

A. Vestibules shall be provided at public entrances and exits wherever weather conditions and heat loss are important factors for consideration. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure.

B. The Lessor shall provide permanent entryway systems (such as grilles or grates) to control dirt and particulates from entering the Building at all primary exterior entryways.

3.11 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)

A. Prior to occupancy, the Premises and any parking garage areas shall meet or will be upgraded to meet, either the applicable egress requirements in the National Fire Protection Association, Life Safety Code (NFPA 101), or the International Code Council, International Building Code (IBC), each current as of the Lease Award Date, or use an alternative approach or method that achieves an equivalent level of safety deemed acceptable by the Government.

B. The Space shall have unrestricted access to a minimum of two remote exits on each floor of Government occupancy.

C. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the IBC.

3.12 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)

A. Any portion of the space located below-grade, including parking garage areas, and all areas in a building referred to as "hazardous areas" (defined in National Fire Protection Association (NFPA) 101) that are located within the entire Building (including non-Government areas) shall be protected by an automatic fire sprinkler system.

B. The entire warehouse building shall be protected throughout by an automatic fire sprinkler system(s) when the offered space exceeds 10,000 rentable square feet in area.

C. Automatic fire sprinkler system(s) shall be installed in accordance with the requirements of NFPA 13, Standard for the Installation of Sprinkler Systems that was in effect on the actual date of installation.

D. Automatic fire sprinkler system(s) shall be maintained in accordance with the requirements of NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-based Fire Protection Systems (current as of the Lease Award Date).

3.13 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)

A. A Building-wide fire alarm system shall be installed when the offered Space exceeds 40,000 square feet of RSF.

B. The fire alarm system shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code that was in effect on the actual date of installation.

C. Fire alarm systems shall be maintained in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date).

D. The fire alarm system shall transmit all fire alarm signals to the local fire department via any of the following means: directly to the local fire department, to the (911) public communications center, to a central station, to a remote supervising station, or to a proprietary supervising station.

E. If the Building's fire alarm control unit is over 25 years old as of the date of award of this Lease, Lessor shall install a new fire alarm system in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date), prior to Government acceptance and occupancy of the Space.

3.14 ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016)

A. Energy-related Requirements:

1. The Energy Independence and Security Act (EISA) establishes the following requirements for Government leases in Buildings that have not earned the ENERGY STAR® Label conferred by the Environmental Protection Agency (EPA) within one year prior to the due date for final proposal revisions ("most recent year").

2. If this Lease was awarded under any of EISA's Section 435 statutory exceptions, the Lessor shall either:

a. Earn the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding Lease); or

b. (i) Complete energy efficiency and conservation improvements if any, agreed to by Lessor in lieu of earning the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding lease); and

(ii) Obtain and publicly disclose the Building's current ENERGY STAR® score (using EPA's Portfolio Manager tool), unless the Lessor cannot access whole building utility consumption data, or there is no building category within Portfolio Manager to benchmark against, including spaces—

I. That are located in States with privacy laws that provide that utilities shall not provide such aggregated information to multitenant building owners; and

II. For which tenants do not provide energy consumption information to the commercial building owner in response to a request from the building owner. (A Federal agency that is a tenant of the space shall provide to the building owner, or authorize the owner to obtain from the utility, the energy consumption information of the space for the benchmarking and disclosure required by this subparagraph D).

III. That cannot be benchmarked (scored) using EPA's Portfolio Manager tool because of excessive vacancy; in which case Lessor agrees to obtain the score and publicly disclose it within 120 days of the eligibility to obtain a score using the EPA Portfolio Manager tool.

Note: "public disclosure" means posting the Energy Star® score on state or local websites in those areas that have applicable disclosure mandates, and reporting the score to the Government via Portfolio Manager. In the absence of an applicable state or local disclosure mandate, Lessor shall either generate and display the Energy Star® score in a public space at the building location or post the score on Lessor's or Lessor's Parent/Affiliate website.

3. If this Lease was awarded to a Building to be built or to a Building predominantly vacant as of the due date for final proposal revisions and was unable to earn the ENERGY STAR® label for the most recent year (as defined above) due to insufficient occupancy, but was able to demonstrate

sufficient evidence of capability to earn the ENERGY STAR® label, then Lessor must earn the ENERGY STAR® label within 18 months after occupancy by the Government.

4. The Lessor is encouraged to purchase at least 50 percent of the Government tenant's electricity from renewable sources.

B. Hydrology-related Requirements:

1. Per EISA Section 438, the sponsor of any development or redevelopment project involving a Federal facility with a footprint that exceeds 5,000 square feet shall use site planning, design, construction, and maintenance strategies for the property to maintain or restore, to the maximum extent technically feasible, the predevelopment hydrology of the Property with regard to the temperature, rate, volume, and duration of flow. If the Lessor proposes to satisfy the Government's space requirements through a development or redevelopment project, and the Government will be the sole or predominant tenant such that any other use of the Property will be functionally or quantitatively incidental to the Government's use, the Lessor is required to implement hydrology maintenance and restoration requirements as required by EISA Section 438.

a. For the purposes of applying EISA Section 438 in this Lease, "sponsor" shall mean "Lessor", and "exceeds 5,000 square feet" shall mean construction that disturbs 5,000 square feet or more of land area at the Property or on adjoining property to accommodate the Government's requirements, or at the Property for whatever reason. Information regarding implementation of the hydrology maintenance and restoration requirements can be found at: <http://www.epa.gov/greeningepa/technical-guidance-implementing-stormwater-runoff-requirements-federal-projects>

b. Lessor is required to implement these hydrology maintenance and restoration requirements to the maximum extent technically feasible, prior to acceptance of the Space, (or not later than one year after the Lease Award Date or Lease Term Commencement Date, whichever is later, of a succeeding or superseding lease). Additionally, this Lease requires EISA Section 438 storm water compliance not later than one year from the date of any applicable disturbance (as defined in EISA Section 438) of more than 5,000 square feet of ground area if such disturbance occurs during the term of the Lease if the Government is Government is the sole or predominant tenant. In the event the Lessor is required to comply with EISA Section 438, Lessor shall furnish the Government, prior to the filing for permits for the associated work, with a certification from Lessor's engineer that the design meets the hydrology maintenance and restoration requirements of EISA Section 438.

3.15 ELEVATORS (WAREHOUSE) (MAY 2014)

A. Lessor shall provide suitable passenger elevator and, when required by Government, freight elevator service to any portion of the Premises not having ground level access. Service shall be available during the normal hours of operation specified in this Lease. However, one passenger elevator and, when required by Government, one freight elevator shall be available at all times for Government use. When a freight elevator is required by the Government, it shall be accessible to the loading areas. When possible, Lessor shall provide Government with 24-hour advance notice if the service is to be interrupted for more than 1-1/2 hours. Lessor shall schedule normal service interruption outside of the Government's normal working hours. Lessor shall also use best efforts to minimize the frequency and duration of unscheduled interruptions.

B. Code: Elevators shall conform to the current requirements of the American Society of Mechanical Engineers ASME A17.1/CSA B44, Safety Code for Elevators and Escalators (current as of the Lease Award Date). Elevators shall be provided with Phase I emergency recall operation and Phase II emergency in-car operation in accordance with ASME A17.1/CSA B44. Fire alarm initiating devices (e.g., smoke detectors) used to initiate Phase I emergency recall operation shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (actual date of installation). The elevators shall be inspected and maintained in accordance with the current edition of the ASME A17.2, Inspector's Manual for Elevators. Except for the reference to ASME A17.1 in ABAAS, Section F105.2.2, all elevators must meet ABAAS requirements for accessibility in Sections 407, 408, and 409 of ABAAS.

C. Safety Systems: Elevators shall be equipped with telephones or other two-way emergency communication systems. The system used shall be marked and shall reach an emergency communication location staffed 24 hours per day, 7 days per week.

D. Speed: The passenger elevators shall have a capacity to transport in 5 minutes 15 percent of the normal population of all upper floors (based on 150 SF per person). Further, the dispatch interval between elevators during the up-peak demand period shall not exceed 35 seconds.

E. Interior Finishes: Passenger elevator cab walls must present a quality image and be sufficiently durable to withstand heavy use. Materials must be installed on removable panels or other replaceable devices to facilitate maintenance and renewal of finishes and shall be subject to approval by the LCO. Ceilings must be replaceable. In passenger elevators recessed down lights or indirect fixtures should be used. Passenger elevator cab floors shall be approved by the LCO and shall be carpet, wood, or high-quality resilient flooring materials. If carpet, use materials with low pile height and high density, and otherwise conform to the requirements of this lease, including sustainability requirements. Finishes for freight elevators must be very durable and easy to clean. Stainless steel walls and doors are preferred. Flooring must be sheet vinyl or resilient vinyl tile. Ceiling light fixtures must be recessed and protected from possible damage.

3.16 FLAGPOLE (SEP 2013)

If the Government is the sole occupant of the Building, a flagpole shall be provided at a location to be approved by the LCO. The flag of the United States of America will be provided by the Lessor, as part of shell rent and replaced at all times during the Lease term when showing signs of wear.

3.17 DEMOLITION (JUN 2012)

The Lessor shall remove existing abandoned electric, telephone, and data cabling and devices, as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

3.18 ACCESSIBILITY (FEB 2007)

The Building, leased Space, and areas serving the leased Space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

3.19 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)

- A. Exterior Building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to TIs.
- B. Exterior doors shall be weather tight and shall open outward. Hinges, pivots, and pins shall be installed in a manner which prevents removal when the door is closed and locked. These doors shall have a minimum clear opening of 32" clear wide x 80" high (per leaf). Doors shall be heavy duty, flush, (1) hollow steel construction, (2) solid core wood, or (3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be fully insulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall be of durable finish and shall have an aesthetically pleasing appearance acceptable to the LCO. The opening dimensions and operations shall conform to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements. Fire door assemblies shall be listed and labeled. Labels on fire door assemblies shall be maintained in a legible condition. Fire door assemblies and their accompanying hardware, including frames and closing devices shall be installed in accordance with the requirements of NFPA 80, Standard for Fire Doors and Other Opening Protectives. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the International Building Code (IBC) as of the Award Date of this Lease.
- C. Exterior doors and all common area doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall or floor mounted) and silencers. All public use doors and restroom doors shall be equipped with kick plates. All doors shall have automatic door closers. All Building exterior doors shall have locking devices installed to reasonably deter unauthorized entry. The Lessor is encouraged to avoid the use of chrome-plated hardware.
- D. There shall be unrestrictive access to a minimum of two remote exits on each floor of the Government's occupancy.
- E. Loading docks shall have a roll-up coiling type door with lock.

3.20 DOORS: IDENTIFICATION (APR 2011)

All signage required in common areas unrelated to tenant identification shall be provided and installed by the Lessor.

3.21 WINDOWS (APR 2011)

- A. Office Space shall have windows in each exterior bay unless waived by the LCO.
- B. All windows shall be weather tight. Operable windows that open shall be equipped with locks. Off-street, ground-level windows and those accessible from adjacent roofs, fire escapes, and other structures that can be opened must be fitted with a sturdy locking device. Windows accessible from fire escapes must be readily operable from the inside of the Building.

3.22 PARTITIONS: GENERAL (OCT 2019)

- A. Partitions in public areas shall be marble, granite, hardwood, or drywall covered with durable wall covering or high performance coating, or equivalent pre-approved by the LCO.
- B. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building, the Lessor is encouraged to use materials for newly installed gypsum board meeting the applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False>.

3.23 PARTITIONS: PERMANENT (OCT 2019)

- A. Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor as part of shell rent as necessary to surround the Space, stairs, corridors, elevator shafts, restrooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by the applicable building code, fire code and ordinances adopted by the jurisdiction in which the Building is located (such as the International Building Code, etc.) current as of the Lease Award Date.
- B. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building, the Lessor is encouraged to use materials for newly installed gypsum board meeting applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False>.

3.24 INSULATION: THERMAL, ACOUSTIC, AND HVAC (OCT 2019)

- A. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFCs), nor shall CFCs be used in the installation of the product.
- B. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.

C. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.

D. All insulation shall contain low emitting volatiles and not result in indoor air levels above 0.016 parts per million (ppm) of formaldehyde..

E. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the Lease Award Date) adopted by the jurisdiction in which the Building is located.

F. For leases 10,000 RSF or greater, all insulation products shall meet applicable, statutory environmentally preferable criteria related to recovered material content as outlined in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/1/construction-materials/22/building-insulation/0) and <https://sftool.gov/greenprocurement/green-products/1/construction-materials/22/building-insulation/0>.

3.25 WALL FINISHES—SHELL (SEP 2015)

A. All restrooms within the Building common areas of Government-occupied floors shall have 1) ceramic tile, recycled glass tile, or comparable wainscot from the finished floor to a minimum height of 4'-6" and 2) semigloss paint on remaining wall areas, or other finish approved by the Government.

B. All elevator areas that access the Space and hallways accessing the Space shall be covered with wall coverings not less than 20 ounces per square yard, high performance paint, or an equivalent.

3.26 PAINTING—SHELL (OCT 2019)

A. The Lessor shall bear the expense for all painting associated with the Building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Space shall be spackled and prime painted.. If any Building shell areas are already painted prior to TIs, then the Lessor shall repaint, at the Lessor's expense, as necessary during TIs.

B. The costs for cyclical painting requirements as outlined in Section 6 shall be included in the shell rent.

C. For leases 10,000 RSF or greater, primer shall meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False>.

3.27 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (OCT 2019)

A. All adjoining floor areas shall be of a common level, and meet ASTM Standard E1155, with a minimum levelness of **Ff35** and **FL25**. Warehouse areas shall have a minimum live load capacity of **180 pounds per square foot**. The Government may require Lessor to provide written certification of the floor load capacity, at no cost to the Government, by a registered Professional Engineer. The Government may also require calculations and structural drawings at no cost to the Government, by a registered Professional Engineer.

B. Warehouse floor surfacing shall have the appropriate surface performance for the operations being performed as outlined in the following table and as verified with in situ testing. The appropriate surface performance shall be maintained throughout the life of the lease term. Periodic in situ testing shall be performed at a frequency appropriate for the expected useful life of the floor attribute required to be maintained:

	DUTY	APPLICATION	PERFORMANCE
a. Special	Unique requirements	One or more of the following attributes 1. Very heavy-duty operational or equipment traffic 2. Unique surface reflectance criteria 3. Anti slip/ anti skid 4. Chemical resistance 5. Anti static 6. Critical free movement floor 7. Critical defined movement floor 8. Critical dust control 9. Joint free	In addition to the Class 1-3 below Note: should one or more of the application attributes be critical for the performance of the required operation seek specialized help in tailoring the appropriate requirements)
b. Class 1	Very High Abrasion, steel wheel traffic and impact	Heavy-duty duty impact from pallets/ skid steer forks	<.1mm abrasion resistance Maintenance free joints
c. Class 2	High-abrasion steel wheel or hard wheel traffic	Medium—	<.3 mm abrasion resistance Maintenance free joints
d. Class 3	light abrasion—rubber tire and foot traffic	Light-duty	Dust free finish

- b. Floor Hardeners, or coatings shall be utilized to achieve the wear performance for the appropriate duty class required in the above table. Coatings, such as polyurethanes membranes are only acceptable for class 3. Should hardeners be required then nano-lithium silicates or other environmentally friendly practices must be employed.
- c. In situ abrasion resistance required of class 2 or 3 shall be determined in accordance with BS EN 13892-4: 2002

3.28 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)

- A. Exposed interior floors in primary entrances and lobbies shall be marble, granite, or terrazzo. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, or terrazzo. Resilient flooring shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble, or carpet base.
- B. Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all restroom and service areas of Government-occupied floors.
- C. Any alternate flooring must be pre-approved by the LCO
- D. The costs for cyclical carpet replacement requirements as outlined in Section 6 shall be included in the shell rent.

3.29 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)

The Lessor shall provide and operate all Building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in the office Space.

3.30 BUILDING SYSTEMS (APR 2011)

Whenever requested, the Lessor shall furnish to GSA as part of shell rent, a report by a registered professional engineer(s) showing that the Building and its systems as designed and constructed will satisfy the requirements of this Lease.

3.31 ELECTRICAL—SHELL (WAREHOUSE) (OCT 2019)

A. The Lessor shall be responsible for meeting the applicable requirements of local codes and ordinances. When codes conflict, the more stringent standard shall apply. The electrical panel supplying electrical service to the warehouse Space shall be located in an enclosed room. The enclosed room should only contain electrical infrastructure and not used for any other purpose. The enclosure must be located within the warehouse Space to be leased and not serve other non-leased facilities. The enclosure shall have door(s) fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch. The electrical distribution panels enclosed in the electrical room shall include: single-phase 120/240 volt service or 3-phase 120/208 volt for leased spaces under 10,000 RSF; 3-phase 120/208 volt service for leased spaces between 10,000 and 25,000 RSF; and 3-phase 277/480 volt and 3-phase 120/208 volt service for leased spaces over 25,000 RSF. A minimum of **150** amps at 120/240 volts per **4,000** rentable square feet of leased Space inclusive of lighting circuits (but assuming no air conditioning mechanical load) shall be provided to circuit breaker panel boxes in the Space.. All switchgear, fuses, and circuit breakers shall be plainly marked or labeled to identify circuits and/or equipment supplied through them. All office Space shall have , 4-wire with bond, 60 hertz electric service available. In no event shall such power distribution (not including lighting and HVAC) for the office Space fall below 4 watts per ABOA SF of Office area. Lessor must provide one watt per ABOA SF for electrical power distribution for warehouse areas.

B. Main power distribution switchboards and distribution and lighting panel boards shall be circuit breaker type with copper buses that are properly rated to provide the calculated fault circuits. All power distribution panel boards shall be supplied with separate equipment ground buses. All power distribution equipment shall be required to handle the actual specified and projected loads and 10 percent spare load capacity. Distribution panels are required to accommodate circuit breakers for the actual calculated needs and 10 percent spare circuits that will be equivalent to the majority of other circuit breakers in the panel system. Fuses and circuit breakers shall be plainly marked or labeled to identify circuits or equipment supplied through them.

C. Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent. The Lessor shall provide duplex utility outlets in restrooms, corridors, and dispensing areas.

3.32 ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)

If the Government pays separately for electricity, no more than 500 SF of office Space may be controlled by one switch or automatic light control for all office Space on the Government meter, whether through a building automation system, time clock, occupant sensor, or other comparable system acceptable to the LCO.

3.33 PLUMBING (JUN 2012)

The Lessor shall include the cost of plumbing in common areas. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for TIs, shall be included in the shell rent.

3.34 DRINKING FOUNTAINS (WAREHOUSE) (OCT 2018)

Lessor shall provide at least one chilled water fountain for the Premises. If more than one fountain is required by local building codes based on general warehouse use of the premises, they also shall be provided by Lessor as part of the shell rental. The fountains shall comply with Section F211 of the Architectural Barriers Act Accessibility Standard. Potable is defined as water meeting current EPA primary drinking water standards or more stringent,

applicable state or local regulations. The Lessor shall serve as first responder to any occupant complaints about drinking water. The Lessor shall promptly investigate any such complaints and implement the necessary controls to address the complaints and maintain potable water conditions.

3.35 RESTROOMS (WAREHOUSE) (OCT 2016)

A. For Warehouse Area, Lessor shall provide at its cost, restroom facilities which are handicap accessible, with an adequate number of fixtures for men and women to meet current local codes based on general warehousing use.

B. For Office Area within the Warehouse Building, if this Lease is satisfied by new construction or major alterations, Lessor shall provide water closets, sinks and urinals on each floor that is partially or fully occupied by the government per the following schedule. The schedule is per floor and based on a density of one person for each 135 ABOA SF, allocated as 50% women and 50% men. If major alterations to the restrooms occur during the term of this Lease, the number of fixtures then must meet the schedule as part of the major alterations.

ESTIMATED NUMBER OF EACH GENDER PER FLOOR			(WOMEN'S) WATER CLOSETS	(WOMEN'S) SINKS	(MEN'S) WATER CLOSETS	(MEN'S) URINALS	(MEN'S) SINKS
1	to	8	2	1	1	1	1
9	to	24	3	2	2	1	1
25	to	36	3	2	2	1	2
37	to	56	5	3	3	2	2
57	to	75	6	4	4	2	2
76	to	96	6	5	4	2	3
97	to	119	7	5	5	2	3
120	to	134	9	5	6	3	4
Above 135			3/40	1/24	1/20	1/40	1/30

C. If no new construction or major renovation of a restroom is occurring, compliance with local code is sufficient. Separate restroom facilities for men and women shall be provided in accordance with local code or ordinances, on each floor occupied by the Government in the Building. The facilities shall be located so that employees will not be required to travel more than 200 feet on one floor to reach the restrooms. Each restroom shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.

D. Each main restroom shall contain the following:

1. A mirror and shelf above the lavatory.
2. A toilet paper dispenser in each water closet stall that will hold at least two rolls and allow easy, unrestricted dispensing.
3. A coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories.
4. At least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories.
5. A coin-operated sanitary napkin dispenser in women's restrooms with a waste receptacle in each water closet stall.
6. A disposable toilet seat cover dispenser.
7. A counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground-fault interrupter-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
8. A floor drain.
9. For new installations and major renovations, restroom partitions shall be made from recovered materials as listed in EPA's CPG.
10. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour. The exhaust fan systems shall be provided with a 24/7 seven day clock to allow programming.

3.36 PLUMBING FIXTURES: WATER CONSERVATION (OCT 2019)

For leases 10,000 RSF or greater, the specifications listed below apply:

1. New installations of plumbing fixtures,
2. Replacement of existing plumbing fixtures, or
3. Existing non-conforming fixtures where the Government occupies the full floor.

A. Water closets must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized.

B. Urinals must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized. Waterless urinals are acceptable.

C. Faucets must conform to EPA WaterSense or fixtures with equivalent flow rates must be utilized.

Information on EPA WaterSense fixtures can be found at [HTTPS://WWW3.EPA.GOV/WATERSENSE/](https://www3.epa.gov/watersense/).

3.37 JANITOR CLOSETS (SEP 2015)

Janitor closets shall meet all local codes and ordinances. When not addressed by local code, Lessor shall provide containment drains plumbed for appropriate disposal of liquid wastes in spaces where water and chemical concentrate mixing occurs for maintenance purposes. Disposal is not permitted in restrooms.

3.38 HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2016)

A. Warehouse areas: Temperature control for all warehouse areas shall be provided by ceiling mounted heating equipment capable of maintaining a minimum temperature of 55 degrees Fahrenheit (with all doors closed) throughout the warehouse area during the heating season regardless of the outside temperature. Unit heaters shall be controlled by individual thermostats mounted in the area of the unit heaters, or controlled from a central master time clock of the 7-day type with a separate manual override switch (12 hours) or other automatic means to permit setback of temperature at night and on weekends. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative. Central air rotation units will be acceptable if loading dock areas are equipped with unit heaters for direct heating over doors. In the warehouse area, unit heaters shall be mounted tight to the ceiling for maximum headroom. Lessor shall provide ventilation/air circulation in accordance with [the latest version of ASHRAE 62.1].

B. Office Areas: Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all Building common areas. The Lessor shall provide conditioned air through medium pressure duct work at a rate of .75 cubic feet per minute per ABOA SF and systems shall be designed with sufficient systems capacity to meet all requirements in this Lease.

C. Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.

D. Equipment Performance. Temperature control for office Spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain Space temperature control over a range of internal load fluctuations of plus 0.5 W/SF to minus 1.5 W/SF from initial design requirements of the tenant.

E. Ductwork Re-use and Cleaning. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.

F. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of the American National Standards Institute, American Society of Heating, Refrigeration and Air-Conditioning Engineers (ANSI/ASHRAE) Standard 62.1, Ventilation for Acceptable Indoor Air Quality.

G. Heating and air-conditioning air distribution systems (air handling units, VAV boxes, fan coil units, etc.) for the Space shall be equipped with particulate matter air filters that meet the Minimum Efficiency Reporting Value (MERV) specified in the current edition of ANSI/ASHRAE Standard 62.1. Locations that do not meet the EPA National Ambient Air Quality Standards (NAAQS) for particulates (PM 10 or PM 2.5) must be equipped with additional filtration on outdoor air intakes as required in ANSI/ASHRAE Standard 62.1. NAAQS information can be found at [HTTPS://WWW.EPA.GOV/GREEN-BOOK](https://www.epa.gov/green-book).

H. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour.

I. Where the Lessor proposes that the Government shall pay utilities, the following shall apply:

1. An automatic air or water economizer cycle shall be provided to all air handling equipment, and
2. The Building shall have a fully functional building automation system capable of control, regulation, and monitoring of all environmental conditioning equipment. The building automation system shall be fully supported by a service and maintenance contract.

J. Warehouse and Office areas: HVAC systems must conform to the locally approved building code.

3.39 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)

A. Sufficient space shall be provided on the floor(s) where the Government occupies Space for the purposes of terminating telecommunications service into the Building. The Building's telecommunications closets located on all floors shall be vertically-stacked. Telecommunications switch rooms, wire closets, and related spaces shall be enclosed. The enclosure shall not be used for storage or other purposes and shall have door(s) fitted with an automatic door-closer and deadlocking latch bolt with a minimum throw of 1/2 inch. The telephone closets shall include a telephone backboard.

B. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable Telecommunications Industry Association (TIA) and Electronic Industries Alliance (EIA) standards. These standards include the following:

1. TIA/EIA-568, Commercial Building Telecommunications Cabling Standard,
2. TIA/EIA 569, Commercial Building Standard for Telecommunications Pathways and Spaces,
3. TIA/EIA-570, Residential and Light Commercial Telecommunications Wiring Standard, and
4. TIA/EIA-607, Commercial Building Grounding and Bonding Requirements for Telecommunications Standard.

C. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable NFPA standards. Bonding and grounding shall be in accordance with NFPA Standard 70, National Electrical Code, and other applicable NFPA standards and/or local code requirements.

3.40 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)

A. The Government may elect to contract its own telecommunications (voice, data, video, Internet or other emerging technologies) service in the Space. The Government may contract with one or more parties to have INS wiring (or other transmission medium) and telecommunications equipment installed.

B. The Lessor shall allow the Government's designated telecommunications provider's access to utilize existing Building wiring to connect its services to the Government's Space. If the existing Building wiring is insufficient to handle the transmission requirements of the Government's designated telecommunications providers, the Lessor shall provide access from the point of entry into the Building to the Government's floor Space, subject to any inherent limitations in the pathway involved.

C. The Lessor shall allow the Government's designated telecommunications providers to affix telecommunications antennas (high frequency, mobile, microwave, satellite, or other emerging technologies), subject to weight and wind load conditions, to roof, parapet, or Building envelope as required. Access from the antennas to the Premises shall be provided.

D. The Lessor shall allow the Government's designated telecommunications providers to affix antennas and transmission devices throughout the Space and in appropriate common areas frequented by the Government's employees to allow the use of cellular telephones and communications devices necessary to conduct business.

3.41 LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2019)

Warehouse/Storage Space & Overall:

A. Lessor shall provide a minimum lighting level of 10 foot-candles, as measured 30 inches above the floor, in aisles and open storage areas in the warehouse Space with the storage racks full. Lessor shall provide a minimum lighting level in the shipping and receiving areas of 30 foot-candles, when measured 30 inches above the floor. Lessor must provide lighting that is equivalent to the energy efficiency requirements in any office areas. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all non-office areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided as part of Shell Rent in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.

B. Occupancy Sensors: The Lessor shall provide ceiling mount occupancy sensors (over aisles and open areas), or scheduling controls through a building automation system (BAS) throughout the storage portion of the Space in order to reduce the hours that the lights are on when a particular area is unoccupied. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

C. Building Perimeter:

1. Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels, (especially at loading dock doors), shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 foot-candles for transition areas and at least 1 foot-candle at the surface throughout the parking lot. Wareyards (storage yards) require a minimum lighting level of 5 foot-candles (at ground level). Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 15:1 and a maximum to average uniformity ratio of 4:1.
2. If the leased space is 100 percent occupied by Government tenants, all exterior parking lot fixtures, including those illuminating a wareyard, shall be "Dark Sky" compliant with no property line trespass.

D. Parking Structures: The minimum illuminance level for parking structures is 5 foot-candle as measured on the floor with a uniformity ratio of 10:1.

E. Parking Sensors: If the leased space is 100 percent occupied by Government tenants, exterior parking area and parking structure lighting shall be sensor or BAS controlled in order that it may be programmed to produce reduced lighting levels during non use. This non-use time period will normally be from 11:00 pm to 6:00 am.

F. Exterior Power Backup: Exterior egress, walkway, parking lot, and parking structure lighting must have emergency power backup to provide for safe evacuation of the Building.

3.42 ACOUSTICAL REQUIREMENTS (JUN 2012)

A. Reverberation Control. Private office and conference rooms using suspended acoustical ceilings shall have a noise reduction coefficient (NRC) of not less than 0.65 in accordance with ASTM C-423. Open office using suspended acoustical ceilings shall have an NRC of not less than 0.75. Private offices, conference rooms, and open offices using acoustical cloud or acoustical wall panels with a minimum of 70% coverage shall have an NRC of not less than 0.85.

B. Ambient Noise Control. Ambient noise from mechanical equipment shall not exceed noise criteria curve (NC) 35 in accordance with the ASHRAE Handbook of Fundamentals in offices and conference rooms; NC 40 in corridors, cafeterias, lobbies, and toilets; NC 50 in other spaces.

C. Noise Isolation. Rooms separated from adjacent spaces by ceiling high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

Conference rooms: NIC 40
Offices: NIC 35

D. Testing. The LCO may require, at Lessor's expense, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.

3.43 ENERGY EFFICIENCY AND CONSERVATION FOR NEW CONSTRUCTION (SEP 2010)

A. All new construction shall achieve an Energy Star Label within 18 months after occupancy by the Government.

B. To earn the Energy Star Label, a Building owner or representative must follow the instructions on the Energy Star Web site at <http://www.energystar.eslabel>.

C. The Lessor is encouraged to purchase at least 50 percent of the Government tenant's electricity from renewable sources.

3.44 SECURITY FOR NEW CONSTRUCTION (OCT 2019)

The Lessor shall provide a written certification from a licensed professional engineer that the Building conforms to a minimum of:

A. Window glazing and façade protection level, with a performance condition appropriate to the identified Facility Security Level.

B. Setback distance, as specified in this Lease, from the face of the Building's exterior to the protected/defended perimeter (i.e., any potential point of explosion). This means the distance from the Building to the curb or other boundary protected by bollards, planters or other street furniture. Such potential points of explosion may be, but are not limited to, such areas that could be accessible by any motorized vehicle (i.e., street, alley, sidewalk, driveway, parking lot).

C. Lobbies, mailrooms, and loading docks shall not share a return-air system with the remaining areas of the Building. The Lessor shall provide lobby, mailroom, and loading dock ventilation systems' outside air intakes and exhausts with low leakage, fast acting, isolation dampers that can be closed to isolate their systems. Dedicated HVAC shall be required for mailrooms only when the Government specifically requires a centrally operated mailroom. On Buildings of more than four stories, air intakes shall be located on the fourth floor or higher. On Buildings of three stories or less, air intakes shall be located on the roof or as high as practical. Locating intakes high on a wall is preferred over a roof location.

3.45 SEISMIC SAFETY FOR NEW CONSTRUCTION (~~SEP 2012~~) INTENTIONALLY DELETED

3.46 FIRE PROTECTION FOR NEW CONSTRUCTION (WAREHOUSE) (MAY 2015)

A. The new Building shall be protected throughout by an automatic fire sprinkler system designed in accordance with the National Fire Protection Association (NFPA) 13, *Installation of Sprinkler Systems* (current as of the Lease Award Date).

B. When an electric fire pump is provided to support the design of the fire sprinkler system, a secondary power source shall be provided to the fire pump by a standby emergency generator or another means acceptable to the Government.

3.47 INDOOR AIR QUALITY DURING CONSTRUCTION (OCT 2019)

A. The Lessor shall provide to the Government safety data sheets (SDS) or other appropriate documents upon request, but prior to installation or use for the following products, including but not limited to, adhesives, caulking, sealants, insulating materials, fireproofing or fire stopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finishes for wood surfaces, janitorial cleaning products, and pest control products.

B. The LCO may eliminate from consideration products with significant quantities of toxic, flammable, corrosive, or carcinogenic material and products with potential for harmful chemical emissions. Materials used often or in large quantities will receive the greatest amount of review.

C. Where demolition or construction work occurs adjacent to occupied Space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.

D. HVAC during Construction: If air handlers are used during construction, the Lessor shall provide filtration media with a MERV of 8 at each return air grill, as determined by the latest edition of ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size.

E. Flush-Out Procedure:

1. HVAC flush-out shall commence after construction ends and the Building has been completely cleaned. All interior finishes, such as millwork, doors, paint, carpet, acoustic tiles, and movable furnishings (e.g., workstations, partitions), must be installed, and major VOC punch list items must be finished.

2. Prior to occupancy, Lessor shall install new filtration media and perform a building flush-out by supplying a total air volume of 14,000 cubic feet of outdoor air per square foot of gross floor area while maintaining an internal temperature of at least 60°F (15°C) and no higher than 80°F (27°C) and relative humidity no higher than 60%.

3. If the LCO determines that occupancy is required before flush-out can be completed, the Space may be occupied only after delivery of a minimum of 3,500 cubic feet of outdoor air per square foot of gross floor area while maintaining an internal temperature of at least 60°F (15°C) and no higher than 80°F (27°C) and relative humidity no higher than 60%. Once the Space is occupied, it must be ventilated at a minimum rate of 0.30 cubic foot per minute (cfm) per square foot of outdoor air or greater. During each day of the flush-out period, ventilation must begin at least three hours before occupancy and continue during occupancy. These conditions must be maintained until a total of 14,000 cubic feet per square foot of outdoor air (4 270 liters of outdoor air per square meter) has been delivered to the space.

3.48 SYSTEMS COMMISSIONING (APR 2011)

The Lessor shall incorporate commissioning requirements to verify that the installation and performance of energy consuming systems meet the Government's project requirements. The commissioning shall cover only work associated with TIs or alterations or at a minimum: heating, ventilating, air conditioning and refrigeration (HVAC&R) systems and associated controls, lighting controls, and domestic hot water systems.

3.49 LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)

- A. Lessor shall provide a minimum of **one (1) loading area with two (2) ground level docks and one (1) recessed dock with self-leveler** for the exclusive use of the Government.
- B. Lessor shall equip each dock with two molded rubber bumpers (at least 6 inches by 12 inches by 14 inches) and heavy-duty bump blocks (the dock must be fully protected with edge guards and dock bumpers). Lessor shall equip each dock with exterior dock seals to prevent the exchange of air from indoors to outdoors and vice versa when the trailer docked for loading or unloading. The entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.
- C. Dock-high doors shall be a minimum of 8' wide by 10' high and shall be approximately 48" above finished exterior grade unless otherwise specified in the Agency Special Requirements. Doors shall be insulated (R8 or better) with 2" angled, metal track and manual push-up. Door shall be spring loaded to assist opening and to safe return to the closed position. Weather-tight seals shall be provided around all 4 sides of the doors.
- D. Drive-in doors shall be a minimum of 12' wide by 16' high unless otherwise specified in the Agency Special Requirements. The slope of the ramp shall not exceed 8.3% or by local code, whichever is more stringent. Doors shall be insulated (R8 or better) with 2" angled, metal track with chain hoist for opening and closing. Weather-tight seals shall be provided around all 4 sides of the doors.
- E. Lessor shall equip the recessed dock with a **hydraulic dock leveler**. If exterior to the building, the entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Any open loading docks must be covered at least 1,200 mm (4 feet) beyond the edge of the loading dock platform over the loading berth. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.
- F. Lessor shall provide sufficient ventilation to remove carbon monoxide even when doors and windows are shut. Ventilation air intakes must be at least 25 feet away from loading docks, garage entries, and similar carbon monoxide contamination points. Docks shall be separated by at least 50 feet in any direction from utility rooms, utility mains, and service entrances, including electrical, telephone/data, fire detection/alarm systems, fire suppression water mains, cooling and heating mains, etc. All regular and emergency fuel storage locations shall be located away from loading docks.
- G. All dock wells shall be level throughout. Each dock shall have a **roll-up, coiling type industrial steel warehouse & dock door with lock**. The loading dock area shall be nearly flat with a 1:50 slope for drainage. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). When a steeper slope is required in the apron area, the headroom must increase with a gradient allowance to permit trucks to traverse the grade change. If the approach to the loading dock is ramped, the design must permit easy snow removal.
- H. Lessor shall equip each loading dock with adjustable lights capable of illuminating the truck or van interior. Each dock shall have either a trailer lock or wheel chocks chained to the platforms. Where specified by Government on Exhibit A (Floor Plans), the Lessor shall provide a ramp from the loading dock down to the vehicle parking area to facilitate deliveries from small trucks and vans. This ramp must have a maximum 8.3% slope. Public and loading dock access must not be from the same point of access (at least one personnel door shall be provided in addition to overhead doors).
- I. All docks shall provide shelter to people and materials in inclement weather. Operating controls for individual dock doors, dock levelers and lights shall be located on the interior wall adjacent to each dock door.
- J. Service dock access may be from an alley, from a below grade ramp, or from a site circulation drive. Lessor shall provide sufficient space for a standard sized trailer (approximately 60 feet) to maneuver and service the facility, and also to screen the service drive as much as possible. At a minimum, Lessor shall provide a truck turning radius sized for a **standard sized tractor trailer** for all loading docks. One-way design for service traffic is preferred in order to avoid the need for large turning areas. The service area of the facility must not interfere with public access roadways.
- K. Lessor shall provide at least one off-street berth for loading and unloading. Loading berths must be located adjacent to the loading dock areas. Unless otherwise specified by local zoning regulations, a single berth must be a minimum of 4,600 mm (15 feet) wide and sized for the longest vehicle servicing the building as determined by Lessee. Additional loading berths do not need to be wider than 3,600 mm (12 feet) if they are contiguous with another loading berth. Lessor shall provide an apron space in front of the loading berth for vehicle maneuvering equal to the length of the berth plus 600 mm (2 feet). The apron must be relatively flat and have positive drainage with a minimum slope of 2%. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). If programming forces a steeper slope in the apron area, the headroom should increase with a gradient allowance to allow trucks to traverse the grade change.
- L. Loading dock areas must be separated and visually screened (wherever practical) from the main public building entrance(s). Lessor shall provide an internal staging area adjacent to the loading dock. The staging area must not interfere with emergency egress from the building. Loading docks must have a direct route to freight elevators (if any) and be sized to accommodate the transport of supplies, equipment replacement parts, and building goods. If provided for, a dock manager's room must have visual control of the entire dock area as well as the building entrance and exit. Service circulation must be separated from public areas such as lobbies, corridors, and elevators. Loading dock stairs must be on the driver's left when backing into the dock. The grade of the apron must slope away from the loading dock and shall not exceed an 8.3% slope.
- M. Trash rooms must be located adjacent to loading docks or service entrances. Trash rooms must be sized to accommodate the trash handling equipment required and provide storage for trash and recycling generated during a three day occupancy of the building. Space must be allowed for sorting and recycling of paper, bottles and cans, metals, and other materials. Facilities that use trash containers that are picked up by vendors must have at least one loading berth for the trash container.

3.50 EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)

Emergency power backup is required for all alarm systems, CCTV monitoring devices, fire alarm systems, entry control devices, lighting, etc., and special equipment, as identified elsewhere within this Lease. Costs for emergency power to critical systems that are security requirements should be allocated to the BSAC cost component.

3.51 MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)

Roof access shall meet the applicable egress requirements in the National Fire Protection Association (NFPA) 101, Life Safety Code or IBC (current as of the Award Date of this Lease).

3.52 DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)**A. Environmental Due Diligence**

Lessor is responsible for performing all necessary “response” actions (as that term is defined at 42 U.S.C. § 9601(25) of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA)) with regard to all “recognized environmental conditions,” as that term is defined in ASTM Standard E1527-13, as such standard may be revised from time to time. This obligation extends to any contamination of the Property where such contamination is not attributable to the Government. Lessor must provide the Government with a summary report demonstrating completion of all required response actions prior to Substantial Completion. Any remediation performed by or on behalf of Lessor must be undertaken in strict compliance with all applicable federal, state and local laws and regulations.

B. National Environmental Policy Act

The National Environmental Policy Act regulations provide for analyzing proposed major federal actions to determine if there are ways to mitigate the impact of the proposed actions to avoid, minimize, rectify, reduce, or compensate for environmental impacts associated with such actions. Where the Government has determined that any or all of these mitigation measures should be or must be adopted to lessen the impact of these proposed actions, Lessor must incorporate all mitigation measures identified and adopted by the Government in the design and construction drawings and specifications. All costs and expenses for development of design alternatives, mitigation measures and review submittals for work to be performed under the Lease are the sole responsibility of Lessor.

3.53 NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS – LEASE (SEP 2014) INTENTIONALLY DELETED

SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES

4.01 SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2017)

Design and construction activities for the Space shall commence upon Lease award. The Lessor shall schedule the following activities to achieve timely completion of the work required by this Lease:

A. DIDs. For the purposes of this Lease, DIDs are defined as layout line drawings of the leased Space, reflecting all Lease requirements, showing partitions and doors; schematic demolition; voice, data, and electrical outlet locations; finishes; generic furniture layout, and any additional details necessary to communicate the design intent to the lessor's architect for the purpose of preparing the construction documents (CDs). A full DID set must include the following elements:

1. Cover Sheet ;
2. Demolition Plan (if applicable);
3. Construction (Partition) Plan;
4. Power/Communication (Electrical) Plan;
5. Furniture Plan;
6. Finish Plan;
6. Racking System Plan; and
7. The exits and fire department access doors in place or any proposed exits, aisles, and fire department access doors..

B. Lessor-Provided DIDs: The Lessor must submit to GSA, as part of the shell cost, complete DIDs conforming to the requirements of this Lease and other Government-supplied information related to the tenant agency's interior build-out requirements not later than **30** Working Days following the Lease Award Date, provided that the Government supplies such information and direction as reasonably required for Lessor to timely complete DIDs. The Government (GSA and the tenant agency) shall attend two meetings at the Lessor's request for the purpose of providing information and direction in the development of DIDs. The Lessor should anticipate at least two submissions of DIDs before receiving approval. At the sole discretion of the Government, the Lessor may be required to submit a budget proposal based on the TIs and associated work as shown on the DIDs. This budget proposal shall be completed, as part of the shell cost, within **10** Working Days of the Government's request.

C. Government review and approval of Lessor-provided DIDs: The Government must notify the Lessor of DID approval not later than **20** Working Days following submission of DIDs conforming to the requirements of this Lease as supplied by the Government. Should the DIDs not conform to these requirements, the Government must notify the Lessor of such non-conformances within the same period; however, the Lessor shall be responsible for any delay to approval of DIDs occasioned by such non-conformance. The Government's review and approval of the DIDs is limited to conformance to the specific requirements of the Lease as they apply to the Space.

D. The Lessor's preparation and submission of construction documents (CDs): The Lessor as part of the TI must complete CDs conforming to the approved DIDs not later than **30** Working Days following the approval of DIDs. The pricing for this work is included under the A/E fees established under Section 1 of the Lease. If during the preparation of CDs the Lessor becomes aware that any material requirement indicated in the approved DIDs cannot be reasonably achieved, the Lessor shall promptly notify GSA, and shall not proceed with completion of CDs until direction is received from the LCO. The LCO shall provide direction within **10** Working Days of such notice, but the Government shall not be responsible for delays to completion of CDs occasioned by such circumstances. For the purpose of this paragraph, a "material requirement" shall mean any requirement necessary for the Government's intended use of the Space as provided for in, or reasonably inferable from, the Lease and the approved DIDs (e.g., number of workstations and required adjacencies).

E. Government review of CDs: The Government shall have **20** Working Days to review CDs before Lessor proceeds to prepare a TI price proposal for the work described in the CDs. At any time during this period of review, the Government shall have the right to require the Lessor to modify the CDs to enforce conformance to Lease requirements and the approved DIDs.

F. The Lessor's preparation and submission of the TI price proposal: The Lessor shall prepare and submit a complete TI price proposal in accordance with this Lease within **30** Working Days following the end of the Government CD review period.

G. The Lessor's preparation and submission of the BSAC price proposal: The Lessor shall prepare and submit a complete BSAC price proposal in accordance with this Lease within **30** Working Days following the end of the Government CD review period.

H. Negotiation of TI price proposal and issuance of notice to proceed (NTP): INTENTIONALLY DELETED

I. Negotiation of TI and BSAC price proposals and issuance of notice to proceed (NTP): The Government shall issue NTP within **30** Working Days following the submission of the TI and BSAC price proposals, provided that both the TI and BSAC price proposals conform to the requirements of the paragraphs titled "Tenant Improvements Price Proposal" and "Building Specific Amortized Capital Price Proposal" and the parties negotiate a fair and reasonable price for TIs.

J. Construction of TIs and completion of other required construction work: The Lessor shall complete all work required to prepare the Premises as required in this Lease ready for use not later than **90** Working Days following issuance of NTP.

4.02 CONSTRUCTION DOCUMENTS (SEP 2012)

The Lessor's CDs shall include all mechanical, electrical, plumbing, fire protection, life safety, lighting, structural, security, and architectural improvements scheduled for inclusion into the Space. CDs shall be annotated with all applicable specifications. CDs shall also clearly identify TIs already in place and the work to be done by the Lessor or others. Notwithstanding the Government's review of the CDs, the Lessor is solely responsible and liable for their technical accuracy and compliance with all applicable Lease requirements.

4.03 TENANT IMPROVEMENTS PRICE PROPOSAL (OCT 2016)

A. The Lessor's TI price proposal shall be supported by sufficient cost or pricing data to enable the Government to evaluate the reasonableness of the proposal, or documentation that the Proposal is based upon competitive proposals (as described below) obtained from entities not affiliated with the Lessor. Any work shown on the CDs that is required to be included in the Building shell rent or already priced as BSAC shall be clearly identified and excluded from the TI price proposal. After negotiation and acceptance of the TI price, GSA shall issue a NTP to the Lessor.

B. Under the provisions of FAR Subpart 15.4, the Lessor shall submit a TI price proposal with information that is adequate for the Government to evaluate the reasonableness of the price or determining cost realism for the TIs within the time frame specified in this section. The TI price proposal shall use the fee rates specified in the "Tenant Improvement Fee Schedule" paragraph of this Lease. The Lessor shall exclude from the TI price proposal all costs for fixtures and/or other TIs already in place, provided the Government has accepted same. However, the Lessor will be reimbursed for costs to repair or improve the fixture(s) and/or any other improvements already in place. The Lessor must provide certified cost or pricing data for TI proposals exceeding the threshold in FAR 15.403-4, to establish a fair and reasonable price. For TI proposals that do not exceed the threshold in FAR 15-403-4, the Lessor shall submit adequate documentation to support the reasonableness of the price proposal as determined by the LCO.

C. The TIs scope of work includes the Lease, the DIDs, the CDs, and written specifications. In cases of discrepancies, the Lessor shall immediately notify the LCO for resolution. All differences will be resolved by the LCO in accordance with the terms and conditions of the Lease.

D. In lieu of requiring the submission of detailed cost or pricing data as described above, the Government (in accordance with FAR 15.403) is willing to negotiate a price based upon the results of a competitive proposal process. A minimum of two qualified General Contractors (GCs) shall be invited by the Lessor to participate in the competitive proposal process. Each participant shall compete independently in the process. In the absence of sufficient competition from the GCs, a minimum of two qualified subcontractors from each trade of the Tenant Improvement Cost Summary (TICS) Table (described below) shall be invited to participate in the competitive proposal process.

E. Each TI proposal shall be (1) submitted by the proposed General Contractors (or subcontractors) using the TICS Table in CSI Masterformat; (2) reviewed by the Lessor prior to submission to the Government to ensure compliance with the scope of work (specified above) and the proper allocation of shell and TI costs; and (3) reviewed by the Government. General Contractors shall submit the supporting bids from the major subcontractors along with additional backup to the TICS Table in a format acceptable to the Government. Backup will follow the TICS table Master format cost elements and be to level 5 as described in P-120, Project Estimating Requirements for the Public Buildings Service.

F. Unless specifically designated in this Lease as a TI or BSAC cost, all construction costs shall be deemed to be included in the Shell Rent. Any costs in the GC's proposal for Building shell items shall be clearly identified on the TICS Table separately from the TI costs.

G. The Government reserves the right to determine if bids meet the scope of work, that the price is reasonable, and that the Lessor's proposed contractors are qualified to perform the work. The Government reserves the right to reject all bids at its sole discretion. The Government reserves the right to attend or be represented at all negotiation sessions between the Lessor and potential contractors.

H. The Lessor shall demonstrate to the Government that best efforts have been made to obtain the most competitive prices possible, and the Lessor shall accept responsibility for all prices through direct contracts with all contractors. The LCO shall issue to the Lessor a NTP with the TIs upon the Government's sole determination that the Lessor's proposal is acceptable. The Lessor shall complete the work within the time frame specified in this section of the Lease.

4.04 BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2015)

The Lessor's BSAC price proposal shall be supported by sufficient cost or pricing data to enable the Government to evaluate the reasonableness of the proposal, or documentation that the Proposal is based upon competitive proposals. The pricing shall be submitted using the Security Unit Price List (SecUP).

4.05 GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2019)

The Lessor shall submit to the LCO:

A. Product data sheets for floor coverings, paints and wall coverings, ceiling materials, all adhesives, wood products, suite and interior doors, subdividing partitions, wall base, door hardware finishes, window coverings, millwork substrate and millwork finishes, lighting and lighting controls, and insulation to be used within the leased Space. This information must be submitted NO LATER THAN the submission of the DIDs.

B. SDS or other appropriate documents upon request for products listed in the Lease. All SDS shall comply with Occupational Safety and Health Administration (OSHA) requirements for the Globally Harmonized System of Classification and Labeling of Chemicals (GHS). The Lessor and its agents shall comply with all recommended measures in the SDS to protect the health and safety of personnel.

C. For leases 10,000 RSF or greater, a re-use plan, if required in accordance with the "Existing Fit-out, Salvaged, or Re-used Building Material" paragraph in the Lease.

D. If the Lessor is unable to comply with the environmentally preferable requirements stated throughout the Lease, he/she must submit a waiver request for each material within the TI pricing submittal. The waiver request shall be based on the following exceptions:

1. Product cannot be acquired competitively within a reasonable performance schedule.
2. Product cannot be acquired that meets reasonable performance requirements.
3. Product cannot be acquired at a reasonable price.
4. An exception is provided by statute.

The price shall be deemed unreasonable when the total life cycle costs are significantly higher for the sustainable product versus the non-sustainable product. Life cycle costs are determined by combining the initial costs of a product with any additional costs or revenues generated from that product during its entire life.

E. Radon test results as may be required by the "Radon in Air" and "Radon in Water" paragraphs in the Lease.

F. Construction waste management plan: For leases 10,000 RSF or greater, prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the LCO, may permit alternative means of disposal.

G. Building recycling service plan: A Building recycling service plan with floor plans annotating recycling area(s) as part of DIDs, if applicable, to be reflected on the CD submission.

H. A signed statement from the Lessor for the leased Space explaining how all HVAC systems serving the leased Space will achieve the desired ventilation of the Space during the flush-out period called for in the Lease.

I. A written commissioning plan submitted to the LCO prior to the completion of DIDs, if applicable, that includes:

1. A schedule of systems commissioning (revised as needed during all construction phases of the project, with such revisions provided to the LCO immediately); and
2. A description of how commissioning requirements will be met and confirmed.

J. If renewable source power is purchased, documentation within 9 months of occupancy.

4.06 CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)

The Lessor shall furnish a detailed construction schedule (such as Critical Path Method) to the Government within **10** Working Days of issuance of the NTP. Such schedule shall also indicate the dates available for Government contractors to install telephone/data lines or equipment, if needed. Within **5** Working Days of NTP, the Lessor shall initiate a construction meeting. The Lessor will have contractor representatives including its architects, engineers, general contractor and sub-contractor representatives in attendance. The Lessor shall keep meeting minutes of discussion topics and attendance.

4.07 PROGRESS REPORTS (JUN 2012)

After start of construction, the Lessor shall submit to the LCO written progress reports at intervals of **20** Working Days. Each report shall include information as to the percentage of the work completed by phase and trade; a statement as to expected completion and occupancy dates; changes introduced into the work; and general remarks on such items as material shortages, strikes, weather, etc., that may affect timely completion. In addition, at the Government's discretion, the Lessor shall conduct meetings every two weeks to brief Government personnel and/or contractors regarding the progress of design and construction of the Space. The Lessor shall be responsible for taking and distributing minutes of these meetings.

4.08 ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)

The Government shall have the right to access any space within the Building during construction for the purposes of performing inspections or installing Government furnished equipment. The Government shall coordinate the activity of Government contractors with the Lessor to minimize conflicts with and disruption to other contractors on site. Access shall not be unreasonably denied to authorized Government officials including, but not limited to, Government contractors, subcontractors, or consultants acting on behalf of the Government on this project.

4.09 CONSTRUCTION INSPECTIONS (SEP 2015)

A. The LCO or the LCO's designated technical representative may periodically inspect construction work to review compliance with Lease requirements and approved DIDs, if applicable.

B. Periodic reviews, witnessing of tests, and inspections by the Government shall not constitute approval of the Lessor's apparent progress toward meeting the Government's objectives but are intended to discover any information which the LCO may be able to call to the Lessor's attention to prevent costly misdirection of effort. The Lessor shall remain responsible for designing, constructing, operating, and maintaining the Building in full accordance with the requirements of the Lease.

4.10 ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (SEP 2015)

A. Ten (10) Working Days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of Building shell and TIs conforming to this Lease and the

approved DIDs, if applicable, is substantially complete, a Certificate of Occupancy (C of O) has been issued as set forth below, and the Building improvements necessary for acceptance as described in the paragraph "Building Improvements" are completed.

B. The Space shall be considered substantially complete only if the Space may be used for its intended purpose, and completion of remaining work will not interfere unreasonably with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punch list generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.

C. The Lessor shall provide a valid C of O, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue C of O's or if the C of O is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease.

D. The Government will not be required to accept space prior to the schedule outlined in this Lease.

4.11 LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)

At acceptance, the Space shall be measured in accordance with the standards set forth in this Lease to determine the total ABOA SF in the Space. The rent for the Space will be adjusted based upon the measured ABOA square footage as outlined under the Payment clause of the General Clauses. At acceptance, the Lease term shall commence. The Lease Term Commencement Date, final measurement of the Premises, reconciliation of the annual rent, and amount of Commission Credit, if any, shall be memorialized by Lease Amendment.

4.12 AS-BUILT DRAWINGS (OCT 2019)

Not later than 20 days after the acceptance of the Space, the Lessor, at Lessor's expense, shall furnish to the Government a complete set of Computer Aided Design (CAD) files of as-built floor plans showing the Space under Lease, as well as corridors, stairways, and core areas. As-built drawings shall include Civil, Architectural, Mechanical, Electrical, and Plumbing features, including, but not limited to, those for IT, Communications, Security, and Fire Protection. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD. The required file extension is ".DWG." Clean and purged files shall be submitted in a digital format. They shall be labeled with Building name, address, list of drawing(s), date of the drawing(s), and Lessor's architect and architect's phone number. The Lessor's operator shall demonstrate the submission on GSA equipment, if requested by the LCO.

4.13 LIQUIDATED DAMAGES (JUN 2012) INTENTIONALLY DELETED

4.14 SEISMIC RETROFIT (SEP 2013) INTENTIONALLY DELETED

4.15 LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)

A. The Lessor's project management fee shall cover all of the Lessor's project management costs associated with the delivery of Tenant Improvements and BSAC items, including, but not limited to:

1. Legal fees
2. Travel costs
3. Insurance
4. Home office overhead and other indirect costs
5. Carrying costs, exclusive of the TI amortization rate. Carrying costs are those costs of capital incurred for the delivery of TI, for the period starting from Lessor's outlay of funds, until the Lease Term Commencement Date.
6. Municipal, county, or state fees (not related to sales tax)
7. TI proposal preparation costs
8. Lessor's labor costs related to the management of the TI build-out.

B. At a minimum, the Lessor shall be responsible for performing the following services in order to receive the project management fee:

1. Provide assistance and expertise to the Government project team in the form of coordination, management, and administration of the design and construction process;
2. Monitor performance of the general contractor and other contractors, control schedules, and oversee financial accounts;
3. Conduct and document design and construction project meetings;
4. Perform administrative tasks, including documentation, record keeping (issuing meeting minutes), and payment validation in addition to submittal and change order processing;
5. Maintain Request for Information (RFI), submittal, and change order logs; and
6. Provide technical expertise (e.g. testing, estimating, resolving claims, or responding to inquiries).

SECTION 5 TENANT IMPROVEMENT COMPONENTS

5.01 TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)

The TIs shall be designed, constructed, and maintained in accordance with the standards set forth in this Lease. For pricing, only those requirements designated within this Section 5, or designated as TIs within the attached agency requirements, shall be deemed to be TI costs.

5.02 FINISH SELECTIONS (SEP 2015)

The Lessor must consult with the Government prior to developing a minimum of three (3) finish options to include coordinated samples of finishes for all interior elements such as paint, wall coverings, base coving, carpet, window treatments, laminates, and flooring. All samples provided must comply with specifications set forth elsewhere in this Lease. All required finish option samples must be provided at no additional cost to the Government within 10 Working Days after initial submission of DIDs. GSA must deliver necessary finish selections to the Lessor within 10 Working Days after receipt of samples. The finish options must be approved by GSA prior to installation. The Lessor may not make any substitutions after the finish option is selected.

5.03 WINDOW COVERINGS (WAREHOUSE) (JUN 2012)

A. Window Blinds. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the TIs. The blinds may be aluminum or plastic vertical blinds, horizontal blinds with aluminum slats of one-inch width or less, solar fabric roller shades, or an equivalent product pre-approved by the Government. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Government.

5.04 DOORS: SUITE ENTRY (OCT 2019)

A. Suite entry doors shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Government. Hollow core wood doors are not acceptable. They shall be operable by a single effort; and shall meet the requirement of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi gloss oil-based paint finish that does not result in indoor air quality levels above 0.016 parts per million (ppm) of formaldehyde.

B. For leases 10,000 RSF or greater, the paint finish must meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False>.

5.05 DOORS: INTERIOR (OCT 2019)

A. Doors within the Space shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 80" high. Doors shall be flush, solid core, wood with a natural wood veneer face or an equivalent door pre-approved by the LCO. Hollow core wood doors are not acceptable. They shall be operable with a single effort, and shall meet the requirements of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint and which does not result in indoor air quality levels above 0.016 parts per million (ppm) of formaldehyde.

B. For leases 10,000 RSF or greater, the paint finish must meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False>.

5.06 DOORS: HARDWARE (SEP 2013)

Doors shall have door handles or door pulls with heavyweight hinges. The Lessor is encouraged to avoid the use of chrome-plated hardware. All doors shall have corresponding doorstops (wall- or floor-mounted) and silencers. All door entrances leading into the Space from public corridors and exterior doors shall have automatic door closers. Doors designated by the Government shall be equipped with 5-pin, tumbler cylinder locks and strike plates. All locks shall be master keyed. Furnish at least two master keys for each lock to the Government. Any exterior entrance shall have a high security lock, with appropriate key control procedures, as determined by Government specifications. Hinge pins and hasps shall be secured against unauthorized removal by using spot welds or pinned mounting bolts. The exterior side of the door shall have a lock guard or astragal to prevent tampering of the latch hardware. Doors used for egress only shall not have any operable exterior hardware. All security-locking arrangements on doors used for egress shall comply with requirements of NFPA 101 or the International Building Code current as of the Lease Award Date.

5.07 DOORS: IDENTIFICATION (JUN 2012)

Door identification shall be installed in approved locations adjacent to office entrances as part of the TIs. The form of door identification shall be approved by the Government.

5.08 PARTITIONS: SUBDIVIDING (OCT 2019)

A. Office subdividing partitions shall comply with applicable building codes and local requirements and ordinances and shall be provided as part of the TIs. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a minimum sound transmission class

(STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the DIDs. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84).

B. HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.

C. If installed in accordance with the "Automatic Fire Sprinkler System" and "Fire Alarm System" paragraphs, sprinklers and fire alarm notification appliances shall be repositioned as appropriate after installation of partitions to maintain the level of fire protection and life safety.

D. Partitioning requirements may be satisfied with existing partitions if they meet the Government's standards and layout requirements.

E. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building, the Lessor is encouraged to use materials for newly installed gypsum board meeting applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False>

5.09 CEILINGS—TI (WAREHOUSE) (OCT 2019)

Government designated office and related areas shall contain a complete acoustical ceiling system (such a ceiling system include grid and lay-in tiles or other Building standard ceiling system as approved by the LCO).

A. Ceilings in office and related areas shall be at a minimum 9 feet and 0 inches and no more than 12 feet and 0 inches measured from floor to the lowest obstruction. Areas with raised flooring shall maintain these ceiling-height limitations above the finished raised flooring. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the Space, with no obvious damage to tiles or grid.

B. Prior to closing the ceiling, Lessor shall coordinate with the Government for the installation of any items above the ceiling.

C. Should the ceiling be installed in the Space prior to construction of the TI, then Lessor shall be responsible for all costs for the disassembly, storage during construction, and subsequent re-assembly of ceiling components which may be required to complete the TI. Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the construction of the TI.

D. Ceilings shall be a flat plane in each room and shall be suspended and finished as follows unless an alternate equivalent is pre-approved by the LCO:

1. Restrooms. Plastered or spackled and taped gypsum board.

2. Offices and conference rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the LCO. For leases 10,000 RSF or greater, newly installed tiles or panels shall meet applicable, statutory environmentally preferable criteria as outlined under the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1732/acoustical-ceiling-tiles/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1732/acoustical-ceiling-tiles/0?addon=False>

3. Corridors and eating/galley areas. Plastered or spackled and taped gypsum board or mineral acoustical tile.

5.10 WALL FINISHES (OCT 2019)

If the Government chooses to install a wall covering, the following specifications shall apply:

A. Commercial grade, weighing not less than 13 ounces per square yard.

B. For leases 10,000 RSF or greater, wall covering shall be vinyl-free, chlorine-free, plasticizer-free with recycled or bio-based content.. If the Government chooses to install a high-performance paint coating, it shall comply with the VOC limits of the Green Seal Standard GS-11.

5.11 PAINTING—TI (OCT 2019)

A. Prior to acceptance, all surfaces within the Space which are designated by GSA for painting shall be newly finished in colors acceptable to the Government.

B. For leases 10,000 RSF or greater, the Lessor shall provide interior paints, primers, coatings, stains, and sealers that meet applicable, statutory, environmentally preferable criteria for biobased and recovered material content as outlined under the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False) and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False>. The Lessor shall use reprocessed latex paint in accordance with EPA's CPG (Comprehensive Procurement Guidelines) on all painted surfaces where feasible.

5.12 FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2019)

A. Broadloom carpet or carpet tiles meeting the requirements set forth in the specifications below shall be installed in all office areas. Office area floor perimeters at partitions shall have wood, rubber, vinyl, or carpet base. Floor covering shall be installed in accordance with manufacturing instructions to lay smoothly and evenly.

B. The use of existing carpet may be approved by the Government; however, existing carpet shall be repaired, stretched, and cleaned before occupancy and shall meet the static buildup requirement as stated in the specifications below.

C. Any alternate flooring shall be pre-approved by the Government.

D. SPECIFICATIONS FOR CARPET TO BE NEWLY INSTALLED OR REPLACED

1. Product sustainability and environmental requirements. For leases 10,000 RSF or greater, floor covering and perimeter products must meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined under the Green Procurement Compilation at WWW.SFTOOL.GOV/GREENPROCUREMENT and [HTTPS://SFTOOL.GOV/GREENPROCUREMENT/GREEN-PRODUCTS/3/BUILDING-FINISHES/23/CARPET/0?ADDON=FALSE](https://SFTOOL.GOV/GREENPROCUREMENT/GREEN-PRODUCTS/3/BUILDING-FINISHES/23/CARPET/0?ADDON=FALSE), [HTTPS://SFTOOL.GOV/GREENPROCUREMENT/GREEN-PRODUCTS/3/BUILDING-FINISHES/1307/FLOOR-COVERINGS-NON-CARPET/0?ADDON=FALSE](https://SFTOOL.GOV/GREENPROCUREMENT/GREEN-PRODUCTS/3/BUILDING-FINISHES/1307/FLOOR-COVERINGS-NON-CARPET/0?ADDON=FALSE), and <https://sftool.gov/greenprocurement/green-products/3/building-finishes/97/floor-tiles-heavy-dutycommercial/0?addon=False>.
2. Face fiber content. Face yarn must be 100 percent nylon fiber. Loop Pile shall be 100 percent Bulk Continuous Filament (BCF); cut and loop shall be 100 percent BCF for the loop portion and may be BCF or staple for the cut portion; cut pile carpet shall be staple or BCF.
3. Performance requirements for broadloom and modular tile:
 - a. Static: Less than or equal to 3.5 kV when tested by AATCC Test Method 134 (Step Test Option).
 - b. Flammability: Meets CPSC-FF-1-70, DOC-FF-1-70 Methenamine Tablet Test criteria.
 - c. Flooring Radiant Panel Test: Meets NFPA 253 Class I or II depending upon occupancy and fire code when tested under ASTM E-648 for glue down installation.
 - d. Smoke Density: NBS Smoke Chamber—Less than 450 Flaming Mode when tested under ASTM E-662.

NOTE: Testing must be performed in a NVLAP accredited laboratory.

4. Texture Appearance Retention Rating (TARR). Carpet must meet TARR rating of at least 3.0 TARR for moderate traffic areas such as private offices, and heavy traffic areas such as training space, conference rooms, courtrooms, etc., and at least 3.5 TARR for severe traffic areas, including open office space, cafeteria, corridors and lobbies. The carpet must be evaluated using ASTM D-5252 Hexapod Drum Test as per the commercial carpet test procedure and the TARR classification determined using ASTM D-7330.
5. Carpet reclamation. Reclamation of existing carpet to be determined with potential vendor. When carpet is replaced, submit certification documentation from the reclamation facility to the LCO.
6. Warranty. Submit a copy of the manufacturer's standard warranty to the LCO within the first 60 days of Government occupancy. The Government is to be a beneficiary of the terms of this warranty.

5.13 HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)

Zone Control. Provide individual thermostat control for office Space with control areas not to exceed 1,500 ABOA SF. Interior spaces must be separately zoned. Specialty occupancies (conference rooms, kitchens, etc.) must have active controls capable of sensing Space use and modulating HVAC system in response to Space demand. Areas that routinely have extended hours of operation shall be environmentally controlled through dedicated heating and air conditioning equipment. Special purpose areas (such as photocopy centers, large conference rooms, computer rooms, etc.) with an internal cooling load in excess of 5 tons shall be independently controlled. Provide concealed package air conditioning equipment to meet localized spot cooling of tenant special equipment. Portable space heaters are prohibited.

5.14 ELECTRICAL: DISTRIBUTION—TI (WAREHOUSE) (MAY 2014)

- A. All electrical, telephone, and data outlets within the Space shall be installed by the Lessor in accordance with the DIDs. All electrical outlets shall be installed in accordance with NFPA Standard 70.
- B. All outlets within the Space shall be marked and coded for ease of wire tracing; outlets shall be circuited separately from lighting. All floor outlets shall be flush with the plane of the finished floor. Outlet cover colors shall be coordinated with partition finish selections.
- C. The Lessor shall in all cases safely conceal outlets and associated wiring (for electricity, voice, and data) to the workstation(s) in partitions, ceiling plenums, in recessed floor ducts, under raised flooring, or by use of a method acceptable to the Government.

5.15 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)

Telecommunications floor or wall outlets shall be provided as part of the TIs. At a minimum, each outlet shall house one 4-pair wire jack for voice and one 4-pair wire jack for data. The Lessor shall ensure that all outlets and associated wiring, copper, coaxial cable, optical fiber, or other transmission medium used to transmit telecommunications (voice, data, video, Internet, or other emerging technologies) service to the workstation shall be safely concealed under raised floors, in floor ducts, walls, columns, or molding. All outlets/junction boxes shall be provided with rings and pull strings to facilitate the installation of cable. Some transmission medium may require special conduit, inner duct, or shielding as specified by the Government.

5.16 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)

Provide sealed conduit to house the agency telecommunications system when required.

5.17 DATA DISTRIBUTION (JUN 2012)

The Government shall be responsible for the cost of purchasing and installing data cable. The Lessor shall safely conceal data outlets and the associated wiring used to transmit data to workstations in floor ducts, walls, columns, or below access flooring. The Lessor shall provide as part of the TI, outlets with rings and pull strings to facilitate the installation of the data cable. When cable consists of multiple runs, the Lessor shall provide ladder type or other acceptable cable trays to prevent Government-provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Space such that they are within a 30-foot horizontal distance of any single drop.

5.18 ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)

A. The Lessor shall provide as part of the TIs separate data, telephone, and electric junction boxes for the base feed connections to Government provided modular or systems furniture, when such feeds are supplied via wall outlets or floor penetrations. When overhead feeds are used, junction boxes shall be installed for electrical connections. Raceways shall be provided throughout the furniture panels to distribute the electrical, telephone, and data cable. The Lessor shall provide all electrical service wiring and connections to the furniture at designated junction points. Each electrical junction shall contain an 8-wire feed consisting of 3 general purpose 120-V circuits with 1 neutral and 1 ground wire, and a 120-V isolated ground circuit with 1 neutral and 1 isolated ground wire. A 20-ampere circuit shall have no more than 8 general purpose receptacles or 4 isolated ground "computer" receptacles.

B. The Government shall be responsible for the cost of purchasing data and telecommunications cable. Said cable shall be installed and connected to systems furniture by the Lessor/contractor with the assistance and/or advice of the Government or computer vendor. The Lessor shall provide wall mounted data and telephone junction boxes, which shall include rings and pull strings to facilitate the installation of the data and telecommunications cable. When cable consists of multiple runs, the Lessor shall provide ladder-type or other acceptable cable trays to prevent Government provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Space such that they are within a 30-foot horizontal distance of any single drop. Said cable trays shall provide access to both telecommunications data closets and telephone closets.

C. The Lessor shall furnish and install suitably sized junction boxes near the "feeding points" of the furniture panels. All "feeding points" shall be shown on Government approved design intent drawings. The Lessor shall temporarily cap off the wiring in the junction boxes until the furniture is installed. The Lessor shall make all connections in the power panel and shall keep the circuit breakers off. The Lessor shall identify each circuit with the breaker number and shall identify the computer hardware to be connected to it. The Lessor shall identify each breaker at the panel and identify the devices that it serves.

D. The Lessor's electrical contractor must connect power poles or base feeds in the junction boxes to the furniture electrical system and test all pre-wired receptacles in the systems furniture. Other Government contractors will be installing the data cable in the furniture panels for the terminal and printer locations, installing the connectors on the terminal/printer ends of the cable, and continuity testing each cable. Work shall be coordinated and performed in conjunction with the furniture, telephone, and data cable installers. Much of this work may occur over a weekend on a schedule that requires flexibility and on-call visits. The Lessor must coordinate the application of Certification of Occupancy with furniture installation.

5.19 LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)**WAREHOUSE AREAS:**

A. **FIXTURES:** Once the design intent drawings are approved, the Lessor shall design and provide interior lighting to comply with requirements under the paragraph, "Lighting: Interior and Parking—Shell." Any additional lighting fixtures and/or components required beyond what would have been provided for an open warehouse 10 foot candle plan plus shipping & receiving areas of 30 foot candles (Shell) are part of the TIs.

B. Lighting for the warehouse, shipping, and receiving portions of the Space is detailed in Section 3 and is part of Shell.

C. **BUILDING PERIMETER:** There may be additional requirements for lighting in exterior parking areas, vehicle driveways, pedestrian walkways, and Building perimeter in the Security Requirements attached to this Lease. Such additional lighting required to meet Security Requirements shall be BSAC.

OFFICE AREAS:

NOTE: FOR PRICING ESTIMATING PURPOSES, FIXTURES IN OFFICE AREAS WILL BE INSTALLED AT THE AVERAGE RATIO OF 1 FIXTURE PER 80 ABOA SF.

A. **FIXTURES:** High efficiency T-8, T-5, or LED light fixtures (and associated ballasts or drivers) shall be installed as either ceiling grid or pendant mounted for an open-office plan. Ceiling grid fixtures shall be either 2' wide by 4' long or 2' wide by 2' long. Lessor shall provide a minimum overall lighting fixture efficiency of 85 percent. Lamps shall maintain a uniform color level throughout the lease term.

B. **LIGHTING LEVELS:** Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1.

C. POWER DENSITY:

Existing Buildings: The maximum fixture power density shall not exceed 1.4 watts per ABOA SF.

New Construction: The maximum fixture power density shall not exceed 1.1 watts per ABOA SF.

D. **DAYLIGHTING CONTROLS:** If the office portion of the Space is more than 10,000 ABOA SF, the Lessor shall provide daylight dimming controls in atriums or within 15 feet of windows and skylights where daylight can contribute to energy savings. Daylight harvesting sensing and controls shall be either integral to the fixtures or ceiling mounted and shall maintain required lighting levels in office work areas.

E. OCCUPANCY/VACANCY SENSORS: The Lessor shall provide ceiling mount occupancy sensors, or vacancy sensors (preferred), or scheduling controls through a building automation system (BAS) throughout the office portion of the Space in order to reduce the hours that the lights are on when a particular space is unoccupied. Occupancy sensors only shall be installed in the non-office areas of the Space as part of Shell Rent. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

5.20 LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)

The Government will require hydraulic dock levelers or loading ramps for any warehouse dock (other than drive thrus) not already having dock high loading docks.

5.21 AUTOMATIC FIRE SPRINKLER SYSTEM – TI (OCT 2016)

Where sprinklers are required in the Space, sprinkler mains and distribution piping in a “protection” layout (open plan) with heads turned down with an escutcheon or trim plate shall be provided as part of Shell rent. Any additional sprinkler fixtures and/or components required in the Space beyond what would have been provided for an open office plan (shell) are part of the TIs.

SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM

6.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)

A. The Government's normal hours of operations are established as **7:00 AM** to **6:00 PM**, Monday through Friday, with the exception of Federal holidays. Services, maintenance, and utilities shall be provided during these hours. The Government shall have access to the Premises and its Appurtenant Areas at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, restrooms, lights, and electric power. Janitorial services shall be performed during normal hours.

B. The Lessor and the Lessor's representatives, employees and contractors shall demonstrate a cooperative, positive, welcoming, respectful, professional and business-like demeanor and shall present a neat, clean, job-appropriate (professional) appearance.

6.02 UTILITIES (APR 2011)

The Lessor is responsible for providing all utilities necessary for base Building and tenant operations as part of the rental consideration.

6.03 UTILITY CONSUMPTION REPORTING (OCT 2016)

Upon the effective date of the Lease, only for leases over 10,000 RSF, the Lessor shall provide regular quarterly reports for the amount of utilities (including water) consumed at the Building broken down by utility type per month for the duration of the Lease. Lessors shall report this utility consumption data within 45 calendar days of the end of each calendar quarter in the Environmental Protection Agency (EPA) Portfolio Manager online tool [HTTPS://WWW.ENERGYSTAR.GOV/](https://www.energystar.gov/). Data reported includes, but is not limited to, the number of actual units consumed, by utility type per month, and associated start and end date(s) for that consumption.

(Refer to the following link for reporting guidance: www.gsa.gov/ucr)

6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2018)

A. In all office areas, temperatures shall conform to local commercial equivalent temperature levels and operating practices in order to maximize tenant satisfaction. These temperatures shall be maintained throughout the leased Premises and service areas, regardless of outside temperatures, during the hours of operation specified in the Lease. The Lessor shall perform any necessary systems start-up required to meet the commercially equivalent temperature levels prior to the first hour of each day's operation. At all times, humidity shall be maintained below 60% relative humidity.

B. In all office areas, during non working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not be provided except as necessary to return Space temperatures to a suitable level for the beginning of working hours. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative.

C. In all office areas, thermal comfort. During all working hours, comply with the latest edition of ASHRAE Standard 55, Thermal Comfort Conditions for Human Occupancy.

D. Warehouse or garage areas require heating and ventilation only. Cooling of this Space is not required. Temperature of warehouse or garage areas shall be maintained at a minimum of 50° Fahrenheit.

E. The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the Lease and shall make a reasonable attempt to schedule major construction outside of office hours.

F. Normal HVAC systems' maintenance shall not disrupt tenant operations.

G. **3,807 ABOA SF** of the Premises shall receive cooling at all times (24 hrs a day, 365 days a year). Specifications on the size and required cooling for each room is outlined in sub-paragraph H below. The temperature of these rooms shall be maintained at **70** degrees F, with humidity control not to exceed 60% relative humidity, regardless of outside temperature or seasonal changes.

H. In accordance with the above, the following areas shall receive HVAC at all times:

Room Name	Room No.	USF	Supplemental Cooling Tonnage
MDF (Inc. Telecom)	1006/1007	466	6
1st Floor IDF	1703	135	3
UPS (Lessor Owned)	1401A		
STAI SERVER	1406A	588	10
2nd Floor IDF	2038	116	3
SCIF EQUIP	2004	72	1
STIG SERVER/LAB	1106	563	2
T2S2 SERVER/LAB	1112	508	10
STIC (NDC) SERVER	1205	370	6
STII SERVER	1308	394	8
STCR SERVER	1405A	155	4
STS COMPUTER/LAB	2101	440	6
Total		3807	59

I. The 24 hour, 365 days a year HVAC service(s) stated above shall be provided by the Lessor as part of the operating rent established under the Lease.

6.05 OVERTIME HVAC USAGE (OCT 2018)

A. If there is to be a charge for heating or cooling outside of the Building's normal hours, such services shall be provided at the hourly rates set forth elsewhere in the Lease. Overtime usage services may be ordered by the Government's authorized representative only.

B. When the cost of service is \$3,500 or less, the service may be ordered orally. An invoice shall be submitted to the official placing the order for certification and payment. Orders for services costing more than \$3,500 shall be placed using GSA Form 300, Order for Supplies or Services, or other approved service requisition procurement document. An invoice conforming to the requirements of this Lease shall be submitted to the official placing the order for certification and payment.

C. Failure to submit a proper invoice within 120 days of providing overtime utilities shall constitute a waiver of the Lessor's right to receive any payment for such overtime utilities pursuant to this Lease.

6.06 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)

The Lessor shall maintain the office area and common area of the Premises in a clean condition and shall provide supplies and equipment for these areas for the term of the Lease. The following schedule describes the level of services intended. Performance will be based on the LCO's evaluation of results, not the frequency or method of performance.

A. Daily. Empty trash receptacles. Sweep entrances, lobbies, and corridors. Spot sweep floors, and spot vacuum carpets. Clean drinking fountains. Sweep and damp mop or scrub restrooms. Clean all restroom fixtures, and replenish restroom supplies. Dispose of all trash and garbage generated in or about the Building. Wash inside and out or steam clean cans used for collection of food remnants from snack bars and vending machines. Dust horizontal surfaces that are readily available and visibly require dusting. Spray buff resilient floors in main corridors, entrances, and lobbies. Clean elevators and escalators. Remove carpet stains. Police sidewalks, parking areas, and driveways. Sweep loading dock areas and platforms. Clean glass entry doors to the Space.

B. Three times a week. Sweep or vacuum stairs.

C. Weekly. Damp mop and spray buff all resilient floors in restrooms and health units. Sweep sidewalks, parking areas, and driveways (weather permitting).

D. Every two weeks. Spray buff resilient floors in secondary corridors, entrance, and lobbies. Damp mop and spray buff hard and resilient floors in office Space.

E. Monthly. Thoroughly dust furniture. Completely sweep and/or vacuum carpets. Sweep storage Space. Spot clean all wall surfaces within 70 inches of the floor.

F. Every two months. Damp wipe restroom wastepaper receptacles, stall partitions, doors, window sills, and frames. Shampoo entrance and elevator carpets.

G. Three times a year. Dust wall surfaces within 70 inches of the floor, vertical surfaces and under surfaces. Clean metal and marble surfaces in lobbies. Wet mop or scrub garages.

H. Twice a year. Wash all interior and exterior windows and other glass surfaces. Strip and apply four coats of finish to resilient floors in restrooms. Strip and refinish main corridors and other heavy traffic areas.

I. Annually. Wash all venetian blinds, and dust 6 months from washing. Vacuum or dust all surfaces in the Building more than 70 inches from the floor, including light fixtures. Vacuum all draperies in place. Strip and refinish floors in offices and secondary lobbies and corridors. Shampoo carpets in corridors and lobbies. Clean balconies, ledges, courts, areaways, and flat roofs.

J. Every two years. Shampoo carpets in all offices and other non-public areas.

K. Every five years. Dry clean or wash (as appropriate) all draperies.

L. As required. Properly maintain plants and lawns. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Provide and empty exterior ash cans and clean area of any discarded cigarette butts.

M. Pest control. Control pests as appropriate, using Integrated Pest Management techniques, as specified in the GSA Environmental Management Integrated Pest Management Technique Guide (E402-1001).

N. Hand Sanitizer. Provide 22 hand sanitizer dispensers and refill as needed. Units are required as follows - 2 elevator lobbies; 6 breakroom/pantry, 9 bathrooms, 4 exits, 1 lobby.

O. Routine Cleaning and Disinfecting Requirements for the Premises. The Lessor shall wipe down daily all solid, high contract surfaces in Building common areas (defined here as those areas used or accessed by the Government's employees and visitors), and within the leased Space using a disinfectant from the EPA-registered list of products identified as effective against Novel Coronavirus SARS-CoV-2 ([HTTPS://WWW.EPA.GOV/PESTICIDE-REGISTRATION/LIST-N-DISINFECTANTS-USE-AGAINST-SARS-COV-2](https://www.epa.gov/pesticide-registration/list-n-disinfectants-use-against-sars-cov-2)), or other products containing the

same active ingredients(s) at the same or greater concentration than those on the list. Cleaning staff shall use products in accordance with directions provided by the manufacturer. Cleaning staff shall wear disposable gloves (e.g., latex, nitrile, etc.), facemasks, and any additional personal protection equipment (PPE) as recommended by the cleaning and disinfectant product manufacturers. Disinfection application and products should be chosen so as to not damage interior finishes or furnishings.

Examples of solid, high contact surfaces in Building common and high traffic areas include, but are not limited to, handrails, door knobs, key card scan pads, light switches, countertops, table tops, water faucets and handles, elevator buttons, sinks, toilets and control handles, restroom stall handles, toilet paper and other paper dispensers, door handles and push plates, water cooler and drinking fountain controls. It does not include agency owned equipment such as desks, telephones, computers, keyboards, docking stations, computer power supplies, and computer mouse, personal fans and heaters, desk lighting, etc. Disinfected surfaces should be allowed to air dry.

The Government reserves the right to issue notice to unilaterally cancel this routine cleaning and disinfecting at any time during the Lease term and, in such a case, the rental rate will be reduced by the amount specified for "Routine Cleaning and Disinfecting Services" under lease clause "Rent and Other Consideration". This reduction shall occur after the Government gives 30 calendar days notice to the Lessor and shall continue in effect until the Lease expires or is terminated.

6.07 SELECTION OF CLEANING PRODUCTS (OCT 2019)

For leases 10,000 RSF or greater where the Government is a sole occupant of the building, the Lessor shall use cleaning products (including general purpose cleaners, floor cleaners, hand soap, etc.) that meet applicable, statutory, environmentally preferable criteria related to biobased and recovered material content as outlined under the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://SFTOOL.GOV/GREENPROCUREMENT) and <https://sftool.gov/greenprocurement/green-products/5/cleaning-products/0>.

6.08 SELECTION OF PAPER PRODUCTS (OCT 2019)

For leases 10,000 RSF or greater where the Government is a sole occupant of the building, the Lessor shall select paper and paper products (e.g., restroom tissue and paper towels) that meet applicable, statutory, environmentally preferable criteria related to biobased and recovered material content as outlined under the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://SFTOOL.GOV/GREENPROCUREMENT) and <https://sftool.gov/greenprocurement/green-products/5/cleaning-products/0>.

6.09 SNOW REMOVAL (WAREHOUSE) (MAY 2014)

Lessor shall provide snow removal services for the Government on all days for which this Lease has designated normal hours. Lessor shall clear parking lots if the accumulation of snow exceeds two inches. Lessor shall clear sidewalks, walkways, loading docks, dock ramps, and entrances before accumulation exceeds 1.5 inches. The snow removal shall take place no later than 5:00 AM, without exception. Should accumulation continue throughout the day, the Lessor shall provide such additional snow removal services to prevent accumulation greater than the maximums specified in this paragraph. In addition to snow removal, the Lessor shall keep sidewalks, walkways, loading docks, dock ramps, and entrances free of ice during the normal hours. The Lessor shall remove excess buildup of sand and/or ice melt to minimize slipping hazards. If the Building entrance(s) has a northern exposure, then Lessor shall take additional measures to protect the safety of pedestrians.

6.10 MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)

A. The Lessor is responsible for the total maintenance, repair and replacement of the leased Premises, the Building, and the Property. Such maintenance, repairs and replacements include the site and private access roads, and all necessary repairs and replacements to the loading docks, ramps, levelers and all other associated equipment and features. All equipment and systems shall be maintained, repaired, and replaced to provide reliable, energy efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance responsibility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with current applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the Government's designated representative.

B. At the Lessor's expense, the Government reserves the right to require documentation of proper operations or testing inspection, testing, and maintenance of fire protection systems, such as fire alarm, fire sprinkler, standpipes, fire pump, emergency lighting, illuminated exit signs, emergency generator, prior to occupancy to ensure proper operation. These tests shall be witnessed by the Government's designated representative.

6.11 MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016)

A. Paint, wall coverings. Lessor shall maintain all wall coverings and high performance paint coatings in "like new" condition for the life of the Lease. All painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if the paint is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this Lease. In addition to the foregoing requirement,

1. Lessor shall repaint common areas at least every three years.
2. Lessor shall perform cyclical repainting of the Space every 5 years of occupancy. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.
3. If the warehouse portion of the Space was painted originally, Lessor shall perform cyclical repainting of the warehouse portion at the same cycle as the office and related space. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.

B. Carpet and flooring.

1. Except when damaged by the Government, the Lessor shall repair or replace flooring at any time during the Lease term when:
 - a. Backing or underlayment is exposed;
 - b. There are noticeable variations in surface color or texture;
 - c. It has curls, upturned edges, or other noticeable variations in texture;
 - d. Tiles are loose; or,
 - e. Tears or tripping hazards are present.
2. Notwithstanding the foregoing, as part of the rental consideration, the Lessor shall replace all carpet and base coving in the Space every 5 years, with a product which meets the requirements in the "Floor Coverings and Perimeters" paragraph in this Lease.
3. Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture per manufacturer's warranty, if necessary. Work shall be performed after the normal hours established elsewhere in this Lease.
4. Except when damaged by the Government, Lessor shall reseal flooring in warehouse areas whenever there are noticeable variations in surface color or texture.

6.12 ASBESTOS ABATEMENT (APR 2011)

If asbestos abatement work is to be performed in the Space after occupancy, the Lessor shall submit to the Government the occupant safety plan and a description of the methods of abatement and re-occupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

6.13 ONSITE LESSOR MANAGEMENT (APR 2011)

The Lessor shall provide an onsite Building superintendent or a locally designated representative available to promptly respond to deficiencies, and immediately address all emergency situations. The Lessor's representative shall be available to respond to any deficiencies 24/7, within four (4) hours of being notified of said deficiency, and within one (1) hour of being notified of any emergency situations, as determined by the Government.

6.14 IDENTITY VERIFICATION OF PERSONNEL (OCT 2016)

A. The Government reserves the right to verify identities of personnel with routine and/or unaccompanied access to the Government's Space, including both pre and post occupancy periods. The Lessor shall comply with the agency personal identity verification procedures below that implement [Homeland Security Presidential Directive-12](#) (HSPD-12), Office of Management and Budget (OMB) guidance [M-05-24](#) and [M-11-11](#), and Federal Information Processing Standards Publication (FIPS PUB) Number 201, as amended. These policies require the Government to conduct background investigations and make HSPD-12 compliant suitability determinations for all persons with routine or unaccompanied access to Government leased Space. By definition, this includes at a minimum each employee of the Lessor, as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased Space for a period greater than 6 months. The Government may also require this information for the Lessor's employees, contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's Space.

B. Application Process: The background investigation will be done using the Government's prescribed process. The Lessor must provide information on each of their contractor/personnel meeting the above criteria to the Government, whereupon each identified contractor/personnel will be notified with instructions for completing the identity verification application within a given time frame. The application process will include completing supplemental information forms that must be inputted into the identity verification system in order for the application to be considered complete. Additionally, the Lessor must ensure prompt completion of the fingerprint process for their contractor/personnel. Email notifications will be sent with instructions on the steps to be taken to schedule an appointment for fingerprinting at an approved regional location along with instructions on how to complete the background investigation application.

C. The Lessor must ensure the Lease Contracting Officer (or the Lease Contracting Officer's designated representative) has all of the requested documentation timely to ensure the completion of the investigation.

D. Based on the information furnished, the Government will conduct background investigations. The Lease Contracting Officer will advise the Lessor in writing if a person fails the investigation, and, effective immediately, that person will no longer be allowed to work or be assigned to work in the Government's Space.

E. Throughout the life of the Lease, the Lessor shall provide the same data for any new employees, contractors, or subcontractors who will be assigned to the Government's Space in accordance with the above criteria. In the event the Lessor's contractor or subcontractor is subsequently replaced, the new contractor or subcontractor is not required to have persons re-apply who were cleared through this process while associated with the former contractor or subcontractor in accordance with GSA policy. The Lessor shall require each cleared person to re-apply and obtain a new clearance in accordance with GSA policy.

F. The Lessor is accountable for not allowing contractors to start work without the successful completion of the appropriate background investigation as required by GSA policy.

G. Access Card Retrieval/Return: Upon an Entry on Duty notification, the Government will issue a Personal Identity Verification (PIV) credential that is sometimes referred to as a GSA Access card. Lessors are responsible for all PIV credential issued to their contractors/personnel pursuant to this

Lease. Lessors are specifically responsible for ensuring that all GSA PIV access cards are returned to the Lease Contracting Officer or their designee whenever their employees or a contractor no longer require access to the Space (such as When no longer needed for contract performance, upon completion of the Contractor employee's employment, and upon contract completion or termination). Additionally, the Lessor must notify the Lease Contracting Officer or their designee whenever a GSA PIV Access card is lost or stolen in which event the Lessor may be responsible for reimbursing the Government for replacement credentials at the current cost per PIV HSPD12 credential. Unreturned PIV Access cards will be considered as lost or stolen cards.

H. The Government reserves the right to conduct additional background checks on Lessor personnel and contractors with routine access to Government leased Space throughout the term of the Lease to determine who may have access to the Premises.

I. The Lease Contracting Officer may delay final payment under a contract if the Contractor fails to comply with these requirements.

J. The Lessor shall insert this paragraph in all subcontracts when the subcontractor is required to have physical access to a federally controlled facility or access to a federal information system.

6.15 SCHEDULE OF PERIODIC SERVICES (JUN 2012)

Within 60 days after occupancy by the Government, the Lessor shall provide the LCO with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly.

6.16 LANDSCAPING (OCT 2019)

A. For leases 10,000 RSF or greater where the Government is the sole occupant of the building, the Lessor shall use landscaping products that meet applicable statutory environmentally preferable criteria related to recycled content as outlined under the Green Procurement Compilation at [HTTPS://SFTOOL.GOV/GREENPROCUREMENT](https://sftool.gov/greenprocurement) and <https://sftool.gov/greenprocurement/green-products/6/landscaping-products/0>.

B. Landscape management practices shall prevent pollution by:

1. Employing practices which avoid or minimize the need for herbicides, fertilizers and pesticides; and
2. Composting/recycling all yard waste.

C. For leases 10,000 RSF or greater, if the Lessor satisfies performance of this Lease by new construction, and where conditions permit, the site shall be landscaped for low maintenance and water conservation with plants that are either native or well-adapted to local growing conditions.

6.17 LANDSCAPE MAINTENANCE (APR 2011)

Landscape maintenance shall be performed during the growing season at not less than a weekly cycle and shall consist of watering, weeding, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an as-needed basis. In addition, dead, dying, or damaged plants shall be replaced.

6.18 RECYCLING—WAREHOUSE (MAY 2014)

A. Where state or local law, code, or ordinance requires recycling programs for the Premises, Lessor shall comply with such state and/or local law, code, or ordinance.

B. When implementing any recycling program, the Lessor shall provide an easily accessible, appropriately sized area (2 SF per 1,000 SF of Building gross floor area) that serves the Space for the collection and storage of materials for recycling. Telecom rooms are not acceptable as recycling space. During the Lease term, the Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the Building and in the Space.

C. For Leases greater than 10,000 rentable SF, with a Lease term greater than six months, the Lessor shall establish a recycling program for (at a minimum) paper, corrugated cardboard, glass, plastics, and metals where local markets for recovered materials exist.

6.19 RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)

During the term of the Lease, the Lessor may not establish vending facilities within the leased Space that will compete with any Randolph-Sheppard vending facilities.

6.20 SAFEGUARDING AND DISSEMINATION OF SENSITIVE BUT UNCLASSIFIED (SBU) BUILDING INFORMATION (FEB 2020)

This clause applies to all recipients of CUI building information (which falls within the CUI Physical Security category), including offerors, bidders, awardees, contractors, subcontractors, lessors, suppliers and manufacturers.

Marking CUI. Contractors must submit any contractor-generated documents that contain building information to GSA for review and identification of any CUI building information that may be included. In addition, any documents GSA identifies as containing CUI building information must be marked in accordance with the Order and the Marking Controlled Unclassified Information Handbook (the current version may be found at [HTTPS://WWW.ARCHIVES.GOV/FILES/CUI/20161206-CUI-MARKING-HANDBOOK-V1-1.PDF](https://www.archives.gov/files/cui/20161206-CUI-MARKING-HANDBOOK-V1-1.PDF)) before the original or any copies are disseminated to any other parties. If CUI content is identified, the CO may direct the contractor, as specified elsewhere in this contract, to imprint or affix CUI document markings (CUI) to the original documents and all copies, before any dissemination, or authorized GSA employees may mark the documents.

1. Authorized recipients.

- a. Building information designated as CUI must be protected with access strictly controlled and limited to those individuals having a Lawful Government Purpose to access such information, as defined in 32 C.F.R. § 2002.4(bb). Those with such a Lawful Government Purpose may include Federal, state and local government entities, and non-governmental entities engaged in the conduct of business on behalf of or with GSA. Non-governmental entities may include architects, engineers, consultants, contractors, subcontractors, suppliers, utilities, and others submitting an offer or bid to GSA, or performing work under a GSA contract or subcontract. Recipient contractors must be registered as "active" in the System for Award Management (SAM) database at WWW.SAM.GOV, and have a Lawful Government Purpose to access such information. If a subcontractor is not registered in the SAM database and has a Lawful Government Purpose to possess CUI building information in furtherance of the contract, the subcontractor must provide to the contractor its DUNS number or its tax ID number and a copy of its business license. The contractor must keep this information related to the subcontractor for the duration of the contract and subcontract.
 - b. All GSA personnel and contractors must be provided CUI building information when needed for the performance of official Federal, state, and local government functions, such as for code compliance reviews and the issuance of building permits. Public safety entities such as fire and utility departments may have a Lawful Government Purpose to access CUI building information on a case-by-case basis. This clause must not prevent or encumber the necessary dissemination of CUI building information to public safety entities.
2. Dissemination of CUI building information:
- a. By electronic transmission. Electronic transmission of CUI information outside of the GSA network must use session encryption (or alternatively, file encryption) consistent with National Institute of Standards and Technology (NIST) SP 800-171. Encryption must be through an approved NIST algorithm with a valid certification, such as Advanced Encryption Standard or Triple Data Encryption Standard, in accordance with Federal Information Processing Standards Publication 140-2, Security Requirements for Cryptographic Modules, as required by GSA policy.
 - b. By nonelectronic form or on portable electronic data storage devices. Portable electronic data storage devices include CDs, DVDs, and USB drives. Nonelectronic forms of CUI building information include paper documents, photographs, and film, among other formats.
 - i. By mail. Contractors must only use methods of shipping that provide services for monitoring receipt such as track and confirm, proof of delivery, signature confirmation, or return receipt.
 - ii. In person. Contractors must provide CUI building information only to authorized recipients with a Lawful Government Purpose to access such information. Further information on authorized recipients is found in section 1 of this clause.
3. Record keeping. Contractors must maintain a list of all entities to which CUI is disseminated, in accordance with sections 2 and 3 of this clause. This list must include, at a minimum:
- a. The name of the state, Federal, or local government entity, utility, or firm to which CUI has been disseminated;
 - b. The name of the individual at the entity or firm who is responsible for protecting the CUI building information, with access strictly controlled and limited to those individuals having a Lawful Government Purpose to access such information;
 - c. Contact information for the named individual; and
 - d. A description of the CUI building information provided.

Once "as built" drawings are submitted, the contractor must collect all lists maintained in accordance with this clause, including those maintained by any subcontractors and suppliers, and submit them to the CO. For Federal buildings, final payment may be withheld until the lists are received.

4. Safeguarding CUI documents. CUI building information (both electronic and paper formats) must be stored within controlled environments that prevent unauthorized access. GSA contractors and subcontractors must not take CUI building information outside of GSA or their own facilities or network, except as necessary for the performance of that contract. Access to the information must be limited to those with a Lawful Government Purpose for access.
5. Destroying CUI building information. When no longer needed, CUI building information must either be returned to the CO or destroyed in accordance with guidelines in NIST Special Publication 800-88, Guidelines for Media Sanitization.
6. Notice of disposal. The contractor must notify the CO that all CUI building information has been returned or destroyed by the contractor and its subcontractors or suppliers in accordance with paragraphs 4 and 5 of this clause, with the exception of the contractor's record copy. This notice must be submitted to the CO at the completion of the contract to receive final payment. For leases, this notice must be submitted to the CO at the completion of the lease term.
7. CUI security incidents. All improper disclosures or receipt of CUI building information must be immediately reported to the CO and the GSA Incident Response Team Center at GSA-IR@GSA.GOV. If the contract provides for progress payments, the CO may withhold approval of progress payments until the contractor provides a corrective action plan explaining how the contractor will prevent future improper disclosures of CUI building information. Progress payments may also be withheld for failure to comply with any provision in this clause until the contractor provides a corrective action plan explaining how the contractor will rectify any noncompliance and comply with the clause in the future.
8. Subcontracts. The contractor and subcontractors must insert the substance of this clause in all subcontracts

6.21 INDOOR AIR QUALITY (OCT 2019)

A. The Lessor shall control airborne contaminants at the source and/or operate the Space in such a manner that indoor air quality action limits identified in the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8), OSHA regulatory limits, and generally accepted consensus standards are not exceeded. .

B. The Lessor shall avoid the use of products containing toxic, hazardous, carcinogenic, flammable, or corrosive ingredients as determined from the product label or manufacturer's safety data sheet. The Lessor shall use available odor-free or low odor products when applying paints, glues, lubricants, and similar wet products. When such equivalent products are not available, lessor shall use the alternate products outside normal working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying chemicals or products with noticeable odors in occupied Spaces and shall adequately ventilate those Spaces during and after application.

C. The Lessor shall serve as first responder to any occupant complaints about indoor air quality (IAQ). The Lessor shall promptly investigate such complaints and implement the necessary controls to address each complaint. Investigations shall include testing as needed, to ascertain the source and severity of the complaint.

D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in Space that it occupies, as well as in space serving the Space (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by:

1. Making available information on Building operations and Lessor activities;
2. Providing access to Space for assessment and testing, if required; and
3. Implementing corrective measures required by the LCO. The Lessor shall take corrective action to correct any tests or measurements that do not meet GSA policy action limits in the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8), OSHA regulatory limits, and generally accepted consensus standards.

E. The Lessor shall provide to the Government safety data sheets (SDS) upon request for the following products prior to their use during the term of the Lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within the Space, common building areas, ventilation systems and zones serving the Space, and the area above suspended ceilings and engineering space in the same ventilation zone as the Space.

F. The Lessor shall use high efficiency (HEPA) filtration vacuums for cleaning and minimum MERV 10 rated ventilation system filtration whenever feasible.

G. The Lessor is encouraged to comply with best practices outlined in Appendix D- Indoor Air Quality in GSA Leased Facilities (Best Practices) within the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8).

6.22 RADON IN AIR (OCT 2016)

If Space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased Space for 2 days to 3 days using charcoal canisters. The Lessor is responsible to provide Space in which radon levels in air are below the GSA action levels of 4 picoCuries per liter (pCi/L) for childcare and 25 pCi/L for all other space. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors shall be completed. For further information on radon, go to: [HTTPS://WWW.EPA.GOV/RADON](https://www.epa.gov/radon).

6.23 RADON IN WATER (JUN 2012)

A. If the water source is not from a public utility, the Lessor shall demonstrate that water provided to the Premises is in compliance with EPA requirements and shall submit certification to the LCO prior to the Government occupying the Space.

B. If the EPA action level is reached or exceeded, the Lessor shall institute appropriate abatement methods which reduce the radon levels to below this action.

6.24 HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)

A. The leased Space shall be free of hazardous materials, hazardous substances, and hazardous wastes, as defined by and according to applicable Federal, state, and local environmental regulations. Should there be reason to suspect otherwise, the Government reserves the right, at Lessor's expense, to require documentation or testing to confirm that the Space is free of all hazardous materials.

B. Lessor shall, to the extent of its knowledge, notify Government of the introduction of any hazardous materials onto the Property by Lessor or others, including but not limited to, co-tenants occupying Space in the Building.

C. All hazardous materials stored in the Space must be kept and maintained according to applicable Federal, State, and local environmental regulations. The Government will notify Lessor of any hazardous materials it will store in the Space.

6.25 MOLD (OCT 2018)

A. Actionable mold is either visible mold or airborne mold of types and concentrations in excess of that found in the local outdoor air or non-problematic control areas elsewhere in the same building, whichever is lower. The Lessor shall safely remediate all actionable mold in accordance with sub-paragraph C below.

B. The Lessor shall provide Space to the Government that is free from ongoing water leaks or moisture infiltration. The Space and ventilation zones serving the Space shall also be free of actionable mold.

C. Within 72 hours following a flood, plumbing leak or heavy rain whereby the Government Space or air zones serving the Space may have become moisture damaged, the Lessor shall repair any leakage sources and remediate the moisture damage. Whenever moisture damage or infiltration persists such that: mold is visible, mold odors are present, or occupants register complaints about mold, the Lessor shall employ a board-certified, industrial hygienist or equivalently qualified consultant to inspect and evaluate the Space and air zones serving the Space for visible and/or actionable mold presence; inspection shall take place no later than 15 calendar days following identification of a potential mold issue as described above. The Lessor shall promptly furnish these inspection results to the Government. After all leaks have been identified and corrected, the Lessor shall safely remediate all visible moldy and/or water damaged materials identified by the consultant using a qualified remediation contractor following the methods identified in "Mold Remediation in Schools and Commercial Buildings" (EPA 402-K-01-001, September 2008) and all applicable state laws pertaining to mold

remediation practices. Remediation shall also remove actionable mold levels. Remediation shall be completed within a time frame acceptable to the Lease Contracting Officer which shall be no later than 90 calendar days following confirmation of the presence of actionable mold.

D. The presence of actionable mold in the Premises may be treated as a Casualty, as determined by the Government, in accordance with the Fire and Other Casualty clause contained in the General Clauses of this Lease. In addition to the provisions of the Fire and Other Casualty clause of this Lease, should a portion of the Premises be determined by the Government to be un-tenantable due to an act of negligence by the Lessor or his agents, the Lessor shall provide reasonably acceptable alternative Space at the Lessor's expense, including the cost of moving, and any required alterations.

6.26 OCCUPANT EMERGENCY PLANS (SEP 2013)

The Lessor is required to cooperate, participate and comply with the development and implementation of the Government's Occupant Emergency Plan (OEP) and if necessary, a supplemental Shelter-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising its OEP and SIP. The Plan, among other things, must include an annual emergency evacuation drill, emergency notification procedures for the Lessor's Building engineer or manager, Building security, local emergency personnel, and Government agency personnel.

6.27 FLAG DISPLAY (OCT 2016)

If the Lessor has supplied a flagpole on the Property as a requirement of this Lease, the Lessor shall be responsible for flag display on all workdays and Federal holidays. The Lessor may illuminate the flag in lieu of raising and lowering the flag daily. The Lessor shall register with the Federal Protective Service (FPS) MegaCenter in order to receive notifications regarding when flags shall be flown at half-staff, as determined by Executive Order.

6.28 PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)

Lessor shall provide, inspect, and maintain portable fire extinguishers in accordance with NFPA No. 10.

6.29 TRASH DUMPSTER SERVICE – LESSOR PROVIDED (WAREHOUSE) (OCT 2016)

Lessor must provide trash dumpster service for the Space on a daily basis. Lessor must provide an outdoor area for dumpsters, conveniently located to the Government's loading area for the trash dumpsters at no additional charge to the Government.

6.30 ACCESS TO BUILDING INFORMATION (MAY 2014)

Building Information—including mechanical, electrical, vertical transport, fire protection and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, preferably by the development of an access list and controlled copy numbering. The LCO may direct that the names and locations of Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the Building directory.

SECTION 7 ADDITIONAL TERMS AND CONDITIONS

7.01 SECURITY REQUIREMENTS (OCT 2016)

The Lessor agrees to the requirements of Facility Security Level III attached to this Lease.

7.02 MODIFIED LEASE PARAGRAPHS (OCT 2016)

The following paragraphs have been modified in this Lease:

- 1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)
- 1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)
- 1.06 RENT AND OTHER CONSIDERATION (WAREHOUSE) (OCT 2019)
- 2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)
- 2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012)
- 4.15 LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)
- 6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2018)
- 6.07 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)
- 6.13 ONSITE LESSOR MANAGEMENT (APR 2011)

~~7.03 ADDENDUM TO GSA FORM 3517B, GENERAL CLAUSES, NO FEDERALLY ELECTED OFFICIALS TO BENEFIT (OCT 2018)~~ INTENTIONALLY DELETED

7.04 SUPPLEMENTAL EQUIPMENT

The Lessor shall be responsible for the maintenance of all Government supplemental equipment in place as of the date of the Lease, including the Government's generator, supplemental HVAC units and UPS system, at Lessor's cost. The Government shall be responsible for the cost of the replacement of all Government supplemental equipment, including the generator, UPS system and supplemental equipment owned by the Government. In the event the Government elects to add additional supplemental equipment, Lessor shall be responsible for maintenance of the same but shall have the right to seek an equitable price adjustment (including a fee) if there is an increase in costs as a result of such additional maintenance.

7.05 ENHANCED ENGINEERING SERVICES

The Lessor shall provide an on-site Building Engineer during the Government's normal hours of operation established in section 6.01. Outside of the Government's normal hours of operation, the Building Engineer shall be on-call at all times. These services exceed the engineering services requirements found elsewhere in this Lease. The parties agree that the base cost of these enhanced engineering services in the first lease year is \$97,416.96, which is payable in monthly installments of \$8,118.08, in arrears. The base cost of enhanced engineering services shall be escalated by 3% annually throughout the Lease term. A schedule of the annual and monthly cost, as escalated, is outlined in paragraph 1.06, sub-paragraph L. The amounts above includes 80 hours of "overtime" on-call services per year. In the event on-call services exceed 80 hours in any given Lease year, the Lessor is eligible to claim additional compensation at the end of that Lease year based on the specific number of hours exceeded. In the event the on-call services are less than 80 hours in any given Lease year, the Government shall be eligible to claim a credit for the unused on-call hours in the form of a withhold of rent for the next period due. Lessor's additional compensation or Government's credit shall be calculated at the rate of \$97.93 per hour in the first lease year, escalating at 3% annually thereafter.

The calculation of the above charges in the first lease year is as follows:

\$136,397.81	Basic cost for full-time on-site engineer plus overhead costs
(\$54,650.40)	Typical Engineering charges (included in operating costs/shell rent)
<u>\$7,834.78</u>	Anticipated Overtime for "on-call" services (80 hours per year)
\$97,416.96	TOTAL

7.06 PROPERTY AND LEASED PREMISES CONDITION

Except as specified in Exhibit H, the Government accepts the Premises and tenant improvements in their existing condition. Lessor confirms and warrants that such existing condition complies with security improvements (except as specified in Exhibit H), Fire Protection and Life Safety requirements, ABAAS compliance, as well as compliance with all local codes and ordinances. Such acceptance by the Government of existing Premises shall not relieve Lessor of continuing obligations for cleaning, janitorial, maintenance, repair, etc. as set forth in the Lease paragraphs and attached General Clauses.

7.07 RECONCILIATION PAYMENT

The parties acknowledge that, prior to the date of this Lease, there have been ongoing negotiations related to the reconciliation of payments due and owed under lease GS-11P-LVA00543, for HVAC Services and Real Estate Tax reimbursements. The parties have agreed that, as of the date of this Lease: the Government is entitled to one time lump sum payment in the amount of \$316,730.10 (the "Settlement Total"). The Settlement Total shall be credited to the Government's benefit as an additional rental abatement. This abatement shall be applied against the rent next due after the Government's rent abatement (in Section 1.06) and commission credit (in Section 1.07) is exhausted. The Government and Lessor acknowledge and agree that the payment of the Settlement Total are intended to memorialize agreement on full and final settlement terms for those matters. The parties acknowledge that the terms of agreement have been fully investigated, negotiated, and agreed between the Government and Lessor, and that each party is relying

upon this understanding in connection with the Settlement Total. Each party hereby waives any and all claims related to the matters for which the Settlement Total has been determined.

7.08 CONSTRUCTION SCHEDULE

Notwithstanding anything to the contrary set forth in the Lease including, without limitation, Section 4.01, the parties shall meet within 10 working days of the full execution and delivery of the Lease to prepare a mutually agreed upon schedule which shall be memorialized by Lease Amendment and shall supersede the time periods set forth in this Lease.

Address 10555 Furnace Road
Lorton, Virginia
Tenant U.S. Drug Enforcement Agency
Landlord Colliers international



GOVERNMENT:
LESSOR:

Exhibit A
GSA Lease No. GS-11P-LVA00543

					USABLE AREA(S)						BASIC RENTABLE AREA(S)			RENTABLE AREA					
FLOOR	GROSS BLDG. AREA	GROSS MEASURED AREA	MAJOR VERTICAL PENETRATION	FLOOR RENTABLE AREA	SPACE I. D.	OFFICE AREA	STORE AREA	BUILDING COMMON AREA	FLOOR USABLE AREA	FLOOR COMMON AREA	FLOOR R/U RATIO	OFFICE AREA	STORE AREA	BUILDING COMMON AREA	BUILDING RENTABLE AREA	BUILDING R/U RATIO	OFFICE AREA	STORE AREA	TOTAL RENTABLE AREA
					LOADING DOCK			2642.80			0.0%								
					MAIN LOBBY			1097.65											
					MAIN ELEC. RM			627.96											
					TENANT AREA #1	15449.03						15449.05					16659.67		16659.67
					TENANT AREA #2	27442.04						27442.08					29592.50		29592.50
					TENANT AREA #3	15595.63						15595.65					16817.76		16817.76
					CORRIDOR	4723.00						4723.00					5093.11		5093.11
					RESTROOM #1			1172.40											
					RESTROOM #2			363.96											
1	70953.31	69593.26	478.69	69114.57		63209.69	0.00	5904.77	69,114.46	0	1.0000	63209.79	0.00	5904.78			68163.04	0.00	68163.04
					TENANT AREA #1	13173.55					0.0%	13173.28					14205.56		14205.56
					TENANT AREA #2	2265.30						2265.26					2442.77		2442.77
					DARK TUNNEL	2527.94						2527.88					2725.97		2725.97
					CORRIDOR	1650.12						1650.08					1779.39		1779.39
					RESTROOM #3			585.68											
2	69165.90	67655.81	47453.65	20202.16		19616.91	0.00	585.68	20,202.59	0	1.0000	19616.50	0.00	585.67			21153.69	0.00	21153.69
																7.8%			
TOTAL	140,119	137,249	47,932	89,317		82,827	0	6,490	89,317	0		82,826	0	6,490	89,317	1.0784	89,317	0	89,317

COMPUTER CALCULATED 11/11/2019 FROM FIELD VERIFICATION 10/10/2019 PER: OTJ Architects

AREA MEASUREMENTS CALCULATED PER ANSI/BOMA Z65.1-1996 APPROVED JUNE 7, 1996
BY AMERICA NATIONAL STANDARDS INSTITUTE, INC. AND PUBLISHED BY BOMA


OTJ
ARCHITECTS

10555 Furnace Road
Lorton, VA

1st Floor BOMA - Single Tenant

10/31/2019
NTS

(b) (5), (b) (7)(F)



LESSOR:


SR

GOVERNMENT:


JTB

1st Floor BOMA Building Information 11/1/2019 10:31:20 AM

OTJ
ARCHITECTS
10555 Furnace Road
Lorton, VA
1st Floor BOMA - P Lines



VERTICAL
PENETRATION
BUILDING
COMMON

LESSOR: SR GOVERNMENT: JTB

10/31/2019
NTS

OTJ
ARCHITECTS

10555 Furnace Road
Lorton, VA

2nd Floor BOMA - Single Tenant


10/31/2019
NTS

(b) (5), (b) (7)(F)

LESSOR: SR GOVERNMENT: JTB

OTJ
ARCHITECTS
10555 Furnace Road
Lorton, VA
2nd Floor BOMA - P Lines

(b) (5), (b) (7)(F)



VERTICAL
PENETRATION

BUILDING
COMMON

LESSOR: SR GOVERNMENT: STB

(b) (5), (b) (7)(F)



ENGINEERS PLANNERS SURVEYORS
LANDSCAPE ARCHITECTS GEOMATICS
VIKA VIRGINIA, LLC
8180 GREENSPRING DRIVE, SUITE 200
TYSONS, VIRGINIA 22102
PHONE: (703) 442-2780
FAX: (703) 761-2287
TYSONS, VA, GERMANTOWN, MD.

THE INFORMATION, DESIGN, AND CONTENT OF THIS DRAWING ARE PROPRIETARY AND SHALL NOT BE COPIED, DIGITALLY CONVERTED, OR USED FOR ANY PURPOSE, IN ANY FORMAT, WITHOUT PRIOR WRITTEN AUTHORIZATION FROM VIK VIRGINIA, LLC. VIOLATIONS MAY RESULT IN PROSECUTION. THIS DRAWING IS THE PROPERTY OF VIK VIRGINIA, LLC AND SHALL BE UTILIZED FOR CONSTRUCTION PURPOSES.

© 2019 VIK VIRGINIA, LLC

LESSOR:  GOVERNMENT: 

REVISIONS

REVISIONS	DATE
1.	1.
2.	2.
3.	3.
4.	4.
5.	5.
6.	6.
7.	7.
8.	8.
9.	9.
10.	10.
11.	11.
12.	12.
13.	13.
14.	14.
15.	15.
16.	16.
17.	17.
18.	18.
19.	19.
20.	20.

PROFESSIONAL SEAL

D.E.A.
TRAINING FACILITY
MOUNT VERNON DISTRICT
FAIRFAX COUNTY, VIRGINIA

SITE PLAN
VEGETATION MAP

DRAWN BY: PNL
DESIGNED BY: NRK
DATE ISSUED: 02/21/2020
DWG. 1" = 30'
VIA NO.
VIA NO.
SHEET 3

(b) (5), (b) (7)(F)

Docu



ENGINEERS PLANNERS SURVEYORS
LANDSCAPE ARCHITECTS GEOMATICS
VIKA VIRGINIA, LLC
8180 GREENWOOD DRIVE, SUITE 200
TYSONS, VIRGINIA 22102
PHONE: (703) 442-2780
FAX: (703) 761-2287
TYSONS, VA, GERMANTOWN, MD.

THE INFORMATION, DESIGN, AND CONTENT OF THIS DRAWING ARE PROPRIETARY AND SHALL NOT BE COPIED, DIGITALLY CONVERTED, OR USED FOR ANY PURPOSE, IN ANY FORMAT, WITHOUT PRIOR WRITTEN AUTHORIZATION FROM VIKA VIRGINIA, LLC. VIOLATIONS MAY RESULT IN PROSECUTION. THIS DRAWING IS THE PROPERTY OF VIKA VIRGINIA, LLC AND SHALL BE UTILIZED FOR CONSTRUCTION PURPOSES ONLY.

© 2019 VIKA VIRGINIA, LLC

LESSOR:  GOVERNMENT: 

REVISIONS

DATE

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	
11.	
12.	
13.	
14.	
15.	
16.	
17.	
18.	
19.	
20.	

PROFESSIONAL SEAL

D.E.A.
TRAINING FACILITY
MOUNT VERNON DISTRICT
FAIRFAX COUNTY, VIRGINIA

**EXISTING TREE
CONSERVATION
PLAN**

DRAWN BY: PNL
DESIGNED BY: NRK
DATE ISSUED: 02/21/2020
DWG. 1" = 30'
VIRG. NO.
VIRG. NO.
SHEET 4

(b) (5), (b) (7)(F)



ENGINEERS PLANNERS SURVEYORS
LANDSCAPE ARCHITECTS GEOMATICS
VIKA VIRGINIA, LLC
8180 GREENSPRING DRIVE, SUITE 200
TYSONS, VIRGINIA 22102
PHONE: (703) 442-2780
FAX: (703) 761-2287
TYSONS, VA, GERMANTOWN, MD.

THE INFORMATION, DESIGN, AND CONTENT OF THIS DRAWING ARE PROPRIETARY AND SHALL NOT BE COPIED, DIGITALLY CONVERTED, OR USED FOR ANY PURPOSE, IN ANY FORMAT, WITHOUT PRIOR WRITTEN AUTHORIZATION FROM VIK VIRGINIA, LLC. VIOLATIONS MAY RESULT IN PROSECUTION, AND THE USER OF THIS DRAWING SHALL BE LIABLE FOR ANY SUCH VIOLATIONS.

© 2019 VIK VIRGINIA, LLC

LESSOR: 

GOVERNMENT: 

REVISIONS

DATE

1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		
9.		
10.		
11.		
12.		
13.		
14.		
15.		
16.		
17.		
18.		
19.		
20.		

PROFESSIONAL SEAL

D.E.A.

TRAINING FACILITY

MOJUNT VERNON DISTRICT
FAIRFAX COUNTY, VIRGINIA

EXISTING TREE
CONSERVATION
INVENTORY

DRAWN BY: PNH
DESIGNED BY: NRK
DATE ISSUED: 02/21/2020
DWG. N/A
VIA V0168A
NO. 5
SHEET

(b) (5), (b) (7)(F)



ENGINEERS PLANNERS SURVEYORS
LANDSCAPE ARCHITECTS GEOMATICS
VIKA VIRGINIA, LLC
8180 GREENSPRING DRIVE, SUITE 200
TYSONS, VIRGINIA 22102
PHONE: (703) 442-2800
FAX: (703) 761-2287
TYSONS, VA, GERMANTOWN, MD.

THE INFORMATION, DESIGN, AND CONTENT OF THIS DRAWING ARE PROPRIETARY AND SHALL NOT BE COPIED, DIGITALLY CONVERTED, OR USED FOR ANY PURPOSE, IN ANY FORMAT, WITHOUT PRIOR WRITTEN AUTHORIZATION FROM VIKA VIRGINIA, LLC. VIOLATIONS MAY RESULT IN PROSECUTION. THIS DRAWING IS THE PROPERTY OF VIKA VIRGINIA, LLC AND SHALL BE UTILIZED FOR CONSTRUCTION PURPOSES ONLY.

© 2019 VIKA VIRGINIA, LLC

LESSOR:  GOVERNMENT: 

REVISIONS

REVISIONS	DATE
1.	11/11/2019
2.	11/11/2019
3.	11/11/2019
4.	11/11/2019
5.	11/11/2019
6.	11/11/2019
7.	11/11/2019
8.	11/11/2019
9.	11/11/2019
10.	11/11/2019
11.	11/11/2019
12.	11/11/2019
13.	11/11/2019
14.	11/11/2019
15.	11/11/2019
16.	11/11/2019
17.	11/11/2019
18.	11/11/2019
19.	11/11/2019
20.	11/11/2019

PROFESSIONAL SEAL

D.E.A.
TRAINING FACILITY
MOUNT VERNON DISTRICT
FAIRFAX COUNTY, VIRGINIA

**EXISTING TREE
CONSERVATION
NOTES AND
DETAILS**

DRAWN BY: PNL
DESIGNED BY: NRK
DATE ISSUED: 02/21/2020
DWG. N/A
SCALE: N/A
VIRGINIA V08168A
SHEET 6

1. UTILITY DEPICTIONS WITHIN THE AREA OF INTEREST CONFORM TO CI/ ASCE STANDARD 38-02.

- ASCE LEVEL B UTILITY DESIGNATION LEGEND:**

APW	APW	WATER MAIN - ARLINGTON PUBLIC WORKS
FW	FW	WATER MAIN - FAIRFAX WATER



① GAS RECORDS SLIGHTLY DIFFERENT THAN FIELD DESIGNATIONS

-

1. NO TITLE REPORT FURNISHED

8180 GREENSBORO DRIVE SUITE 200
TYSONS, VIRGINIA 22102
PHONE: (703) 442-7800
FAX: (703) 761-2787
TYSONS, VA

© 2019 VTKA VIRGINIA, LL

SP

REVISIONS	DATE
-----------	------

MOUNT VERNON DISTRICT
FAIRFAX COUNTY, VIRGINIA

SUBSURFACE

LEVEL B

WORKSHEET

SHEET NO. **EXH - A1**

Parking Plan and Narrative**GSA Request for Lease Proposal No. 7VA2463 ("RLP")****GSA Lorton, LLC ("Offeror")**

The site currently contains a 158 surface parking spaces (152 regular spaces and 6 handicapped spaces) that are secured within a fenced and gated perimeter and provided for the Government's exclusive use. The Offeror shall provide 42 additional surface parking spaces at Areas #1 and #2A as illustrated on the enclosed parking plan. The additional of these 42 spaces will bring the site total to 200 spaces in compliance with the RLP requirements.

The following conditions are noted regarding parking:

- 1) Notwithstanding the Offeror's intention to provide parking at the areas shown on the attached plan, the Offeror may, at its sole discretion, provide the 42 parking spaces at different locations if that is deemed to be more feasible and/or cost effective.
- 2) Parking shall be provided at the Offeror's expense and shall therefore be included for free within the fully serviced rent.
- 3) Immediately upon Lease execution the Lessor will direct its civil engineer, VIKI LLC, to conduct additional site due diligence as necessary and pursue County approval and permitting. The parties understand and agree that this permitting and approval process may take several months and, therefore, it will not be completed prior to Lease commencement.
- 4) Upon completion of the permitting process and subsequent contractor bidding, the Offeror shall commence work to expand the parking area. This work shall proceed in cooperation with the DEA. The Offeror shall coordinate this work with DEA to minimize disruption to DEA's training operations and DEA shall make all reasonable efforts to enable efficient, cost-effective and timely construction of the project. In any case, the parties agree that for some period of time, fewer than 158 spaces may be available for the DEA's use. The parties also agree that normal deliveries to the Building's loading areas may need to be re-routed during certain phases of construction.

LESSOR

SR

GOVERNMENT:

JTB



United States Department of Justice: Drug Enforcement Administration

DEA Security Statement of Work: General Security
Requirements, Specifications, and System components.

Office of Security Programs
Version: 2018/8.0

LESSOR: SR GOVERNMENT: MTB

Contents

I. GENERAL REQUIREMENTS 3

 A. Summary Of Work..... 3

 B. Systems, Warranties and Maintenance..... 3

 C. Preexisting conditions 3

 D. Location of Work 3

 E. Substitution of Equipment..... 3

 F. Coordination 3

 G. Regulatory Requirements..... 4

 H. Submittals of Material Lists, Technical Information Sheets and Variances..... 4

 I. Licenses and Permits 5

 J. Warranties 5

II. GENERAL SYSTEM SPECIFICATIONS 6

 K. Scope 6

 L. Description of the System..... 6

III. SYSTEM COMPONENTS 7

 M. General 7

 N. Closed Circuit Television 7

 O. Recording Server 8

 P. Intrusion Detection System 9

 Q. Access Control System 10

IV. Appendixes..... 12

 R. Appendix 1 12

 S. Appendix 2 12

 T. Appendix 3 12

 U. Appendix 3 13

I. GENERAL REQUIREMENTS

A. Summary Of Work

DEA Office of Security Programs will review all vendor contract proposals for technical accuracy, completeness, and suitability, and will make the final determination of selected security vendor based on the lowest acceptable bid. This summary applies to the procurement, installation, training and implementation of an integrated security management system for the site described. The contractor shall furnish a complete system including all labor, materials and equipment for a complete and functional integrated security system. Use of subcontractors and/or other vendors to install and maintain any or all of the security system(s) (other than cabling, conduit, and power) must be approved in advance by DEA Headquarters, Physical Security Section. GSA or open market pricing shall be used, whichever is more advantageous to DEA.

B. Systems, Warranties and Maintenance

The work included as specified herein and as shown on the contract drawings consists of, but is not limited to, the following:

- a. Card Access Control System
- b. Closed Circuit Television System (CCTV)
- c. Intrusion Detection System (IDS)
- d. Warranty coverage
- e. Systems tracking
- f. Submittals and shop drawings
- g. Maintenance and service support

C. Preexisting conditions

The contractor shall visit the site, check all existing conditions and be satisfied with the conditions under which the work is to be performed before submitting the project bid. No allowances shall be made for any extra expense due to the contractor's failure or neglect to discover prior conditions affecting the work, to include hardware and labor necessary to complete the work.

D. Location of Work

DEA's Office of Security Programs is looking to perform work in: _____

E. Substitution of Equipment

The substitution of equipment after bid approval will occur only when there is a significant advantage to the client agency, created by an overall upgrading of a component(s) by a manufacturer or an operational advantage created by a change in the state of the art of the equipment to be supplied. In the event the above occurs, the contractor shall make the DEA representatives aware of the new equipment and shall provide DEA the new information. At the DEA's discretion, the option to accept or reject the substitution will then be exercised.

F. Coordination

1. Project coordination. Contractor shall coordinate all project activities with the GSA project representative.

LESSOR:  GOVERNMENT: 

2. Job site administration. Contractor shall provide an onsite project manager who shall maintain coordination with the DEA and completely inform the DEA representative of project status on a weekly basis or as agreed.
3. Other trade coordination. Contractor shall closely coordinate all work with other trades. It is the contractor's responsibility to understand the scope of work of all other trades that affect the Security System to ensure that all power, cabling, networking, raceway, backboards, pull-strings, hardware, patching, painting and other services are included in the project. The contractor who delivers a fully functional Security System must supply those services not provided by other trades.

G. Regulatory Requirements

Work on or within the scope of this project shall be in accordance with but not limited to the following codes, rules and regulations.

- a. Appropriate local government codes
- b. National Electric Code (NFPA – 70)
- c. Uniform Building Code
- d. National Fire Code (NFPA - 1)

H. Submittals of Material Lists, Technical Information Sheets and Variances

1. Bidding Proposals:
 - a) When submitting a bid proposal please list the following information for each item on bid:
 - I. Item Quantity
 - II. Model Number (please use a part/model number that will allow retrieval of part information from any internet search engine).
 - III. Description : allow for an accurate description of part/device
 - i. Bad Example – 1076CG Rcsd,3/4 Dia,Stl,Dr
 - ii. Good Example – Door Contact, Recessed Steel Door Mount, 3/4" diameter.
 - IV. Price Each
 - V. Price Total (example: If there are 10 items specified for the project then this column would be the total of the Price Each column times ten).
 - VI. Labor as a separate item.
 - VII. See Appendix 1 for sample bid proposal part layout.

LESSOR:

SR

GOVERNMENT:

JTB

2. Prior to the deadline for submittals, the contractor shall submit the following:
 - a) A materials list with the names of manufacturers, model numbers, and technical information on all items proposed.
 - b) Product technical information sheets for each principal component in the proposed system and subsystem, including cable, wire and wire marking devices. The specific model number(s) must be identified within the technical information sheet (highlighted).
 - c) A statement listing every technical and operations parameter wherein the submitted equipment varies from that which was originally specified. If the contractor fails to list a particular variance and his submittal is accepted, but it is subsequently deemed to be unsatisfactory because of an unlisted variance, the contractor must replace or modify such equipment at once and without cost to the DEA.
 - d) A statement to the effect that the contractor has read and understood this statement of work and agrees to fully abide by it, as further detailed by the specific security plans to be provided by DEA.
 - e) A statement to the effect that at least one technician who has been formally trained and certified in that system will be involved in the installation and programming of every component of the overall security system.
3. Shop Drawings will be submitted to the DEA for approval prior to commencement of site work or fabrication work. These drawings shall include but not be limited to the following:
 - a) Building floor plans and site plan showing location of all devices and proposed routes for interconnecting conduits and interconnecting cable runs.
 - b) Interior elevations of each typical security cabinet, layout and all interfacing items associated with the cabinet.
 - c) Point to point wiring diagram showing quantity and type of wire used for each device. Typical manufacturer's drawings are not acceptable.
 - d) Catalog cut sheets of all equipment and devices with proposed model numbers and options highlighted or arrowed.
4. As-Built Drawings will be provided to the DEA. This will be a complete set consisting of at a minimum, the following data.
 - a) Routing of conduit and cables, including cable designations for each cable.
 - b) Accurate location of all installed equipment under the specifications using the same device and symbol legend or notations.
 - c) A complete list of equipment for each level or functional area.
 - d) Complete point-to-point wiring diagrams, including complete terminal strip layout and identification along with wire termination and tagging for all conductors.
 - e) Upon completion of the project, these drawings shall be transmitted to the attention of DEA security representative (ISP) at DEA HQ, 8701 Morrisette Dr., Springfield, VA 22152. All drawings must be submitted in hard copy and soft copy (if available).

I. Licenses and Permits

The contractor shall at the time of the proposals be fully licensed to perform all specific tasks by the local authority at the job location. The licensing may include but not be limited to a valid state Electrical Contractor, Low Voltage System Contractor, Alarm Operator and local business license.

CONTRACTORS THAT PRIMARILY OPERATE AS EQUIPMENT DISTRIBUTERS ARE RESTRICTED FROM BIDDING.

J. Warranties

1. The contractor shall guarantee all equipment and systems for a period of one year commencing with the acceptance of the security systems as fully functional by the DEA. The warranty shall cover all costs for the warranty service, including parts, labor, field service, pickup, transportation, delivery, and reinstallation and retesting.

LESSOR:  GOVERNMENT: 

2. Requests for non-emergency service placed by the owner/occupant by 10:00AM Monday through Friday shall be responded to before 5:00PM that day. Non-emergency items are those that do not secure the perimeter or high security areas.
3. Emergency Service Requests will be met within a four (4) hour reporting window. If the criteria for an emergency is not met (failure of a perimeter or high security room securing device) the billing will go to the DEA.

II. GENERAL SYSTEM SPECIFICATIONS

K. Scope

The selected contractor shall install and make operational a fully functional security system that will incorporate Closed Circuit Television (CCTV), an Intrusion Detection System (IDS), and a proximity card based Access Control System (ACS). The security system must have the ability to be remotely accessed by other field locations through a network, modem or another form of communication. The system shall be Underwriters Laboratory (UL) rated. The IDS shall be monitored by the appropriate Federal Protective Service (FPS) Megacenter Monitoring Station. Installation of cabling equipment, testing and training associated with the security system shall be included. Work shall be coordinated with the General Contractor and other Sub Contractors to meet the intended construction schedule. Under normal circumstances it is required that the system will be operated at least one week before occupying the space. Vendor will provide 8 hours of user training, along with user manuals, software, and keys (as appropriate) for all systems.

L. Description of the System

The security system shall be comprised of CCTV, ACS and IDS devices, positioned approximately as shown on security plans to be provided by DEA. The CCTV system shall be comprised of both fixed and pan-tilt zoom, color, indoor and outdoor, vandal resistant IP based cameras; will be recorded by Milestone XProtect Corporate software running on one or more computers; with video distribution to flat screen monitors throughout the facility, managed by a central computer located elsewhere. The ACS shall be comprised of FIPS-201/HSPD-12 compliant, Software House iStar panels with multi-technology (both PIV and standard Wiegand 26 bit) proximity card readers; which will release electronic locks and/or strikes as well as vehicle gates; will interact with a videophone visitor announcement system; and must be managed by a Software House CCure-9000 networked system, with a central computer located elsewhere. The IDS shall be comprised of DMP XR-500 (or better) panels and keypads with multiple alarm groups; connected via telephone lines with a backup cellular communicator in case of line or communication failure; which will be monitored by the appropriate FPS Megacenter; with zone shunt keypads located inside the protected zones; where each user has a separate code; where users can arm, but not disarm, the entire system from one of the perimeter keypads; where each zone is protected by both motion sensors and balanced magnetic switch (BMS) door contacts, and possibly glass break sensors.

LESSOR:

SR

GOVERNMENT:

JTB

III. SYSTEM COMPONENTS

M. General

All devices, wire and equipment shall be listed by the Underwriters Laboratory or be Factory Mutual approved. Devices will be installed in full accordance with UL and manufacturer's installation guides and requirements. All systems must be fully functional at the time of acceptance testing. All external cabling will be exterior grade and run through exterior grade conduit.

The Video Management System shall be installed by a Milestone Certified Gold Partner or higher. Installation technician(s) will be Milestone Certified in accordance with all vendor specified installation requirements. Technician(s) performing installation, programming and end-user system training will be Milestone Certified on the current version of XProtect Corporate DEA is utilizing. Contractors that primarily operate as equipment distributors are restricted from bidding. The Contractor is to provide certificates of certification to the DEA Security Representative prior to installation.

N. Closed Circuit Television

1. The camera specified shall be designed for surveillance and industrial applications. The camera shall be high resolution, fully automatic, color camera capable of providing high resolution video over an IP LAN/WAN network.
 - a) The camera shall be fully supported by the current Milestone XProtect™ *Corporate* Video Device Driver Package.
 - b) The camera shall be edge storage capable
 - i. A removable storage device with a capacity matching the maximum allowed by the specific camera model will be provided with each device.
 - c) The camera shall, at minimum, support HD 720P resolution.
 - d) The camera shall, at minimum, be capable of providing a H.264 video stream 30 frames per second.
 - e) The camera encoding rate shall be selectable from 1 to 30 frames per second in all resolutions.
 - f) The camera must be capable of providing an RTSP video stream (such as AXIS P33 series cameras).
 - g) The camera shall be designed to support power over the Ethernet (PoE) using UTP Category 5e or Cat 6 with RJ45 connectors when an IEEE802.3af compliant switch is utilized.
 - h) The camera must be capable of performing upgrades, such as the firmware, through web browser without the use of additional software applications.
2. The contractor, based on the site visit, Security Plans and evaluated by the DEA, will submit proposed lens selection for each camera for written acceptance.
3. Camera housings in the interior of the facility shall be ceiling mount type housings, which will match the general design of the building. All camera housings will entirely enclose wiring and cameras and be tamper proof.
4. Exterior cameras may be either dome or other environmental housing which suits the general appearance of the facility and appropriate to local weather conditions. All housings will entirely enclose wiring and cameras and be tamper proof. All exterior CCTV camera transmission lines must protect against lightning and other related power surges.

LESSOR:

SR

GOVERNMENT:

JTB

5. Cabling will be Category 5e or Category 6. All necessary networking devices, particularly power-over-ethernet switches, must be included. The only acceptable switches are: Cisco WS-3850-24P-E, Cisco WS-3850-48P-E.
6. Video Decoders are required to allow for each security monitors within the office (see Security Plan). Video monitors shall be 32" or larger color, flat panel televisions with the capability to support the resolution from the cameras, which equates to HD720P or better. All monitors shall be wall mounted adjacent to the ceiling to provide the best viewing by the primary users while protecting the view within the protected space. All monitors shall be provided with a video decoding unit. The video decoding units will be mounted behind each security monitor. Acceptable equipment is the ACTi ECD-1000-G. Video decoding units will be directly connected to each security monitor using a HDMI 1.4a cable or better. Projects with more than 4 individual security monitors require additional equipment. Please contact DEA/ISPS to discuss current equipment standards.
7. All power requirements for the equipment shall be coordinated with the electrical contractor on site. All breakers shall be marked and if dedicated circuits are required the security contractor is responsible for interfacing with the electrical contractor for the requisite circuits.
8. The computer and networking equipment must be protected from power spikes and brief power failures by an Uninterrupted Power Supply (UPS). The UPS should provide approximately 15 minutes of runtime at half load and should be rack mountable.

O. Recording Server

The Recording Server(s) shall be used for recording video feeds and for communicating with cameras and other devices. The Recording Server(s) shall communicate via network with the Management Server at another location.

1. Contractor is to provide and install any necessary Milestone XProtect software and drivers for the system to function (available freely from Milestone). The Recording Server(s) is (are) to be provided by the contractor. All Recording Servers should be provided with a two post conversion kit for a 4U chassis (2POST-4UKIT). DEA strongly recommends "App-Techs" as a provider of Milestone XProtect video recording computers. (Provide site reference, camera quantity and ask for DEA Configuration).
- 2.
3. Contractor is to procure and provide to DEA a number of XProtect Corporate device licenses sufficient to handle all the video feeds of the system. Contractor must coordinate with Milestone Systems Representative Walter Coady (wjc@milestone.us / 503-350-1119) for all licensing issues. All device licenses must be added to existing DEA Software License Code (SLC). Confirmation from Milestone that the device licenses were added to the existing DEA SLC is required.
- 4.
5. The Recording Servers, once configured, shall run independently of the Management Server, and continue to operate in the event that the Management Server is offline.
6. The following are the minimum requirements for the computer(s) running the Recording Server application.
 - a) CPU – Minimum Intel® Core i5, Quad-Core, 2.8GHZ processor or better (more powerful CPU recommended for Client Viewer running higher numbers of cameras).
 - b) RAM – Minimum of 8 GB.
 - c) Network – Minimum 2 gigabit network ports.
 - d) Graphics Adapter – Minimum 1280x1024 (2560 x 1600 max), 1 HDMI, 2 DVI.
 - e) Hard Disk Space (minimum) – OS: 80GB+, Live: 200GB+, Archive: 6TB on (2) 3TB drives+.
 - f) Hard Disk Drive Configuration – RAID 5

LESSOR:



GOVERNMENT:



- g) Operating System – Windows 7 Enterprise 64 bit. Software – Microsoft .NET 4.0. DirectX 9.0 or newer. Microsoft Internet Explorer 7.0 or newer.
 - h) Software – Microsoft .NET 4.0. DirectX 9.0 or newer. Microsoft Internet Explorer 7.0 or newer.
- 7. The Recording Server will record for a thirty day period or more, 24 Hours a Day. Motion should be anticipated at 40%. Storage calculations should be based upon a 1.3 Megapixel Camera at 1280 x 1024 resolution with a constant frame rate of 15KB and an average image size 30 KB.
 - 8. Each Recording Server shall have a default storage area. The default storage area will be a dedicated Hard Disk Drive. A storage area is a directory where the database content, primarily recordings from the connected cameras is stored. Recordings from the connected cameras shall be stored in individual camera databases. The system shall allow an unlimited amount of storage to be allocated for each connected device. The system shall have multiple, physically different, direct attached hard drives: Operating System, Live Database, and one or more Archive drives.
 - 9. The Recording Server shall utilize high performance, direct attached SATA or SAS 15K RPM (or better) disk drives for live recording storage, formatted with 64KB clusters. Live database array type JBOD. Use of tape-backup systems shall not be acceptable.
 - 10. The system shall allow archiving to be enabled on a per camera basis and allow the user to define which archiving drive shall be used for each camera. The Hard Disk Drive storing the Archive Database will be direct attached, SATA 7.2K RPM (or better), formatted with 64KB clusters. Archive database array type JBOD.
 - 11. An independent SATA or SAS 7.2K RPM (or better) Hard Disk Drive (or SSD drive) will be provided for the Operating System and Application Volume. It will not be used for the Live or Archive Database. OS/Application volume type JBOD.
 - 12. The Recording Server(s) shall have multiple Network Interface Cards (NIC) and support connection to the cameras on a network separate from the Client Viewer, Management Server and System Manager.
 - 13. The Recording Server shall have the ability to accept the full frame rate supplied by the cameras, while recording a lower frame rate, yet still make the higher frame rate available to the Clients for live viewing.
 - 14. The computer and networking equipment must be protected from power spikes and brief power failures by an Uninterrupted Power Supply (UPS). The UPS should provide approximately 15 minutes of runtime at half load and should be rack mountable in a standard two post, 7'Hx19"W racks provided by the Government.
 - 15. The computer must be provided with LCD monitor or short depth rack mount LCD monitor keyboard drawer.
 - 16. Provide floor standing mini rack cabinet.
 - 17. Contractor is to program the system, and instruct the designated DEA personnel how to perform all necessary and usual functions of the full and completed video system.

P. Intrusion Detection System

- 1. DEA will design the Intrusion Detection System (IDS) to be installed to protect DEA facilities. IDS will be a DMP (XR-500 or better) based system, compatible with FPS Megacenter monitoring. Bosch, Radionics or Ademco based systems are acceptable, but DMP is greatly preferred. Contractor is to assist DEA and the FPS Megacenter with programming the system. Contractor is to instruct the designated DEA personnel how to perform all necessary and usual functions of the IDS.
- 2. IDS installed to protect DEA facilities will meet the requirements of Interim Federal Specifications W-A-00450B (GSA/FFS). These requirements will be cited on all contracts and purchase orders. All components comprising the IDS will comply with applicable UL Standards (UL 611, 681, 1076 and 2050 apply).
- 3. The transmission link between the central monitoring station and the protected facility will be electronically supervised. Additionally the supervisory loop among alarm sensors and the Premise Control Unit (PCU) will be supervised. This line supervision refers to systems in which the

LESSOR:  GOVERNMENT: 

transmission is based on pseudo-random generated tones or digital encoding using an interrogation and response polling scheme throughout the entire communications, or UL Class AA line supervisions (UL Standard 611). The signal shall not repeat itself within a minimum six-month period. This line supervision shall be impervious to compromise using impedance matching resistance or potential (voltage) current substitution, signal substitution techniques or any single compromise attempt. This requires that more than one (1) form of line supervision is provided (UL) Standard 611 (Grade AA Service). The second means of communication shall be wireless (preferably cellular based, either Telguard or DMP) system, which alerts/activates on both line and communications failure. Contractor must assist DEA in setting up an appropriate communications service so that the wireless communicator can communicate with the FPS Megacenter.

4. All alarm sensors and panels will be equipped with tamper switches placed on a 24 hour alarmed partition to advise of unauthorized entry or manipulation.
5. UL Approved Premise Control Units (PCU) alarm processors associated with DEA intrusion detection systems will be furnished with an emergency power supply. Emergency Power must comply with UL 603 and will be a rechargeable battery and/or generator capable of sustaining systems operation for a minimum of 24 hours in the event of a commercial power outage. When batteries are used for emergency power, they will be maintained at full charge by automatic charging circuits. Switchover from line to battery power will be automatic and instantaneous. A conspicuously visible indicator on the control unit will be actuated to signal a change in state and the consequent mode of operation. The PCU will be protected from power spikes by a circuit breaker or replaceable fuse.
6. Zone shunt (access/secure) keypads associated with DEA multi-zoned systems will be installed within the perimeter of the protected zones. The keypads will provide an alarm delay of sufficient duration to permit legitimate access and egress by authorized personnel. Perimeter keypads must have the ability to arm, but not disarm all groups at once. Otherwise, only the keypads physically present inside an area protected by a group will be able to arm or disarm that group (normally one keypad per group other than the perimeter).
7. Intrusion detection systems installed within DEA facilities will provide the following protection:
 - a) Triple biased balanced magnetic contacts will be installed on the **interior** side of all perimeter doors and secure rooms as designated by DEA representatives. These contacts must be properly installed, parallel to each other, not perpendicular. Installation may require the use of "L" or "Z" brackets to achieve parallel installation.
 - b) Dual technology, Passive Infrared (PIR), 360 degree motion detectors will be installed within the secure areas unless otherwise directed.
 - c) Glass break detector will be continuously active (24/7). Where glass break detectors are present in a DEA facility, a test device must be present for initial system testing, and remain on-site for future testing.
 - d) Duress, hold up type alarms will provide both local signaling (strobe lights with sounders strategically placed within the office space) and remote annunciation within the central station monitoring the system. Local signaling will be neither audible nor visible from the "SECURE ENTRANCE/RECEPTION AREA". Sounders will in no case be louder than 95dB.
 - e) The placement of intrusion detection system motion sensors will be determined through an on-site inspection of the facility by representatives of the DEA Office of Security Programs, but should be approximately as shown in the DEA provided security plans.
8. Intrusion detection systems installed within DEA office space **must** be compatible with FPS Megacenter Monitoring Center covering the office area. Vendor must insure, with the assistance of DEA, that the system is properly programmed, functional, and being monitored.

Q. Access Control System

1. The access control system shall be a Software House based HSPD-12/FIPS-201 compliant system. The iStar Panel will be controlled over a network by a Software House C-Cure 9000 server located elsewhere. Both proximity ID access cards and government PIV cards will be used to actuate the door release function. Contractor shall provide, activate, and program 100 proximity cards for initial system use and testing (10 all access, 90 perimeter only), in addition to programming the PIV cards of the personnel at the facility. Contractor shall install the CCure 9000 client software on the

LESSOR:

SR

GOVERNMENT:

JTB

Milestone recording server to program the Software House system. Contractor will program the system, and instruct the designated DEA personnel how to perform all necessary and usual functions with the CCure-9000 system.

2. All alerts generated shall go directly to the client and server for evaluation. A screen with the information and appropriate evaluation and response criteria shall be illustrated at that time to assist with the incident.
3. There shall be battery power back up for the system for a minimum of 24 hours. This system shall have the ability to operate without the PC or network if a problem occurs. Information will be loaded into a buffer until it can be displayed or enacted. Buffer overload must not cause the system to fail. The ACS panels will be protected from power spikes and failures through an uninterruptible power supply.
4. The system must have instant response to Card read or keypad entry regardless of system size.
5. The processing power shall be distributed throughout the system to intelligent controllers. The processing must occur at each controller to provide a much more secure system.
6. The receptionist's area will normally have a master video Aiphone. Sub-master and door unit Aiphones will also be designated on the drawing. The Aiphone system must communicate with the ACS to, at a minimum, shunt appropriate door contacts when a door is released.
7. Some doors with proximity readers shall have a PIR request to exit (REX) device to shunt the access system upon openings. See attached design for specific locations. Under no circumstances will a REX release an electric strike. Electric strikes must fail secure unless otherwise specified by DEA. Card readers on perimeter doors will normally also have PIN keypads (see the DEA security plans for details).
8. Contractor must be capable of providing initial system programming at the time of installation. Technicians who program the system must be formally trained and certified by Software house to work on CCure 9000 systems. Network and telephone connectivity are to be provided by DEA or other vendors, but connectivity at time of installation cannot be guaranteed in advance. Contractor must make connections to the DEA provided network, which may be physically remote from the ACS panels. Card readers may require flash programming cards to enable proper PIV reading functions. All panels and card readers must be updated to the latest firmware at the time of installation.
9. Magnetic locks will not be used except as explicitly stated on DEA provided security plans. Where present, magnetic locks must meet fire code standards for installation and function. Furthermore, each magnetic lock must be equipped with a power interrupting, high security (UL-437) keybox (outside) with momentary override button (inside). Magnetic locks shall never receive battery power.
10. Vehicle gates shall be controlled by the ACS using proximity card readers for entry, and a sensing device (ground loop, unidirectional motion sensor, etc.) for exit. The gate operator must be on the protected side of any fencing or other physical barrier. The gate operator must have pushbutton operation, not accessible from the unprotected side of any fencing. Gates and operators must be appropriate for the size, location, and environmental conditions at the site.

LESSOR:


SR

GOVERNMENT:


JTB

IV. Appendixes

R. Appendix 1

Quantity	Model	Manufacturer	Description	Each	Total
2	1076CG	Big Company	Door Contact, Recessed Steel, Door Mount, ¾ inch diameter	\$7.63	\$15.26
12	RE-24L	Little Company	Form C Door Release, 24V DC Input	\$14.96	\$179.52
1	AX-084C	Medium Company	Central Exchange Unit for 8 door and 4 masters	\$892.64	892.64
1	Labor	Contractor	Installation, programming, and testing	\$12,000	\$12,000

S. Appendix 2

1. Deadbolt and other locks as specified on the DEA provided security plans must be high security (UL-437), grade 1 locks. Acceptable models include Schlage Everest Primus XP (B800 series) and Medeco3 Maxum.
2. High security locks and cylinders shall never be master keyed. Standard grade locks shall be master keyed.
3. Neither the contractor nor the lessor shall retain any keys to the DEA facility or spaces. All keys to DEA spaces shall be delivered to DEA.
4. DEA will provide the functional descriptions of doors and locks as part of the security plan. DEA will also specify keying schedules and number of keys to be provided.
5. Where possible, the deadbolt and keyset functions shall be combined into a single lockset with a high security cylinder.
6. Any door with an electric strike shall be secured by a heavy duty automatic closer and a storeroom lockset.
7. Select doors may be specified as requiring soundproofing sweeps and seals. These shall provide a complete, 360° seal between the door and frame. These doors must still fully close solely by the function of an automatic closer. These doors will be tested, and are expected to meet the standard of STC-45 (normal conversations can be detected but not understood). Helpful hint: If light can be seen around/under a closed door, it is not properly soundproofed.
8. All locks must function smoothly and properly. All doors must close smoothly and completely.
9. Perimeter and certain other doors will be specified as requiring pinned hinges. At least two of the hinges on these doors (topmost and bottommost) must be of a visibly secure type.

T. Appendix 3

1. DEA requires secure parking areas for government owned vehicles and certain other vehicles. Secure parking areas are fenced and gated to prevent unauthorized personnel and vehicles from entering the secured area.
2. DEA will work with the lessor, architect and others to design an acceptable security plan for the facility, grounds, and parking areas.


LESSOR:

SR

GOVERNMENT:

JTB

U. Appendix 3



SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL III

THESE PARAGRAPHS CONTAIN ADDITIONAL SECURITY REQUIREMENTS THAT MAY BE INSTALLED IN THE LEASED SPACE, AND UNLESS INDICATED OTHERWISE, ARE TO BE PRICED AS PART OF THE BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC). BECAUSE EACH BUILDING IS UNIQUE, THE FINAL LIST OF SECURITY COUNTERMEASURES WILL BE DETERMINED DURING THE DESIGN PHASE AND IDENTIFIED IN THE DESIGN INTENT DRAWINGS AND CONSTRUCTION DOCUMENTS. AFTER COMPLETING THE CONSTRUCTION DOCUMENTS, THE LESSOR SHALL SUBMIT A LIST OF THE ITEMIZED COSTS. SUCH COSTS SHALL BE SUBJECT TO NEGOTIATION.

WHERE THEY ARE IN CONFLICT WITH ANY OTHER REQUIREMENTS OF THIS LEASE, THE STRICTEST SHALL APPLY.


DEFINITIONS:

CRITICAL AREAS AND SYSTEMS- The areas that house systems that if damaged and/or compromised could have significant adverse consequences for the facility, operation of the facility, or mission of the agency or its occupants and visitors. These areas may also be referred to as "limited access areas," "restricted areas," or "exclusionary zones." Critical areas do not necessarily have to be within Government-controlled Space (e.g., generators, air handlers, electrical feeds, utilities, telecom closets or potable water supply that may be located outside Government-controlled Space).

SENSITIVE AREAS – Sensitive areas include vaults, SCIFs, evidence rooms, war rooms, and sensitive documents areas. Sensitive areas are primarily housed within Government-controlled space.


FACILITY ENTRANCES, LOBBY, COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR: SR GOVERNMENT: MTB

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR: SR GOVERNMENT: MTB

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)




LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)



LESSOR:  GOVERNMENT: 

(b) (5), (b) (7)(F)



LESSOR:  GOVERNMENT: 

LESSOR'S ANNUAL COST STATEMENT*Important - Read attached "Instructions"***OMB Control Number: 3090-0086****Expiration Date: 11/30/2019**

Paperwork Reduction Act Statement - This information collection meets the requirements of 44 U.S.C. § 3507, as amended by section 2 of the Paperwork Reduction Act of 1995. You do not need to answer these questions unless we display a valid Office of Management and Budget (OMB) control number. The OMB control number for this collection is 3090-0086. We estimate that it will take 2 hours to read the instructions, gather the facts, and answer the questions. Send only comments relating to our time estimate, including suggestions for reducing this burden, or any other aspects of this collection of information to: U.S. General Services Administration, Regulatory Secretariat Division (M1V1CB), 1800 F Street, NW, Washington, DC 20405.

1. Request for Lease Proposals (RLP)

7VA2463

2. Statement Date

05-14-2020

3. Rental Area (Square Feet)

3A. Entire Building

89,317

3B. Leased by Government

89,317

4. Building Name and Address (*Number, Street, City, State, and Zip Code*)

Gunston Commerce Center
10555 Furnace Road
Lorton, VA 22079-2616

**SECTION I - ESTIMATED ANNUAL COST OF SERVICES AND UTILITIES
FURNISHED BY LESSOR AS PART OF RENTAL CONSIDERATION**

SERVICES AND UTILITIES	LESSOR'S ANNUAL COST FOR		FOR GOVERNMENT USE ONLY
	(a) Entire Building	(b) Government-Leased Area	
A. CLEANING, JANITOR AND/OR CHAR SERVICE			
5. Salaries			
6. Supplies (<i>Wax, cleaners, cloths, etc.</i>)	(b) (4)		
7. Contract Services (<i>Window washing, waste and snow removal</i>)	(b) (4)		
B. HEATING			
8. Salaries			
9. Fuel ("X" one) <input type="checkbox"/> Oil <input type="checkbox"/> Gas <input type="checkbox"/> Coal <input type="checkbox"/> Electric	(b) (4)		
10. System Maintenance and Repair	(b) (4)		
C. ELECTRICAL			
11. Current for Light and Power	(b) (4)		
12. Replacement of Bu bs, Tires, Starters	(b) (4)		
13. Power for Special Equipment			
14. System Maintenance and Repair (<i>Ballasts, Fixtures, etc.</i>)	(b) (4)		
D. PLUMBING			
15. Water (<i>For all purposes</i>) (<i>Include Sewage Charges</i>)	(b) (4)		
16. Supplies (<i>Soap, towels, tissues not in 6 above</i>)	(b) (4)		
17. System Maintenance and Repair	(b) (4)		
E. AIR CONDITIONING			
18. Utilities (<i>Include electricity, if not in C11</i>)			
19. System Maintenance and Repair	(b) (4)		
F. ELEVATORS			
20. Salaries (<i>Operators, starters, etc.</i>)			
21. System Maintenance and Repair	(b) (4)		

GENERAL SERVICES ADMINISTRATION**GSA 1217 (REV. 11/2016)**

LESSOR:

SR

GOVERNMENT:

JTB

G. MISCELLANEOUS (To the extent not included on Page 1)			
22. Building Engineer and/or Manager			
23. Security (<i>Watchperson, guards, not janitors</i>)	(b) (4)		
24. Social Security Tax and Workperson's Compensation Insurance			
25. Lawn and Landscaping Maintenance	(b) (4)		
26. Other (<i>Explain on separate sheet</i>)			
27. TOTAL	(b) (4)		

SECTION II - ESTIMATED ANNUAL COST OF OWNERSHIP EXCLUSIVE OF CAPITAL CHARGES


28. Real Estate Taxes	(b) (4)		
29. Insurance (<i>Hazard, Liability, etc.</i>)	(b) (4)		
30. Building Maintenance and Reserves for Replacement			
31. Lease Commission			
32. Management	(b) (4)		
33. TOTAL	(b) (4)	(b) (4)	

LESSOR'S CERTIFICATION - The amounts entered in Columns (a) and (b) represent my best estimate as to the annual costs of services, utilities, and ownership.

34. Signature of:

☐ Owner

☐ Legal Agent

TYPED NAME AND TITLE	SIGNATURE	DATE
34A. Steve Riley Authorized Signatory	34B.  D834E5059BBB470...	34C. 4/16/2021
35A.	35B.	35C.

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

GENERAL CLAUSES
(Acquisition of Leasehold Interests in Real Property)

CATEGORY	CLAUSE NO.	48 CFR REF.	CLAUSE TITLE
GENERAL	1		SUBLETTING AND ASSIGNMENT
	2	552.270-11	SUCCESSORS BOUND
	3	552.270-23	SUBORDINATION, NON-DISTURBANCE AND ATTORNMEN
	4	552.270-24	STATEMENT OF LEASE
	5	552.270-25	SUBSTITUTION OF TENANT AGENCY
	6	552.270-26	NO WAIVER
	7		INTEGRATED AGREEMENT
	8	552.270-28	MUTUALITY OF OBLIGATION
PERFORMANCE	9		DELIVERY AND CONDITION
	10		DEFAULT BY LESSOR
	11	552.270-19	PROGRESSIVE OCCUPANCY
	12		MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT
	13		FIRE AND CASUALTY DAMAGE
	14		COMPLIANCE WITH APPLICABLE LAW
	15	552.270-12	ALTERATIONS
	16		ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY
PAYMENT	17	552.270-33	SYSTEM FOR AWARD MANAGEMENT - LEASING
	18	52.204-13	SYSTEM FOR AWARD MANAGEMENT MAINTENANCE
	19	552.270-31	PROMPT PAYMENT
	20	52.232-23	ASSIGNMENT OF CLAIMS
	21		PAYMENT
	22	52.232-33	PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT
STANDARDS OF CONDUCT	23	52.203-13	CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT
	24	552.270-32	COVENANT AGAINST CONTINGENT FEES
	25	52-203-7	ANTI-KICKBACK PROCEDURES
	26	52-223-6	DRUG-FREE WORKPLACE
	27	52.203-14	DISPLAY OF HOTLINE POSTER(S)
ADJUSTMENTS	28	552.270-30	PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY
	29	52.215-10	PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA
	30	552.270-13	PROPOSALS FOR ADJUSTMENT
	31		CHANGES
AUDITS	32	552.215-70	EXAMINATION OF RECORDS BY GSA
	33	52.215-2	AUDIT AND RECORDS—NEGOTIATION

LESSOR:

SR

GOVERNMENT:

JTB

Exhibit G**GSA Lease No. GS-11P-LVA00543**

DISPUTES	34	52.233-1	DISPUTES
LABOR STANDARDS	35	52.222-26	EQUAL OPPORTUNITY
	36	52.222-21	PROHIBITION OF SEGREGATED FACILITIES
	37	52.219-28	POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION
	38	52.222-35	EQUAL OPPORTUNITY FOR VETERANS
	39	52.222-36	EQUAL OPPORTUNITY FOR WORKERS WITH DISABILITIES
	40	52.222-37	EMPLOYMENT REPORTS ON VETERANS
SUBCONTRACTING	41	52.209-6	PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT
	42	52.215-12	SUBCONTRACTOR CERTIFIED COST OR PRICING DATA
	43	52.219-8	UTILIZATION OF SMALL BUSINESS CONCERNS
	44	52.219-9	SMALL BUSINESS SUBCONTRACTING PLAN
	45	52.219-16	LIQUIDATED DAMAGES—SUBCONTRACTING PLAN
	46	52.204-10	REPORTING EXECUTIVE COMPENSATION AND FIRST- TIER SUBCONTRACT AWARDS
OTHER	47	52.204-25	PROHIBITION ON CONTRACTING FOR CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT
	48	52.204-19	INCORPORATION BY REFERENCE OF REPRESENTATIONS AND CERTIFICATIONS

The information collection requirements contained in this solicitation/contract that are not required by regulation have been approved by the Office of Management and Budget (OMB) pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

LESSOR:

SR

GOVERNMENT:

JTB

GENERAL CLAUSES
(Acquisition of Leasehold Interests in Real Property)

1. SUBLETTING AND ASSIGNMENT (JAN 2011)

The Government may sublet any part of the premises but shall not be relieved from any obligations under this lease by reason of any such subletting. The Government may at any time assign this lease, and be relieved from all obligations to Lessor under this lease excepting only unpaid rent and other liabilities, if any, that have accrued to the date of said assignment. Any subletting or assignment shall be subject to prior written consent of Lessor, which shall not be unreasonably withheld.

2. 552.270-11 SUCCESSORS BOUND (SEP 1999)

This lease shall bind, and inure to the benefit of, the parties and their respective heirs, executors, administrators, successors, and assigns.

3. 552.270-23 SUBORDINATION, NON-DISTURBANCE AND ATTORNMENT (SEP 1999)

(a) Lessor warrants that it holds such title to or other interest in the premises and other property as is necessary to the Government's access to the premises and full use and enjoyment thereof in accordance with the provisions of this lease. Government agrees, in consideration of the warranties and conditions set forth in this clause, that this lease is subject and subordinate to any and all recorded mortgages, deeds of trust and other liens now or hereafter existing or imposed upon the premises, and to any renewal, modification or extension thereof. It is the intention of the parties that this provision shall be self-operative and that no further instrument shall be required to effect the present or subsequent subordination of this lease. Government agrees, however, within twenty (20) business days next following the Contracting Officer's receipt of a written demand, to execute such instruments as Lessor may reasonably request to evidence further the subordination of this lease to any existing or future mortgage, deed of trust or other security interest pertaining to the premises, and to any water, sewer or access easement necessary or desirable to serve the premises or adjoining property owned in whole or in part by Lessor if such easement does not interfere with the full enjoyment of any right granted the Government under this lease.

(b) No such subordination, to either existing or future mortgages, deeds of trust or other lien or security instrument shall operate to affect adversely any right of the Government under this lease so long as the Government is not in default under this lease. Lessor will include in any future mortgage, deed of trust or other security instrument to which this lease becomes subordinate, or in a separate non-disturbance agreement, a provision to the foregoing effect. Lessor warrants that the holders of all notes or other obligations secured by existing mortgages, deeds of trust or other security instruments have consented to the provisions of this clause, and agrees to provide true copies of all such consents to the Contracting Officer promptly upon demand.

(c) In the event of any sale of the premises or any portion thereof by foreclosure of the lien of any such mortgage, deed of trust or other security instrument, or the giving of a deed in lieu of foreclosure, the Government will be deemed to have attorned to any purchaser, purchasers, transferee or transferees of the premises or any portion thereof and its or their successors and assigns, and any such purchasers and transferees will be deemed to have assumed all obligations of the Lessor under this lease, so as to establish direct privity of estate and contract between Government and such purchasers or transferees, with the same force, effect and relative priority in time and right as if the lease had initially been entered into between such purchasers or transferees and the Government; provided, further, that the Contracting Officer and such purchasers or transferees shall, with reasonable promptness following any such sale or deed delivery in lieu of foreclosure, execute all such revisions to this lease, or other writings, as shall be necessary to document the foregoing relationship.

(d) None of the foregoing provisions may be deemed or construed to imply a waiver of the Government's rights as a sovereign.

LESSOR:



GOVERNMENT:



4. 552.270-24 STATEMENT OF LEASE (SEP 1999)

(a) The Contracting Officer will, within thirty (30) days next following the Contracting Officer's receipt of a joint written request from Lessor and a prospective lender or purchaser of the building, execute and deliver to Lessor a letter stating that the same is issued subject to the conditions stated in this clause and, if such is the case, that (1) the lease is in full force and effect; (2) the date to which the rent and other charges have been paid in advance, if any; and (3) whether any notice of default has been issued.

(b) Letters issued pursuant to this clause are subject to the following conditions:

(1) That they are based solely upon a reasonably diligent review of the Contracting Officer's lease file as of the date of issuance;

(2) That the Government shall not be held liable because of any defect in or condition of the premises or building;

(3) That the Contracting Officer does not warrant or represent that the premises or building comply with applicable Federal, State and local law; and

(4) That the Lessor, and each prospective lender and purchaser are deemed to have constructive notice of such facts as would be ascertainable by reasonable pre-purchase and pre-commitment inspection of the Premises and Building and by inquiry to appropriate Federal, State and local Government officials.

5. 552.270-25 SUBSTITUTION OF TENANT AGENCY (SEP 1999)

The Government may, at any time and from time to time, substitute any Government agency or agencies for the Government agency or agencies, if any, named in the lease.

6. 552.270-26 NO WAIVER (SEP 1999)

No failure by either party to insist upon the strict performance of any provision of this lease or to exercise any right or remedy consequent upon a breach thereof, and no acceptance of full or partial rent or other performance by either party during the continuance of any such breach shall constitute a waiver of any such breach of such provision.

7. INTEGRATED AGREEMENT (JUN 2012)

This Lease, upon execution, contains the entire agreement of the parties and no prior written or oral agreement, express or implied, shall be admissible to contradict the provisions of the Lease. Except as expressly attached to and made a part of the Lease, neither the Request for Lease Proposals nor any pre-award communications by either party shall be incorporated in the Lease.

8. 552.270-28 MUTUALITY OF OBLIGATION (SEP 1999)

The obligations and covenants of the Lessor, and the Government's obligation to pay rent and other Government obligations and covenants, arising under or related to this Lease, are interdependent. The Government may, upon issuance of and delivery to Lessor of a final decision asserting a claim against Lessor, set off such claim, in whole or in part, as against any payment or payments then or thereafter due the Lessor under this lease. No setoff pursuant to this clause shall constitute a breach by the Government of this lease.

9. DELIVERY AND CONDITION (JAN 2011)

(a) Unless the Government elects to have the space occupied in increments, the space must be delivered ready for occupancy as a complete unit.

(b) The Government may elect to accept the Space notwithstanding the Lessor's failure to deliver the Space substantially complete; if the Government so elects, it may reduce the rent payments.

LESSOR:



GOVERNMENT:



10. DEFAULT BY LESSOR (APR 2012)

(a) The following conditions shall constitute default by the Lessor, and shall give rise to the following rights and remedies for the Government:

(1) Prior to Acceptance of the Premises. Failure by the Lessor to diligently perform all obligations required for Acceptance of the Space within the times specified, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may terminate the Lease on account of the Lessor's default.

(2) After Acceptance of the Premises. Failure by the Lessor to perform any service, to provide any item, or satisfy any requirement of this Lease, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may perform the service, provide the item, or obtain satisfaction of the requirement by its own employees or contractors. If the Government elects to take such action, the Government may deduct from rental payments its costs incurred in connection with taking the action. Alternatively, the Government may reduce the rent by an amount reasonably calculated to approximate the cost or value of the service not performed, item not provided, or requirement not satisfied, such reduction effective as of the date of the commencement of the default condition.

(3) Grounds for Termination. The Government may terminate the Lease if:

(i) The Lessor's default persists notwithstanding provision of notice and reasonable opportunity to cure by the Government, or

(ii) The Lessor fails to take such actions as are necessary to prevent the recurrence of default conditions,

and such conditions (i) or (ii) substantially impair the safe and healthful occupancy of the Premises, or render the Space unusable for its intended purposes.

(4) Excuse. Failure by the Lessor to timely deliver the Space or perform any service, provide any item, or satisfy any requirement of this Lease shall not be excused if its failure in performance arises from:

(i) Circumstances within the Lessor's control;

(ii) Circumstances about which the Lessor had actual or constructive knowledge prior to the Lease Award Date that could reasonably be expected to affect the Lessor's capability to perform, regardless of the Government's knowledge of such matters;

(iii) The condition of the Property;

(iv) The acts or omissions of the Lessor, its employees, agents or contractors; or

(v) The Lessor's inability to obtain sufficient financial resources to perform its obligations.

(5) The rights and remedies specified in this clause are in addition to any and all remedies to which the Government may be entitled as a matter of law.

11. 552.270-19 PROGRESSIVE OCCUPANCY (SEP 1999)

The Government shall have the right to elect to occupy the space in partial increments prior to the substantial completion of the entire leased premises, and the Lessor agrees to schedule its work so as to deliver the space incrementally as elected by the Government. The Government shall pay rent commencing with the first business day following substantial completion of the entire leased premise unless the Government has elected to occupy the leased premises incrementally. In case of incremental occupancy, the Government shall pay rent pro rata upon the first

LESSOR: SR GOVERNMENT: JTB

Exhibit G
GSA Lease No. GS-11P-LVA00543

business day following substantial completion of each incremental unit. Rental payments shall become due on the first workday of the month following the month in which an increment of space is substantially complete, except that should an increment of space be substantially completed after the fifteenth day of the month, the payment due date will be the first workday of the second month following the month in which it was substantially complete. The commencement date of the firm lease term will be a composite determined from all rent commencement dates.

12. MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT (APR 2015)

The Lessor shall maintain the Property, including the building, building systems, and all equipment, fixtures, and appurtenances furnished by the Lessor under this Lease, in good repair and tenantable condition so that they are suitable in appearance and capable of supplying such heat, air conditioning, light, ventilation, safety systems, access and other things to the premises, without reasonably preventable or recurring disruption, as is required for the Government's access to, occupancy, possession, use and enjoyment of the premises as provided in this lease. For the purpose of so maintaining the premises, the Lessor may at reasonable times enter the premises with the approval of the authorized Government representative in charge. Upon request of the Lease Contracting Officer (LCO), the Lessor shall provide written documentation that building systems have been properly maintained, tested, and are operational within manufacturer's warranted operating standards. The Lessor shall maintain the Premises in a safe and healthful condition according to applicable OSHA standards and all other requirements of this Lease, including standards governing indoor air quality, existence of mold and other biological hazards, presence of hazardous materials, etc. The Government shall have the right, at any time after the Lease Award Date and during the term of the Lease, to inspect all areas of the Property to which access is necessary for the purpose of determining the Lessor's compliance with this clause.

13. FIRE AND CASUALTY DAMAGE (JUN 2016)

If the building in which the Premises are located is totally destroyed or damaged by fire or other casualty, this Lease shall immediately terminate. If the building in which the Premises are located are only partially destroyed or damaged, so as to render the Premises untenable, or not usable for their intended purpose, the Lessor shall have the option to elect to repair and restore the Premises or terminate the Lease. The Lessor shall be permitted a reasonable amount of time, not to exceed **270 days** from the event of destruction or damage, to repair or restore the Premises, provided that the Lessor submits to the Government a reasonable schedule for repair of the Premises within **60 days** of the event of destruction or damage. If the Lessor fails to timely submit a reasonable schedule for completing the work, the Government may elect to terminate the Lease effective as of the date of the event of destruction or damage. If the Lessor elects to repair or restore the Premises, but fails to repair or restore the Premises within **270 days** from the event of destruction or damage, or fails to diligently pursue such repairs or restoration so as to render timely completion commercially impracticable, the Government may terminate the Lease effective as of the date of the destruction or damage. During the time that the Premises are unoccupied, rent shall be abated. Termination of the Lease by either party under this clause shall not give rise to liability for either party.

Nothing in this lease shall be construed as relieving Lessor from liability for damage to, or destruction of, property of the United States of America caused by the willful or negligent act or omission of Lessor.

14. COMPLIANCE WITH APPLICABLE LAW (JAN 2011)

Lessor shall comply with all Federal, state and local laws applicable to its ownership and leasing of the Property, including, without limitation, laws applicable to the construction, ownership, alteration or operation of all buildings, structures, and facilities located thereon, and obtain all necessary permits, licenses and similar items at its own expense. The Government will comply with all Federal, State and local laws applicable to and enforceable against it as a tenant under this lease, provided that nothing in this Lease shall be construed as a waiver of the sovereign immunity of the Government. This Lease shall be governed by Federal law.

15. 552.270-12 ALTERATIONS (SEP 1999)

The Government shall have the right during the existence of this lease to make alterations, attach fixtures, and erect structures or signs in or upon the premises hereby leased, which fixtures, additions or structures so placed in, on, upon, or attached to the said premises shall be and remain the property of the Government and may be removed or otherwise disposed of by the Government. If the lease contemplates that the Government is the sole occupant of the building, for

LESSOR: SR GOVERNMENT: JTB

Exhibit G
GSA Lease No. GS-11P-LVA00543

purposes of this clause, the leased premises include the land on which the building is sited and the building itself. Otherwise, the Government shall have the right to tie into or make any physical connection with any structure located on the property as is reasonably necessary for appropriate utilization of the leased space.

16. ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (APR 2015)

(a) Ten (10) working days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of building shell and TIs conforming to this Lease and the approved DIDs is substantially complete, and a Certificate of Occupancy has been issued as set forth below.

(b) The Space shall be considered substantially complete only if the Space may be used for its intended purpose and completion of remaining work will not unreasonably interfere with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punchlist generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.

(c) The Lessor shall provide a valid Certificate of Occupancy, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue Certificates of Occupancy or if the Certificate of Occupancy is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates that the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease to ensure an acceptable level of safety is provided. Under such circumstances, the Government shall only accept the Space without a Certificate of Occupancy if a licensed fire protection engineer determines that the offered space is compliant with all applicable local codes and ordinances and fire protection and life safety-related requirements of this Lease.

17. 552.270-33 SYSTEM FOR AWARD MANAGEMENT – LEASING (FEB 2020)

(a) Definitions. As used in this provision—

“Electronic Funds Transfer (EFT) indicator means a four-character suffix to the unique entity identifier. The suffix is assigned at the discretion of the commercial, nonprofit, or Government entity to establish additional System for Award Management records for identifying alternative EFT accounts (see [subpart 32.11](#)) for the same entity.

“Registered in the System for Award Management (SAM)” means that—

(1) The Offeror has entered all mandatory information, including the unique entity identifier and the EFT indicator, if applicable, the Commercial and Government Entity (CAGE) code, as well as data required by the Federal Funding Accountability and Transparency Act of 2006 (see [subpart 4.14](#)) into SAM

(2) The offeror has completed the Core, Assertions, and Representations and Certifications, and Points of Contact sections of the registration in SAM;

(3) The Government has validated all mandatory data fields, to include validation of the Taxpayer Identification Number (TIN) with the Internal Revenue Service (IRS). The offeror will be required to provide consent for TIN validation to the Government as a part of the SAM registration process; and

(4) The Government has marked the record “Active”.

“Unique entity identifier” means a number or other identifier used to identify a specific commercial, nonprofit, or Government entity. See www.sam.gov for the designated entity for establishing unique entity identifiers.

(b)

(1) An Offeror is required to be registered in SAM prior to award, and shall continue to be registered during performance, and through final payment of any contract, basic agreement, basic ordering agreement, or blanket purchasing agreement resulting from this solicitation.

(2) The Offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation “Unique Entity Identifier” followed by the unique entity identifier that identifies the Offeror's name and address exactly as stated in the offer. The Offeror also shall enter its EFT indicator, if applicable. The unique entity identifier will be used by the Contracting Officer to verify that the Offeror is registered in the SAM.

(c) If the Offeror does not have a unique entity identifier, it should contact the entity designated at www.sam.gov for establishment of the unique entity identifier directly to obtain one. The Offeror should be prepared to provide the following information:

(1) Company legal business name.

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

- (2) Tradestyle, doing business, or other name by which your entity is commonly recognized.
- (3) Company physical street address, city, state, and Zip Code.
- (4) Company mailing address, city, state and Zip Code (if separate from physical).
- (5) Company telephone number.
- (6) Date the company was started.
- (7) Number of employees at your location.
- (8) Chief executive officer/key manager.
- (9) Line of business (industry).
- (10) Company headquarters name and address (reporting relationship within your entity).

(d) If the Offeror does not become registered in the SAM database in the time prescribed by the Contracting Officer, the Contracting Officer will proceed to award to the next otherwise successful registered Offeror.

(e) Processing time should be taken into consideration when registering. Offerors who are not registered in SAM should consider applying for registration immediately upon receipt of this solicitation. See <https://www.sam.gov> for information on registration.

18. 52.204-13 SYSTEM FOR AWARD MANAGEMENT MAINTENANCE (OCT 2018)

This clause is incorporated by reference.

19. 552.270-31 PROMPT PAYMENT (JUN 2011)

The Government will make payments under the terms and conditions specified in this clause. Payment shall be considered as being made on the day a check is dated or an electronic funds transfer is made. All days referred to in this clause are calendar days, unless otherwise specified.

(a) *Payment due date—*

(1) *Rental payments.* Rent shall be paid monthly in arrears and will be due on the first workday of each month, and only as provided for by the lease.

(i) When the date for commencement of rent falls on the 15th day of the month or earlier, the initial monthly rental payment under this contract shall become due on the first workday of the month following the month in which the commencement of the rent is effective.

(ii) When the date for commencement of rent falls after the 15th day of the month, the initial monthly rental payment under this contract shall become due on the first workday of the second month following the month in which the commencement of the rent is effective.

(2) *Other payments.* The due date for making payments other than rent shall be the later of the following two events:

(i) The 30th day after the designated billing office has received a proper invoice from the Contractor.

(ii) The 30th day after Government acceptance of the work or service. However, if the designated billing office fails to annotate the invoice with the actual date of receipt, the invoice payment due date shall be deemed to be the 30th day after the Contractor's invoice is dated, provided a proper invoice is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(b) *Invoice and inspection requirements for payments other than rent.*

(1) The Contractor shall prepare and submit an invoice to the designated billing office after completion of the work. A proper invoice shall include the following items:

(i) Name and address of the Contractor.

LESSOR:

SR

GOVERNMENT:

JTB

Exhibit G
GSA Lease No. GS-11P-LVA00543

(ii) Invoice date.

(iii) Lease number.

(iv) Government's order number or other authorization.

(v) Description, price, and quantity of work or services delivered.

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the remittance address in the lease or the order).

(vii) Name (where practicable), title, phone number, and mailing address of person to be notified in the event of a defective invoice.

(2) The Government will inspect and determine the acceptability of the work performed or services delivered within seven days after the receipt of a proper invoice or notification of completion of the work or services unless a different period is specified at the time the order is placed. If actual acceptance occurs later, for the purpose of determining the payment due date and calculation of interest, acceptance will be deemed to occur on the last day of the seven day inspection period. If the work or service is rejected for failure to conform to the technical requirements of the contract, the seven days will be counted beginning with receipt of a new invoice or notification. In either case, the Contractor is not entitled to any payment or interest unless actual acceptance by the Government occurs.

(c) *Interest Penalty.*

(1) An interest penalty shall be paid automatically by the Government, without request from the Contractor, if payment is not made by the due date.

(2) The interest penalty shall be at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) that is in effect on the day after the due date. This rate is referred to as the "Renegotiation Board Interest Rate," and it is published in the **Federal Register** semiannually on or about January 1 and July 1. The interest penalty shall accrue daily on the payment amount approved by the Government and be compounded in 30-day increments inclusive from the first day after the due date through the payment date.

(3) Interest penalties will not continue to accrue after the filing of a claim for such penalties under the clause at 52.233-1, Disputes, or for more than one year. Interest penalties of less than \$1.00 need not be paid.

(4) Interest penalties are not required on payment delays due to disagreement between the Government and Contractor over the payment amount or other issues involving contract compliance or on amounts temporarily withheld or retained in accordance with the terms of the contract. Claims involving disputes, and any interest that may be payable, will be resolved in accordance with the clause at 52.233-1, Disputes.

(d) *Overpayments.* If the Lessor becomes aware of a duplicate payment or that the Government has otherwise overpaid on a payment, the Contractor shall—

(1) Return the overpayment amount to the payment office cited in the contract along with a description of the overpayment including the—

(i) Circumstances of the overpayment (e.g., duplicate payment, erroneous payment, liquidation errors, date(s) of overpayment);

(ii) Affected lease number; (iii) Affected lease line item or sub-line item, if applicable; and

(iii) Lessor point of contact.

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

- (2) Provide a copy of the remittance and supporting documentation to the Contracting Officer.

20. 52.232-23 ASSIGNMENT OF CLAIMS (MAY 2014)

(Applicable to leases over the micro-purchase threshold.)

(a) The Contractor, under the Assignment of Claims Act, as amended, [31 U.S.C. 3727](#), [41 U.S.C. 6305](#) (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

21. PAYMENT (MAY 2011)

(a) When space is offered and accepted, the amount of American National Standards Institute/Building Owners and Managers Association Office Area (ABOA) square footage delivered will be confirmed by:

(1) The Government's measurement of plans submitted by the successful Offeror as approved by the Government, and an inspection of the space to verify that the delivered space is in conformance with such plans or

(2) A mutual on-site measurement of the space, if the Contracting Officer determines that it is necessary.

(b) Payment will not be made for space which is in excess of the amount of ABOA square footage stated in the lease.

(c) If it is determined that the amount of ABOA square footage actually delivered is less than the amount agreed to in the lease, the lease will be modified to reflect the amount of ABOA space delivered and the annual rental will be adjusted as follows:

ABOA square feet not delivered multiplied by one plus the common area factor (CAF), multiplied by the rate per rentable square foot (RSF). That is: $(1+CAF) \times \text{Rate per RSF} = \text{Reduction in Annual Rent}$

22. 52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT (OCT 2018)

This clause is incorporated by reference.

23. 52.203-13 CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT (JUN 2020)

(Applicable to leases over \$5.5 million total contract value and performance period is 120 days or more.)

This clause is incorporated by reference.

24. 552.270-32 COVENANT AGAINST CONTINGENT FEES (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover the full amount of the contingent fee.

(b) *Bona fide agency*, as used in this clause, means an established commercial or selling agency (including licensed real estate agents or brokers), maintained by a Contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

(1) *Bona fide employee*, as used in this clause, means a person, employed by a Contractor and subject to the Contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

(2) *Contingent fee*, as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

(3) *Improper influence*, as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

25. 52.203-7 ANTI-KICKBACK PROCEDURES (JUN 2020)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

This clause is incorporated by reference.

26. 52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(Applicable to leases over the Simplified Lease Acquisition Threshold, as well as to leases of any value awarded to an individual.)

This clause is incorporated by reference.

27. 52.203-14 DISPLAY OF HOTLINE POSTER(S) (JUN 2020)

(Applicable to leases over \$5.5 Million total contract value and performance period is 120 days or more.)

(a) *Definition.*

United States, as used in this clause, means the 50 States, the District of Columbia, and outlying areas.

(b) *Display of fraud hotline poster(s).* Except as provided in paragraph (c)—

(1) During contract performance in the United States, the Contractor shall prominently display in common work areas within business segments performing work under this contract and at contract work sites—

(i) Any agency fraud hotline poster or Department of Homeland Security (DHS) fraud hotline poster identified in paragraph (b)(3) of this clause; and

(ii) Any DHS fraud hotline poster subsequently identified by the Contracting Officer.

(2) Additionally, if the Contractor maintains a company website as a method of providing information to employees, the Contractor shall display an electronic version of the poster(s) at the website.

(3) Any required posters may be obtained as follows:

LESSOR:

SR

GOVERNMENT:

JTB

Exhibit G
GSA Lease No. GS-11P-LVA00543

Poster(s)	Obtain from

(Contracting Officer shall insert—

(i) Appropriate agency name(s) and/or title of applicable Department of Homeland Security fraud hotline poster); and

(ii) The website(s) or other contact information for obtaining the poster(s).)

(c) If the Contractor has implemented a business ethics and conduct awareness program, including a reporting mechanism, such as a hotline poster, then the Contractor need not display any agency fraud hotline posters as required in paragraph (b) of this clause, other than any required DHS posters.

(d) *Subcontracts.* The Contractor shall include the substance of this clause, including this paragraph (d), in all subcontracts that exceed the threshold specified in Federal Acquisition Regulation [3.1004](#)(b)(1) on the date of subcontract award, except when the subcontract—

(1) Is for the acquisition of a commercial item; or

(2) Is performed entirely outside the United States.

28. 552.270-30 PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

(a) If the head of the contracting activity (HCA) or his or her designee determines that there was a violation of subsection 27(a) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in the Federal Acquisition Regulation, the Government, at its election, may—

(1) Reduce the monthly rental under this lease by five percent of the amount of the rental for each month of the remaining term of the lease, including any option periods, and recover five percent of the rental already paid;

(2) Reduce payments for alterations not included in monthly rental payments by five percent of the amount of the alterations agreement; or

(3) Reduce the payments for violations by a Lessor's subcontractor by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was placed.

(b) Prior to making a determination as set forth above, the HCA or designee shall provide to the Lessor a written notice of the action being considered and the basis thereof. The Lessor shall have a period determined by the agency head or designee, but not less than 30 calendar days after receipt of such notice, to submit in person, in writing, or through a representative, information and argument in opposition to the proposed reduction. The agency head or designee may, upon good cause shown, determine to deduct less than the above amounts from payments.

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this lease.

29. 52.215-10 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA (AUG 2011)

(Applicable when cost or pricing data are required for work or services over \$750,000.)
This clause is incorporated by reference.

30. 552.270-13 PROPOSALS FOR ADJUSTMENT (OCT 2016)

This clause is incorporated by reference.

31. CHANGES (MAR 2013)

(a) The LCO may at any time, by written order, direct changes to the Tenant Improvements within the Space, Building Security Requirements, or the services required under the Lease.

(b) If any such change causes an increase or decrease in Lessor's costs or time required for performance of its obligations under this Lease, whether or not changed by the order, the Lessor shall be entitled to an amendment to the Lease providing for one or more of the following:

- (1) An adjustment of the delivery date;
- (2) An equitable adjustment in the rental rate;
- (3) A lump sum equitable adjustment; or
- (4) A change to the operating cost base, if applicable.

(c) The Lessor shall assert its right to an amendment under this clause within 30 days from the date of receipt of the change order and shall submit a proposal for adjustment. Failure to agree to any adjustment shall be a dispute under the Disputes clause. However, the pendency of an adjustment or existence of a dispute shall not excuse the Lessor from proceeding with the change as directed.

(d) Absent a written change order from the LCO, or from a Government official to whom the LCO has explicitly and in writing delegated the authority to direct changes, the Government shall not be liable to Lessor under this clause.

32. 552.215-70 EXAMINATION OF RECORDS BY GSA (JUL 2016)

This clause is incorporated by reference.

33. 52.215-2 AUDIT AND RECORDS—NEGOTIATION (JUN 2020)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)
This clause is incorporated by reference.

34. 52.233-1 DISPUTES (MAY 2014)

This clause is incorporated by reference.

35. 52.222-26 EQUAL OPPORTUNITY (SEP 2016)

This clause is incorporated by reference.

36. 52.222-21 PROHIBITION OF SEGREGATED FACILITIES (APR 2015)

This clause is incorporated by reference.

LESSOR:



GOVERNMENT:



37. 52.219-28 POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION (MAY 2020)

(Applicable to leases exceeding the micro-purchase threshold.)

*This clause is incorporated by reference.***38. 52.222-35 EQUAL OPPORTUNITY FOR VETERANS (JUN 2020)**

(Applicable to leases \$150,000 or more, total contract value.)

(a) *Definitions.* As used in this clause-

"Active duty wartime or campaign badge veteran," "Armed Forces service medal veteran," "disabled veteran," "protected veteran," "qualified disabled veteran," and "recently separated veteran" have the meanings given at Federal Acquisition Regulation (FAR) [22.1301](#).

(b) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-300.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified protected veterans, and requires affirmative action by the Contractor to employ and advance in employment qualified protected veterans.

(c) Subcontracts. The Contractor shall insert the terms of this clause in subcontracts valued at or above the threshold specified in FAR [22.1303](#)(a) on the date of subcontract award, unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

39. 52.222-36 EQUAL OPPORTUNITY FOR WORKERS WITH DISABILITIES (JUN 2020)

(Applicable to leases over \$15,000 total contract value.)

(a) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-741.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified individuals on the basis of disability, and requires affirmative action by the Contractor to employ and advance in employment qualified individuals with disabilities.

(b) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of the threshold specified in Federal Acquisition Regulation (FAR) [22.1408](#)(a) on the date of subcontract award, unless exempted by rules, regulations, or orders of the Secretary, so that such provisions will be binding upon each subcontractor or vendor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs of the U.S. Department of Labor, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

40. 52.222-37 EMPLOYMENT REPORTS ON VETERANS (JUN 2020)

(Applicable to leases \$150,000 or more, total contract value.)

*This clause is incorporated by reference.***41. 52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JUN 2020)**

(Applicable to leases over \$35,000 total contract value.)

*This clause is incorporated by reference.***42. 52.215-12 SUBCONTRACTOR CERTIFIED COST OR PRICING DATA (JUN 2020)**

(Applicable if over \$750,000 total contract value.)

This clause is incorporated by reference.

LESSOR:



GOVERNMENT:



43. 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2018)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)
This clause is incorporated by reference.

44. 52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (JUN 2020) ALTERNATE III (JUN 2020)

(Applicable to leases over \$700,000 total contract value.)
This clause is incorporated by reference.

45. 52.219-16 LIQUIDATED DAMAGES—SUBCONTRACTING PLAN (JAN 1999)

(Applicable to leases over \$700,000 total contract value.)
This clause is incorporated by reference.

46. 52.204-10 REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS (JUN 2020)

(Applicable if over \$30,000 total contract value.)
This clause is incorporated by reference.

47. 52.204-25 PROHIBITION ON CONTRACTING FOR CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT (AUG 2020)

(a) *Definitions.* As used in this clause—

Backhaul means intermediate links between the core network, or backbone network, and the small subnetworks at the edge of the network (e.g., connecting cell phones/towers to the core telephone network). Backhaul can be wireless (e.g., microwave) or wired (e.g., fiber optic, coaxial cable, Ethernet).

Covered foreign country means The People's Republic of China.

Covered telecommunications equipment or services means—

(1) Telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities);

(2) For the purpose of public safety, security of Government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities);

(3) Telecommunications or video surveillance services provided by such entities or using such equipment; or

(4) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country.

Critical technology means—

(1) Defense articles or defense services included on the United States Munitions List set forth in the International Traffic in Arms Regulations under subchapter M of chapter I of title 22, Code of Federal Regulations;

(2) Items included on the Commerce Control List set forth in Supplement No. 1 to part 774 of the Export Administration Regulations under subchapter C of chapter VII of title 15, Code of Federal Regulations, and controlled-

(i) Pursuant to multilateral regimes, including for reasons relating to national security, chemical and biological weapons proliferation, nuclear nonproliferation, or missile technology; or

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

(ii) For reasons relating to regional stability or surreptitious listening;

(3) Specially designed and prepared nuclear equipment, parts and components, materials, software, and technology covered by part 810 of title 10, Code of Federal Regulations (relating to assistance to foreign atomic energy activities);

(4) Nuclear facilities, equipment, and material covered by part 110 of title 10, Code of Federal Regulations (relating to export and import of nuclear equipment and material);

(5) Select agents and toxins covered by part 331 of title 7, Code of Federal Regulations, part 121 of title 9 of such Code, or part 73 of title 42 of such Code; or

(6) Emerging and foundational technologies controlled pursuant to section 1758 of the Export Control Reform Act of 2018 (50 U.S.C. 4817).

Interconnection arrangements means arrangements governing the physical connection of two or more networks to allow the use of another's network to hand off traffic where it is ultimately delivered (e.g., connection of a customer of telephone provider A to a customer of telephone company B) or sharing data and other information resources.

Reasonable inquiry means an inquiry designed to uncover any information in the entity's possession about the identity of the producer or provider of covered telecommunications equipment or services used by the entity that excludes the need to include an internal or third-party audit.

Roaming means cellular communications services (e.g., voice, video, data) received from a visited network when unable to connect to the facilities of the home network either because signal coverage is too weak or because traffic is too high.

Substantial or essential component means any component necessary for the proper function or performance of a piece of equipment, system, or service.

(b) *Prohibition.* (1) Section 889(a)(1)(A) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2019, from procuring or obtaining, or extending or renewing a contract to procure or obtain, any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. The Contractor is prohibited from providing to the Government any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless an exception at paragraph (c) of this clause applies or the covered telecommunication equipment or services are covered by a waiver described in FAR [4.2104](#).

(2) Section 889(a)(1)(B) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2020, from entering into a contract, or extending or renewing a contract, with an entity that uses any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless an exception at paragraph (c) of this clause applies or the covered telecommunication equipment or services are covered by a waiver described in FAR 4.2104. This prohibition applies to the use of covered telecommunications equipment or services, regardless of whether that use is in performance of work under a Federal contract.

(c) *Exceptions.* This clause does not prohibit contractors from providing—

(1) A service that connects to the facilities of a third-party, such as backhaul, roaming, or interconnection arrangements; or

LESSOR:



GOVERNMENT:



Exhibit G
GSA Lease No. GS-11P-LVA00543

(2) Telecommunications equipment that cannot route or redirect user data traffic or permit visibility into any user data or packets that such equipment transmits or otherwise handles.

(d) Reporting requirement. (1) In the event the Contractor identifies covered telecommunications equipment or services used as a substantial or essential component of any system, or as critical technology as part of any system, during contract performance, or the Contractor is notified of such by a subcontractor at any tier or by any other source, the Contractor shall report the information in paragraph (d)(2) of this clause to the Contracting Officer, unless elsewhere in this contract are established procedures for reporting the information; in the case of the Department of Defense, the Contractor shall report to the website at <https://dibnet.dod.mil>. For indefinite delivery contracts, the Contractor shall report to the Contracting Officer for the indefinite delivery contract and the Contracting Officer(s) for any affected order or, in the case of the Department of Defense, identify both the indefinite delivery contract and any affected orders in the report provided at <https://dibnet.dod.mil>.

(2) The Contractor shall report the following information pursuant to paragraph (d)(1) of this clause

(i) Within one business day from the date of such identification or notification: the contract number; the order number(s), if applicable; supplier name; supplier unique entity identifier (if known); supplier Commercial and Government Entity (CAGE) code (if known); brand; model number (original equipment manufacturer number, manufacturer part number, or wholesaler number); item description; and any readily available information about mitigation actions undertaken or recommended.

(ii) Within 10 business days of submitting the information in paragraph (d)(2)(i) of this clause: any further available information about mitigation actions undertaken or recommended. In addition, the Contractor shall describe the efforts it undertook to prevent use or submission of covered telecommunications equipment or services, and any additional efforts that will be incorporated to prevent future use or submission of covered telecommunications equipment or services.

(e) *Subcontracts*. The Contractor shall insert the substance of this clause, including this paragraph (e) and excluding paragraph (b)(2), in all subcontracts and other contractual instruments, including subcontracts for the acquisition of commercial items.

48. 52.204-19 INCORPORATION BY REFERENCE OF REPRESENTATIONS AND CERTIFICATIONS (DEC 2014).

This clause is incorporated by reference.

LESSOR:

SR

GOVERNMENT:

JTB

Exhibit H
GSA Lease No. GS-11P-LVA00543

Shell and Tenant Improvements (to be Approved by DEA)

Shell Improvements

1. Increased parking capacity, as outlined in Exhibit C to the Lease
2. HVAC improvements-SAC office, balancing, upgrades, etc.
3. Replace remaining RTU's
4. Roof replacement
5. Replace parking lot lighting with environmentally friendly, energy efficient fixtures
6. Power wash/polish aluminum façade panels
7. Landscaping-upgraded plantings and improved service
8. Add supplemental cooling to lease
9. Provide full time onsite building engineer coverage (including when Douglas is on leave, etc.). The Government will pay for the engineer via a separate agreement.
10. Total bathroom renovation at all (9) restrooms including automatic faucets, hand dryers, water closets, millwork, flooring, wall finishes, etc.
11. Total locker room renovation at both M & W including showers, lockers, fixtures, millwork, flooring, and wall finishes, etc.
12. Replace 2x4 fluorescent fixtures with LED fixtures
13. Replace ceiling tile & grid
14. Add ADA power assisted door to the main restrooms on 1st and 2nd floors
15. Parking lot resurfacing where necessary; resealing every 2-3 years with restriping
16. Replace VCT flooring in main corridor.

Tenant Improvements (subject to change as directed by the Government)

1. Replace generator, fueled by natural gas and increase capacity
2. Increase electrical capacity
3. Add Suite 2100 & supplemental cooling systems at server rooms MDF/IDF 1006/1007, STIG 1106, UPS 1401A, and STS 2101 to UPS
4. Upgrade drywall partitions at all private offices and conference rooms to meet current DEA standards
5. Increase storage capacity at warehouses
6. Renovate main lobby and increase size
7. Remodel conference rooms and multi-purpose room
8. Upgrade elevator lobbies
9. Renovate guard shack-A/V, fixtures, millwork
10. Total breakroom renovation at all (6) breakrooms including appliances (commercial refrigerator w/ icemaker, microwaves & garbage disposal), millwork, flooring, wall finishes, etc.
11. Replace VCT flooring at Training Classroom
12. Replace building standard carpet tile with product suitable for lab/warehouse operations; add contrasting border in executive area

Initials:  & 
LESSOR & GOV'T

Exhibit H
GSA Lease No. GS-11P-LVA00543

13. Paint refresh throughout
14. Dedicated picnic table area with appropriate hardscape with shade from sun and rain
15. Replace all perimeter entrances with ADA power assisted doors

Building-Specific Amortized Capital (subject to change as directed by the Government)

1. Replace bullet-resistant glass at guard shack
2. Upgrade card access system
3. Upgrade security system
4. Keying-Perimeter doors as well as sensitive doors require re-keying. A key hierarchy and door schedule will be developed by the DSO and ISP to facilitate re-keying of the designated doors
5. Install Pedestrian gate
6. Replace property fence with anti-climb fence meeting the following specifications:
 - No less than 8' high, as measured from accessible grades or footholds and shall be supplied and installed along the perimeter.
 - Gates of heavy- duty commercial/industrial manufacture shall be integrated into the fence at a minimum of one (1) point of entry and designed for high frequency use.
 - The gate-operating mechanisms shall be heavy-duty and equipped with manual bypass and safety sensors. Gates shall be automatic with manual override in driveway at exit door for exiting purposes. Upon entry, gates shall close automatically behind the vehicle. Access control shall be exercised via a proximity card reader system, which is compatible /interchangeable with elevator, building and special area access controls and installed on mounting posts.
 - DEA reserves the right to approve/amend the offered fencing materials.

Initials:  & 
LESSOR GOV'T

ESIGN DISCLOSURES AND CONSENT

It is required by law to provide you with certain disclosures and information about the products, services or accounts you may receive or access in connection with your relationship with us ('Required Information'). With your consent, we can deliver Required Information to you by a) displaying or delivering the Required Information electronically; and b) requesting that you print or download the Required Information and retain it for your records.

This notice contains important information that you are entitled to receive before you consent to electronic delivery of Required Information. Your consent also permits the general use of electronic records and electronic signatures in connection with the Required Information.

After you have read this information, if you agree to receive Required Information from us electronically, and if you agree to the general use of electronic records and electronic signatures in connection with our relationship, please click the 'I ACCEPT' button below.

Statement of electronic disclosures:

You may request to receive Required Information on paper, but if you do not consent to electronic delivery of Required Information, we cannot proceed with the acceptance and processing to create a relationship with you in connection to the products, services or account.

If you consent to electronic delivery of Required Information, you may withdraw that consent at any time. However, if you withdraw your consent we will not be able to continue processing to create a relationship with you in connection to the products, services or account.

If you consent to electronic disclosures, that consent applies to all Required Information we give you or receive from you in connection with our relationship and the associated notices, disclosures, and other documents.

You agree to print out or download Required Information when we advise you to do so and keep it for your records. If you are unable to print or download any Required Information, you may call us and request paper copies. If you need to update your e-mail address or other contact information with us, you may do so by calling us and requesting the necessary updates.

If you wish to withdraw your consent to electronic disclosures, you may do so by calling us and requesting withdrawal of consent. After consenting to receive and deliver Required Information electronically, you may request a paper copy of the Required Information by calling us.

If you do not have the required software and/or hardware, or if you do not wish to use electronic records and signatures for any other reason, you can request paper copies of the Required Information to be sent to you by calling us.

Your consent does not mean that we must provide the Required Information electronically. We may to, at our option, deliver Required Information on paper. We may also require that certain communications from you be delivered to us on paper at a specified address.

I have read the information about the use of electronic records, disclosures, notices, and e-mail, and consent to the use of electronic records for the delivery of Required Information in connection with our relationship. I have been able to view this information using my computer and software. I have an account with an internet service provider, and I am able to send e-mail and receive e-mail with hyperlinks to websites and attached files. I also consent to the use of electronic records and electronic signatures in place of written documents and handwritten signatures.